State of Tennessee Regional Water Supply Planning Pilot Study

02 August 2010

Benjamin L. Rohrbach, P.E. Chief, Hydrology and Hydraulics U.S. Army Corps of Engineers Nashville District



US Army Corps of Engineers
BUILDING STRONG®



Presentation Outline

- Ongoing Activities
- Regional Need Statements
- Alternatives Under Consideration
- Projected Demand vs. Existing Yield
- OASIS Modeling of Systems Reliability
- Questions and Comments



Ongoing Activities

- Data gathering completed to support:
 - ► Phase II Study Activities
 - Financial Strength of Regional Utility Systems
 - Utility Interconnection Capacity Evaluation
 - OASIS Model Development and Calibration

Performing:

- ► Phase III Study Activities
 - Preliminary Design of Alternative Water Sources
 - Preliminary Yield of Alternative Water Sources
 - Cost Estimates
 - Alternative Screening Protocol and Decision Matrix



Regional Need Statements North Central Tennessee Pilot Area

- The principle water source for North Central Tennessee is Old Hickory Lake. Raw water withdrawn by White House and Gallatin Utilities satisfies approximately 90% of the existing demand in the pilot area region.
- The overall raw water demand for the North Central Tennessee pilot area is projected to increase from approximately 19 MGD to 28 MGD by 2030. Currently there is sufficient raw water to meet this demand and there are no physical limitations on finished water production for meeting mean day use. It should be noted that a charge for withdrawals from Old Hickory Lake may be instituted at some point in the future and could impact water rates across the region.
- The City of Portland satisfies its raw water demand through withdrawals from small surface water sources, and its average annual demand of approximately 2.3 MGD exceeds the firm yield of its sources. Portland purchases finished water from neighboring utilities on an as needed basis, but with no formal contracts for this outside supply, security for the system is not provided.



Regional Need Statements Southern Cumberland Plateau Pilot Area

- The current raw water supply in the region was perceived as barely sufficient during the recent drought. The hardest hit utility, Monteagle, managed the drought by purchasing finished water through connections to Sewanee and Tracy City, and by establishing several emergency raw water sources.
- Overall raw water demand in the region is expected to grow only slightly, from approximately 2.39 MGD to 2.53 MGD, by the year 2030. Demand projections for Big Creek and Sewanee Utility Districts are well below the firm yields of their existing raw water sources. Existing and projected raw water demands for Monteagle and Tracy City, however, are currently greater than the firm yield of their primary sources. The composite firm yield of the region's existing raw water sources is barely sufficient to meet existing demand, indicating a need for additional source development.
- Interconnections between the utilities are well established, with existing formal contracts between Tracy City and Big Creek, as well as Tracy City and Monteagle. The utilities must maintain and improve this ability to share water among themselves. This is paramount to each utility's ability to meet demand during droughts, as the small drainage areas of the South Cumberland Plateau's water sources leaves them particularly vulnerable.

North Central Tennessee Pilot Area

- Optimizing Water Sharing between Utilities
- Evaluation Utilizes OASIS
 - Existing Interconnections
 - Improved Interconnections

			Contract										Flow Records	
			Max (gal per		Min Pressure			TIP.	Ji		-7			Max Day (avg
Contract	Seller	Buyer	month or MGD)	month)	(psi)		Max flow (gpm)	Date Enacted		Expires	Rates \$/kgal		Maximum Month	dayx1.25)
Yes	GPU	Westmoreland	15 MG per month	750,000		20			6/1/1978	6/1/2018	\$	4.92	17,933,385	747,000
No	GPU	White House	1 MGD daily avg								\$	3.34	7,439,293	1,497,000
Yes	GPU	CSBWUD	1.5 MGD				1043		3/8/2007	3/8/2017	\$	3.18	34,093,000	1,377,000
No	WHUD	Portland	-	-							No contract		14,369,500	599,000
No	Westmoreland	Portland									No contract			
No	Westmoreland	CSBWUD									No contract		3,540,200	147,508



North Central Tennessee Pilot Area

- Portland's Caney Fork Creek Project
 - Earthen Embankment/Roller Compacted Concrete Dam
 - Preliminary Expected Project Yield 2.08 MGD
 - Total Source Firm Yield 3.20 MGD
 - Expected Release Requirement:
 - 1.73 cfs (@ .1 cfsm)
 - . 1.12 MGD



Southern Cumberland Plateau Pilot Area

- Optimizing Water Sharing between Utilities
- Evaluation Utilizes OASIS
 - Existing Interconnections
 - Improved Interconnections

						Contract In	forma	ation	Rates	Flow Record		
			Max (gal per			Min						Max gpd (avg
Contract	Seller	Buyer	month)		Max flow (gpd)	Pressure	Dat	te Enacted	Expires	Rates (\$/kgal)	Maximum Month	dayx1.25)
Yes	BCUD	TCPU		3000000			50	9/21/2009	1 yr after first delivery	\$4.05	3,165,000	105,500
No	SUD	Monteagl	e								951,000	126,600
										\$1.19 (with > 5 days notice)		
Yes	TCPU	Monteagl		1750000	250000			9/20/1999		\$2.70 (< 5 days notice & use > 50 kgpd)	6,054,000	235,000
No	TCPU	BCUD						fit			34,546,400	1,341,600



Southern Cumberland Plateau Pilot Area

New Reservoir on Big Creek

- Earthen Embankment Dam
- Preliminary Expected Project Yield 6.11 MGD
- Total Source Firm Yield 7.43 MGD
- Expected Release Requirement :
 - 2.05 cfs (@ .1 cfsm)
 - 1.32 MGD

Purchase of Ramsey Lake

- Convert Existing Lake to Water Supply Source
- Preliminary Expected Project Yield .58 MGD
- Total Source Firm Yield .67 MGD
- Expected Release Requirement :
 - .29 cfs (@ .1 cfsm)
 - .09 MGD




Southern Cumberland Plateau Pilot Area

- Raise Big Fiery Gizzard Lake
 - Existing Dam Raised 7 feet
 - Preliminary Expected Yield after Project .64 MGD
 - Total Source Firm Yield 1.28 MGD
 - Expected Release Requirement :
 - 1.0 cfs by Permit
 - With 2.2 square mile watershed @ .1 cfsm .2 cfs = .13 MGD
- Pipeline to Watts Bar Lake (South Pittsburgh)
 - 220,000 feet of transmission line to Monteagle In 3 Phases
 - Preliminary Expected Project Yield
 - .6 MGD Phase I
 - 3.0 MGD Phase II
 - Extend Services Phase III



Portland, TN


- Current Portland average demand is 2.29 MGD
- ► In the period of record, the maximum number of days, in one year, the demand was not met is ~90
- ► In any given year:
 - ▶ 2%, ~87 days
 - ▶ 5%, ~60 days
 - ▶ 10%, ~45 days
 - ▶ 20%, ~37 days





Portland, TN


- Current Portland average demand is 2.29 MGD
- ► The estimated firm yield of City Lake is .417 MGD
- OASIS utilized to provide a more completed evaluation of the risk to, and reliability of, Portland's system





Sewanee, TN


- Current Sewanee average demand is .297 MGD
- ► The combined firm yield of multiple sources is estimated as .498 MGD
- On an individual basis, Sewanee UD possesses adequate source water and treatment capacity
- Wastewater discharge limiting factor





Monteagle, TN


- Current Monteagle average demand is
 .552 MGD
- ► The firm yield of primary and secondary sources estimated as .468 MGD
- Projected demand through the study period is estimated to be decreasing
- Monteagle impacted most dramatically during recent drought





Tracy City, TN


- Current Tracy City average demand is .699 MGD
- The firm yield of Big Fiery Gizzard lake estimated as .347 MGD
- .65 MGD release required by permit for minimum flow downstream
- ▶ .13 MGD @ .1 cfsm





Big Creek Utility District


- Current Big Creek
 Utility District average
 demand is .864 MGD
- ► The firm yield of Ranger Lake estimated as 1.093 MGD
- On an individual basis,
 Big Creek UD
 possesses adequate
 source water and
 treatment capacity





Southern Cumberland Plateau Region

- Existing average demand for the region is 2.394 MGD, projected to reach 2.523 MGD by 2030
- ► The combined firm yield of sources in the region has been estimated as 2.406 MGD
- As a region, there is a demonstrated need for additional water





OASIS Modeling of Systems Reliability

- Optimize Yield of Existing Sources
- Evaluate Reliability of Existing Systems
 - Establish Reliability Objectives
- Scenarios
 - Base Case 2030 Demands
 - Evaluate Drought Plans Locally
 - Evaluate Regional Cooperation Water Sharing
 - Regional Cooperation with Local Drought Plans
 - Regional Cooperation with Regional Drought Plans
- Summary and Next Steps

