Work Order (Bid Form)

Knoxville/Knox County Community Action Committee

WORK ORDER INFORMATION

Work Order Name: WO/80008KN0709/1
Work Order Type: Weatherization
Audit Name: 80008KN0709-Audit

CLIENT INFORMATION

Client Name:
Client ID: 80008KN0709
Alt. Client ID: Knox

Address:
,

AGENCY INFORMATION

Agency: Knoxville/Knox County CAC
Address: P.O.Box 51650
Knoxville, TN 37950-1650

Agency Phone: (865) 244-3080
Fax: (865) 544-1647
Email Address: jason.estes@cachousing.org

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

•Single Family Dwelling
Contractor to follow 2006 International Residential Code as adopted by the City of Knoxville or Knox County as applicable.
City
House built in 1955
An EPA Certified Firm/Renovator is required.

Measures

Measure 1 **DWH Pipe Insulation** ***Components*** ***Inspected***

Comment

#	Material / Labor	Description / Comment	Units	Estimated Qty	Estimated Unit Cost	Estimated Total	Actual Qty	Actual Unit Cost	Actual Total
1	Insulation	DHW Pipe Insulation Includes labor cost. All corners must be cut properly. Refer to Appendix A- Standards for Weatherization Materials and Southeast Field Guide.	Each	1					
2	Labor	DHW Pipe Insulation	Each	1					

Other Detail

Measure Sub Total: ***Sub Total:***

Field Notes:

Measure 2 DWH Tank Insulation

Components

Inspected

Comment extend pressure rlief pipe as needed.

#	Material / Labor	Description / Comment	Units	Estimated Qty	Estimated Unit Cost	Estimated Total	Actual Qty	Actual Unit Cost	Actual Total
1	Hot Water Equipm	DHW Tank Insulation	Each	1					
		Includes labor cost. R-10 minimum. Refer to Appendix A- Standards for Weatherization Materials and Southeast Field Guide.							
2	Labor	DHW Tank Insulation	Each	1					

Other Detail

Measure Sub Total: ***Sub Total:***

Field Notes:

Measure 3 **Storm Windows** **Components** W2 **Inspected**

Comment •Includes labor and material. Refer to House diagram for estimated measurements. Responsibility of contractor to verify measurements in the field before ordering window(s). Contractor to include the thermal break, caulking, framing, and any other related items to convey a completed measure.

				Estimated			Actual		
#	Material / Labor	Description / Comment	Units	Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Windows	Storm Window Includes labor and material. Refer to House diagram for estimated measurements. Responsibility of contractor to verify measurements in the field before ordering window(s). Contractor must follow all egress codes if applicable. Contractor to include the thermal break, caulking, framing, and any other related items to convey a completed measure.	Each	1					
2	Labor	Storm Window	Each	1					

Other Detail

Measure Sub Total: **Sub Total:**

Field Notes:

Measure 4 **Smart Thermostat** **Components** **Inspected**

Comment Install thermostat. Must be equal to Honeywell's PRO 4000 Programmable Thermostat (must submit equivalent to Housing Director for approval) . Must educate client on operation of thermostat.

#	Material / Labor	Description / Comment	Units	Estimated Qty	Estimated Unit Cost	Estimated Total	Actual Qty	Actual Unit Cost	Actual Total
1	Heating Equipmen	Smart Thermostat	Each	1					
		Includes labor cost. Must be equal to Honeywell's PRO 4000 Programmable Thermostat. Must be installed by a qualified technician. Must train homeowner on operation of thermostat. Refer to Appendix A- Standards for Weatherization Materials and South East Field Guide.							
2	Labor	Smart Thermostat	Each	1					

Other Detail

Measure Sub Total: **Sub Total:**

Field Notes:

Measure 5 **CO Monitor is Needed** **Components** **Inspected**

Comment Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.

#	Material / Labor	Description / Comment	Units	Estimated Qty	Estimated Unit Cost	Estimated Total	Actual Qty	Actual Unit Cost	Actual Total
1	Health and Safety	CO monitor Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.	Each	1					
2	Labor	Labor	Each	1					

Other Detail

Measure Sub Total: **Sub Total:**

Field Notes:

Measure 6 **Fix Improper Venting (Clothes Dryer)** ***Components*** ***Inspected***

Comment Dryer Vents installed with damper. Metal pipe installed without any fastners protruding through pipe. Must be vented to outside of home. Maximum length is 15 feet. No changes allowed. Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.

				Estimated			Actual		
#	Material / Labor	Description / Comment	Units	Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	Dryer Vent w/ Metal Piping (upto 15' in length) Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.	Each	1					
2	Labor	Labor	Each	1					

Other Detail

Measure Sub Total: ***Sub Total:***

Field Notes:

Work Order Grand Total: ***Grand Total:***