



Work Order (Bid Form)

WORK ORDER INFORMATION

Work Order Name: WO/15015SE-4158/1

Work Order Type: Weatherization

Audit Name: NA

CLIENT INFORMATION

Client Name:

Address:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

AGENCY INFORMATION

Agency: Southeast Tennessee Human Resource Agency

Agency Phone: (423) 949-2191

Address: 312 Resource Rd.

Fax: (423) 949-4023

Dunlap, TN 37327

Email Address: aramsey@sethira.us

Agency Contact: Gaskins, Glenn

Work Phone:

Cell Phone: (865) 679-8303

Email Address: amerispechome20@bellsouth.net

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

Site Built

Home was built before 1978 per client. EPA RRP lead protocol may apply if home meets steps of WAP ARRA 10-20.

Client Name:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

Work Order (Bid Form)

Work Order Name: WO/15015SE-4158/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 1 of 6

Measures

Measure 1 CO Monitor is Needed

Components

Inspected

Comment Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	CO monitor Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:

Sub Total:

Field Notes:

Measure 2 Install Downtube at Water Heater PRV

Components

Inspected

Comment Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
10	Unspecified	Misc Material	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:

Sub Total:

Field Notes:

Client Name:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

Work Order (Bid Form)

Work Order Name: WO/15015SE-4158/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 2 of 6

Measure 3 Infiltration Redctn**Components****Inspected**

Comment Home is leaky with board and batten siding and plank flooring. Air sealing will be difficult.

☐

1. Small area of unenclosed wall in bathroom at end of bathtub. Enclose and seal.
2. Air infiltration at wall seams in bath at OSB. Seal.
3. Air infiltration at bathroom cased opening. Seal.
4. Block and seal at Window AC units. Rigid blocking recommended.
5. Rehang and adjust door to unheated side room. Weatherstrip and add door sweep.
6. Weatherstrip front entry door and add threshold. Some fabrication and adjustment needed.
7. Replace broken window panes at wdw #8 & #2.

#	Material / Labor	Description / Comment	Units	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
10	Miscellaneous Su	Infiltration Reduction	Each	1					

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total: **Sub Total:** **Field Notes:**

Client Name:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

Work Order (Bid Form)

Work Order Name: WO/15015SE-4158/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 3 of 6

Measure 4 DWH Pipe Insulation**Components****Inspected****Comment**

#	Material / Labor	Description / Comment	Units	Estimated			Actual		
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	DHW Pipe Insulation Includes labor cost. All corners must be cut properly. Refer to Appendix A- Standards for Weatherization Materials and Southeast Field Guide.	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
3	Other	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:**

Client Name:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

Work Order (Bid Form)

Work Order Name: WO/15015SE-4158/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 4 of 6

Measure 5 DWH Tank Insulation**Components****Inspected****Comment**

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Hot Water Equip	DHW Tank Insulation Includes labor cost. R-10 minimum. Refer to Appendix A- Standards for Weatherization Materials and Southeast Field Guide.	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
3	Other	DHW Tank Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:**

Client Name:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

Work Order (Bid Form)

Work Order Name: WO/15015SE-4158/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 5 of 6

Measure 6 Storm Windows**Components** 4,1,2,7,8,5,10,11**Inspected****Comment** Contractor to take and verify all measurements.☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Windows	Storm Window Includes labor and material. Refer to House diagram for estimated measurements. Responsibility of contractor to verify measurements in the field before ordering window(s). Contractor must follow all egress codes if applicable. Contractor to include the thermal break, caulking, framing, and any other related items to convey a completed measure.	SqFt	212.4	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Storm Window	SqFt	212.4	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
3	Other	Storm Window	Each Window	18	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:****Work Order Grand Total:****Grand Total:**

Client Name:

Client ID: 15015SE-4158

Alt. Client ID: McMinn

Work Order (Bid Form)

Work Order Name: WO/15015SE-4158/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 6 of 6