



Work Order (Bid Form)

WORK ORDER INFORMATION

Work Order Name: WO/15015SE-5074/1

Work Order Type: Weatherization

Audit Name: NA

CLIENT INFORMATION

Client Name:

Address:

Client ID: 15015SE-5074

Alt. Client ID: Meigs

AGENCY INFORMATION

Agency: Southeast Tennessee Human Resource Agency

Agency Phone: (423) 949-2191

Address: 312 Resource Rd.
Dunlap, TN 37327

Fax: (423) 949-4023

Email Address: aramsey@sethtra.us

Agency Contact: Gaskins, Glenn

Work Phone:

Cell Phone: (865) 679-8303

Email Address: amerispechome20@bellsouth.net

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

Site Built

Home built in 1956 per client. Lead Safe Weatherization protocol applies.

Measures

Measure 1 Infiltration Redctn				Components			Inspected		
Comment 1. Weatherstrip D1 Door at Laundry. 2. Seal all joints in door frame and trim on door from laundry to house. Seal ceiling plywood seams at Laundry. 3. Panel over and seal unused door opening at middle bedroom. Opening backs up to bathroom tub. Air infiltration from attic area. Consult with client about foaming/sealing and enclosing area. 4. Seal/caulk all trim joints at bathroom door.							<input type="checkbox"/>		
#	Material / Labor	Description / Comment	Units	Estimated		Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
10	Miscellaneous Su	Infiltration Reduction	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other Detail									
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Measure Sub Total:						<input type="text"/>	Sub Total: <input type="text"/>		
Field Notes:									

Measure 2 Attic Ins. R-38				Components Attic			Inspected		
Comment Fill attic ceiling to R38 blown cellulose. 1106 sq ft. Rework and insulate/weatherstrip attic access. Install insulation dam. Adhere to specifications of Southeast Weatherization Field Guide.							<input type="checkbox"/>		
#	Material / Labor	Description / Comment	Units	Estimated		Actual			
				Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	Attic Insulation - Blown Cellulose - R-38	SqFt	1106	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Other Detail									
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
Measure Sub Total:						<input type="text"/>	Sub Total: <input type="text"/>		
Field Notes:									

Client Name:
Client ID: 15015SE-5074
Alt. Client ID: Meigs

Work Order (Bid Form)
Work Order Name: WO/15015SE-5074/1
Report Run On: 4/29/2010

DOE Weatherization Assistant
Version 8.6.0
Page 2 of 3

Measure 3 Practice Lead Safe Weatherization (Walls)**Components****Inspected**

Comment Home is pre-1978. Follow lead safe weatherization protocol. Contractor to follow requirements of EPA Lead -Based Paint Renovation, Repair and Painting. Contractor to adhere to 4 step requirements of WAP ARRA 10-20 for determining need for presence of Certified Rennovator/Firm

☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	Equipment	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:****Work Order Grand Total:****Grand Total:**

Client Name:

Client ID: 15015SE-5074

Alt. Client ID: Meigs

Work Order (Bid Form)

Work Order Name: WO/15015SE-5074/1

Report Run On: 4/29/2010

DOE Weatherization Assistant

Version 8.6.0

Page 3 of 3