



Work Order (Bid Form)

WORK ORDER INFORMATION

Work Order Name: WO/15015SE-6069/1

Work Order Type: Weatherization

Audit Name: 15015SE-6069AUDIT

CLIENT INFORMATION

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Address:

Copperhill, TN 37317

CLIENT CONTACT INFORMATION

NA

Applicant/Person of
Record



Site Built
Built approx 1990
Approx 916 sqft

AGENCY INFORMATION

Agency: Southeast Tennessee Human Resource Agency

Address: 312 Resource Rd.

Dunlap, TN 37327

Agency Phone: (423) 949-2191

Fax: (423) 949-4023

Email Address: aramsey@sethra.us

Agency Contact: Bloodworth, Willaim D.

Work Phone:

Cell Phone: (423) 505-4585

Email Address: Darblood@comcast.net

Company Name & License Number: _____

Contractor's Signature: _____

COMMENT

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 1 of 8

Measures

Measure 1 Infiltration Redctn

Components

Inspected

Comment Caulk inside of all windows (7) including trim, Airseal under bathroom sink, Patch approx one sqft hole in drywall behind washer, Weatherstrip two doors, Airseal approx three inch hole under washer, Build insulated door for attic-1 (install and weatherstrip) approx 22x36

☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
10	Miscellaneous Su	Infiltration Reduction	See Above	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:

Sub Total:

Field Notes:

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 2 of 8

Measure 2 DWH Pipe Insulation**Components****Inspected****Comment**☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	DHW Pipe Insulation Includes labor cost. All corners must be cut properly. Refer to Appendix A- Standards for Weatherization Materials and Southeast Field Guide.	Linear Foot	10	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
3	Other	DHW Pipe Insulation	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:****Measure 3 Attic Ins. R-38****Components** ATTIC-1**Inspected****Comment** Batt insulation is installed with paper side up, either cut facing or turn over before adding insulation☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Insulation	Attic Insulation - Blown Cellulose - R-38	SqFt	276	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:**

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 3 of 8

Measure 4 Storm Windows**Components** W-7,W-3,W-1,W-2,W-6,W-4**Inspected****Comment** Need interior storms. Approx window sizes W-1,2,3,7 32x52 W4,6 32x36

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Windows	Storm Window Includes labor and material. Refer to House diagram for estimated measurements. Responsibility of contractor to verify measurements in the field before ordering window(s). Contractor must follow all egress codes if applicable. Contractor to include the thermal break, caulking, framing, and any other related items to convey a completed measure.	SqFt	62.22	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Storm Window	SqFt	62.22	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
3	Other	Storm Window	Each Window	6	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:**

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 4 of 8

Measure 5 Refrigerator Rplcmnt				Components				Inspected	
Comment									
				Estimated		Actual			
#	Material / Labor	Description / Comment	Units	Qty	Unit Cost	Total	Qty	Unit Cost	Total
10	Refrigerators	Kenmore - 68972 or equivalent	Each	1					
Other Detail									
Measure Sub Total:							Sub Total:		
Field Notes:									

Measure 6 CO Monitor is Needed				Components				Inspected	
Comment									
				Estimated		Actual			
#	Material / Labor	Description / Comment	Units	Qty	Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	CO monitor	Each	1					
		Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.							
2	Labor	Labor	Each	1					
Other Detail									
Measure Sub Total:							Sub Total:		
Field Notes:									

**Measure 7 Fix Other Water Heating Problem
(Romex connector)****Components****Inspected****Comment**☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	Equipment Romex connector	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor Install Romex connector	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:****Measure 8 Install heat pump****Components****Inspected**

Comment Heatpump replaces unvented LP heater and window air conditioner. Properly dispose of LP heater and window air conditioner. No existing ductwork.
Approx 916 sqft. Contractor to verify heatpump size required.

☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
10	Heating Equipmen	Heat pump	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total:**Sub Total:****Field Notes:**

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 6 of 8

Measure 9 PressureRelief Piping Needed**Components****Inspected**

Comment Water heater must have safety discharge pipe installed on pressure relief valve that should terminate 6" above floor or outside dwelling area as specified by local codes.

☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	Pressure relief piping 6' of copper pipe to extend no further than 6" above floor.	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	Each	1	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total: **Sub Total:** **Field Notes:****Measure 10 Vapor Barrier Needed
(Basement/Crawlspace)****Components****Inspected**

Comment Must be 6 mil poly. Must be installed 100% of crawlspace with 6" turned up all walls and support piers. Must be securely fastened. Must be cleated down to earth. Must be secured at all seams. Refer to Attachment A- Standards for Weatherization Materials and Southeast Field Guide.

☐

#	Material / Labor	Description / Comment	Units	Qty	Estimated		Actual		
					Unit Cost	Total	Qty	Unit Cost	Total
1	Health and Safety	Basement /Crawlspace Vapor Barrier	SqFt	616	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
2	Labor	Labor	SqFt	616	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Other Detail

<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>	<input type="text"/>

Measure Sub Total: **Sub Total:** **Field Notes:**

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 7 of 8

Work Order Grand Total:

Grand Total:

Client Name: NA

Client ID: 15015SE-6069

Alt. Client ID: Polk

Work Order (Bid Form)

Work Order Name: WO/15015SE-6069/1

Report Run On: 4/18/2010

DOE Weatherization Assistant

Version 8.6.0

Page 8 of 8