



**STATE OF TENNESSEE  
DEPARTMENT OF TRANSPORTATION**

Construction division  
SUITE 700, JAMES K. POLK BUILDING  
505 DEADERICK STREET  
NASHVILLE, TN 37243  
(615) 741-2848

**JOHN C. SCHROER**  
COMMISSIONER

**BILL HASLAM**  
GOVERNOR

March 15, 2018

**ADDENDUM #2**

**Re: I-440, Widening from I-40 to I-24  
Davidson County  
Contract No. DB1701**

**To Whom It May Concern:**

This addendum revises the RFP Contract Book 3. Attached are the revised sheets.

You must acknowledge this addendum by completing the "Addendum Letter Acknowledgement form C and the Technical Proposal Signature Page (Form TPSP) within your Technical Proposal. It is the bidder's responsibility to notify all affected manufacturers, suppliers and subcontractors of this change.

Sincerely,

A handwritten signature in blue ink that reads "Lia Baird".

Assistant Director of Construction  
Construction Division

# **DESIGN-BUILD**

## **PROJECT SPECIFIC INFORMATION**

**TENNESSEE DEPARTMENT OF TRANSPORTATION**

**Interstate 440, Widening from I-40 to I-24,  
Project includes removing and replacing existing pavement**

**Davidson County- TENNESSEE**

**CONTRACT NUMBER: DB1701**



**January 12, 2018**  
**Addendum #1 March 13, 2018**  
**Addendum #2 March 15, 2018**

	to prevent ground disturbance. Any damage to vegetated areas outside the limits of construction shall be repaired at the Design-Builder’s expense. These areas are to be returned to their pre-construction state as directed and concurred with by the Department.
3.3.m	The Design-Builder shall notify the Department and all adjoining properties and stakeholders thirty (30) days prior to proposed noise barrier wall clearing, demolition or construction. Noise barrier construction shall only be conducted during daytime hours not earlier than 8:00 A.M. and no later than 7:00 P.M.
3.3.n	If a proposed noise barrier wall cannot be constructed prior to demolishing an existing noise barrier wall, the Design-Builder shall begin construction of new noise barrier walls within thirty (30) days of the start of demolition of an existing sound barrier wall or cutting of trees whichever occurs first, unless otherwise approved by the Department. The Design-Builder shall complete construction of any new sound barrier wall intended to replace an existing sound barrier wall which was acting as a screen for adjacent properties within 90 days from the start of demolition of the existing sound barrier wall or cutting of trees whichever occurs first, unless otherwise approved by the Department. Once work commences on an individual noise barrier wall, the Design-Builder shall continue construction operations until the wall is complete, unless otherwise approved by the Department. Design-Builder shall provide temporary 6’ high chain link fencing for access control during noise barrier replacement.
3.3.o	All proposed noise barrier walls shall be absorptive.

**3.4 Noise Barrier Walls (Repairs)**

Req. No	Requirement text
3.4.a	<p>The Design-Builder shall repair the existing noise walls on the I-440 corridor in accordance with the Noise Walls Inspection Report and Preliminary Plans as included on the Project Website and with the Special Provision 718NB Absorptive Barriers as included in <b>Contract Book 2 (Design-Build Contract)</b>. The Design-Builder shall be required to perform a design level investigation and report to validate and augment the wall repair information included in this RFP. The report shall be submitted within the proposal. The Department will utilize the design level investigation reports to determine final wall repair areas. These final wall repair areas will be distributed to the Design-Builders for bidding purposes.</p> <p><del>The Design-Builder shall submit their investigative report not later than 3-12-2018 to the Department. The final wall areas will be distributed to the Design Builders no later than 3-31-2018.</del></p> <p>The Department will provide the final wall area and unit price on the project website on 4-2-2018. Overage of repair quantity (beyond the quantities provided and as determined during construction) shall be paid (with prior approval of the Engineer) as to be defined in Section 13.5 in a forthcoming addendum.</p>
3.4.b	The wall repairs modifications shall comply with the Department’s specifications and shall be aesthetically uniform in accordance with the existing noise walls. Noise barrier repairs shall only be conducted during daytime hours not earlier than 8:00 A.M. and no later than 7:00 P.M.
3.4.c	Upon completion of the Project, the Design-Builder shall provide TDOT Structures Division a final revised set of plans for all walls. The plans shall be delivered on CD