

Estimated Quantities -- Letting July 01, 2022

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNW266 - HAYWOOD

Contract ID: CNW266

Letting Date: July 01, 2022 10:00 AM

Projects: 38S179-S8-003
38S222-S8-003

N/A
N/A

Counties: HAYWOOD

District:

DBE Goal Percent:

Description: The full depth reclamation and paving on S.R. 179 from the Tipton County line (L.M. 0.00) to U.S. 79 (S.R. 1) (L.M. 4.27) and on S.R. 222 from near Stanton-Sommerville Road (L.M. 3.00) to U.S. 79 (S.R. 1) (L.M. 4.52).

Contract Time: DT - 11/15/2022

Item No.	Description	Quantity	Units
202-03.01	REMOVAL OF ASPHALT PAVEMENT	1,889.000	S.Y.
203-06	WATER	427.000	M.G.
208-01.05	BROOMING & DEGRASSING SHOULDERS	10.890	L.M.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (C OR D)	4,329.000	TON
304-01.04	PROCESSING (RECLAIMED BASE MATERIAL)	68,487.000	S.Y.
304-01.08	PORTLAND CEMENT (FULL DEPTH PAVEMENT RECLAMATION)	2,442.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	1,039.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	7,728.000	TON
307-01.10	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING C-W	1,610.000	TON
403-02.01	TRACKLESS TACK COAT	44.000	TON
405-01.01	BITUMINOUS MATERIAL (BSC)	92.000	TON
405-01.02	MINERAL AGGREGATE (BSC)	805.000	TON

Contract ID CNW266 - HAYWOOD

Item No.	Description	Quantity	Units
411-01.10	ACS MIX(PG64-22) GRADING D	3,708.000	TON
411-12.04	SCORING FOR RUMBLE STRIPE (NON-CONTINUOUS) (4IN WIDTH)	6.000	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	37.000	TON
415-01.02	COLD PLANING BITUMINOUS PAVEMENT	505.000	S.Y.
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	2.000	EACH
705-02.10	GUARDRAIL TRANSITION 27IN TO 31IN	6.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	10.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-06	SIGNS (CONSTRUCTION)	1,378.000	S.F.
713-02.21	SIGN POST DELINEATION ENHANCEMENT	15.000	L.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-16.09	RAILROAD ADVANCE WARNING SIGN AND SUPPORT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	281.000	EACH
716-01.30	REMOVAL OF SNOWPLOWABLE REFLECTIVE MARKER	281.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	269.000	L.F.
716-03.02	PLASTIC WORD PAVEMENT MARKING (RXR)	2.000	EACH
716-05.05	PAINTED PAVEMENT MARKING (STOP LINE)	65.000	L.F.
716-05.20	PAINTED PAVEMENT MARKING (6" LINE)	58.438	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN LINE)	21.512	L.M.
717-01	MOBILIZATION	(1)	LS

() Item will be bid as lump sum.

