

Estimated Quantities -- Letting July 26, 2024

Quantities shown are for information only and should not be used for bidding purposes. The official bid files should be obtained from www.bidx.com

Contract ID CNY204 - FAYETTE

Contract ID: CNY204

Letting Date: July 26, 2024 10:00 AM

Projects: 24S222-S3-003

N/A

Counties: FAYETTE

District:

DBE Goal Percent:

Description: The grading, drainage, signals, and paving on S.R. 222 from Hebron Drive (L.M. 7.67) to near Thorpe Drive (L.M. 8.21), including the I-40 interchange (Exit 42).

Contract Time: DT - 5/31/2026

Item No.	Description	Quantity	Units
105-01	CONSTRUCTION STAKES, LINES AND GRADES	(1)	LS
201-01	CLEARING AND GRUBBING	(1)	LS
202-01	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	(1)	LS
203-01	ROAD & DRAINAGE EXCAVATION (UNCLASSIFIED)	81,222.000	C.Y.
203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	17,948.000	TON
203-03.01	BORROW EXCAVATION (SELECT MATERIAL)	9,879.000	C.Y.
203-04	PLACING AND SPREADING TOPSOIL	9,587.000	C.Y.
203-05	UNDERCUTTING	9,879.000	C.Y.
203-06	WATER	470.000	M.G.
204-08.01	BACKFILL MATERIAL (FLOWABLE FILL)	36.000	C.Y.
208-01.05	BROOMING & DEGRASSING SHOULDERS	2.700	L.M.
209-05	SEDIMENT REMOVAL	3,400.000	C.Y.
209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	40,143.000	L.F.
209-08.03	TEMPORARY SILT FENCE (WITHOUT BACKING)	31,789.000	L.F.
209-08.07	ROCK CHECK DAM	145.000	EACH
209-08.08	ENHANCED ROCK CHECK DAM	55.000	EACH

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
209-09.01	SANDBAGS	1,945.000	BAG
209-09.03	SEDIMENT FILTER BAG (15' X 15')	4.000	EACH
209-20.03	POLYETHYLENE SHEETING (6 MIL. MINIMUM)	500.000	S.Y.
209-40.30	CATCH BASIN PROTECTION (TYPE A)	22.000	EACH
209-65.03	TEMPORARY DIVERSION CHANNEL	270.000	L.F.
209-65.04	TEMPORARY IN STREAM DIVERSION	190.000	L.F.
303-02	MINERAL AGGREGATE, TYPE B BASE, GRADING (DESCRIPTION) (D)	53,368.000	TON
303-10.01	MINERAL AGGREGATE (SIZE 57)	131.000	TON
304-01.02	CEMENT (SOIL-CEMENT BASE)	1,066.000	TON
304-01.03	PROCESSING (SOIL-CEMENT BASE)	56,520.000	S.Y.
304-02	BITUMINOUS MATERIAL (SOIL-CEMENT BASE)	49.000	TON
307-01.01	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING A	535.000	TON
307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	2,576.000	TON
307-01.21	ASP. CONC. MIX(PG70-22) (BPMB-HM) GR. A-S	404.000	TON
307-01.22	ASP. CONC. MIX(PG76-22) (BPMB-HM) GR. A-S	1,812.000	TON
307-02.01	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING A	1,509.000	TON
307-02.08	ASPHALT CONCRETE MIX (PG70-22) (BPMB-HM) GRADING B-M2	528.000	TON
307-03.01	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING A	4,085.000	TON
307-03.08	ASPHALT CONCRETE MIX (PG76-22) (BPMB-HM) GRADING B-M2	1,285.000	TON
307-03.10	ASPHALT CONC MIX (PG76-22)(BPMB-HM) GR CS	1,750.000	TON
313-03	TREATED PERMEABLE BASE	11,969.000	S.Y.
402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	53.000	TON
402-02	AGGREGATE FOR COVER MATERIAL (PC)	190.000	TON
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	51.000	TON
403-02.01	TRACKLESS TACK COAT	50.000	TON
403-02.02	HOT APPLIED TACK COAT	38.000	TON

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
407-20.05	SAW CUTTING ASPHALT PAVEMENT	11,885.000	L.F.
411-01.07	ACS MIX (PG64-22) GRADING E SHOULDER	382.000	TON
411-01.10	ACS MIX(PG64-22) GRADING D	511.000	TON
411-01.21	LONGITUDINAL JOINT SEALANT	3.900	L.M.
411-02.10	ACS MIX(PG70-22) GRADING D	1,518.000	TON
411-03.23	ACS MIX (PG76-22) OGFC	3,258.000	TON
411-12.01	SCORING SHOULDERS (CONTINUOUS) (16IN WIDTH)	2.800	L.M.
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	4,445.000	TON
501-01.03	PORTLAND CEMENT CONCRETE PAVEMENT (PLAIN) 10"	11,969.000	S.Y.
502-03.13	CONCRETE PAVEMENT REMOVAL	3,521.000	S.Y.
502-03.20	FULL DEPTH PCC PAVEMENT REPAIR	62.000	C.Y.
502-04.01	SAWING CONCRETE PAVEMENT (FULL DEPTH)	3,108.000	L.F.
502-04.02	LOAD TRANSFER DOWELS	2,760.000	EACH
502-04.03	TRANSVERSE TIE-BARS	337.000	EACH
607-03.02	18" CONCRETE PIPE CULVERT (CLASS III)	187.000	L.F.
607-03.30	18" PIPE CULVERT	5.000	L.F.
607-05.02	24" CONCRETE PIPE CULVERT (CLASS III)	11.000	L.F.
607-05.30	24" PIPE CULVERT	55.000	L.F.
607-06.30	30" PIPE CULVERT	175.000	L.F.
607-08.02	42" CONCRETE PIPE CULVERT (CLASS III)	23.000	L.F.
607-10.30	54" PIPE CULVERT	73.000	L.F.
607-11.03	60" CONCRETE PIPE CULVERT (CLASS III)	26.000	L.F.
607-11.30	60" PIPE CULVERT	15.000	L.F.
607-16.01	23"X 14" HORIZONTAL OVAL CONCRETE PIPE CULVERT	279.000	L.F.
607-37.02	18" CORRUGATED METAL PIPE CULVERT	17.000	L.F.
607-39.02	18" PIPE CULVERT (SIDE DRAIN)	108.000	L.F.
607-39.05	36" PIPE CULVERT (SIDE DRAIN)	51.000	L.F.
611-02.11	JUNCTION BOX, TYPE 2	1.000	EACH

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
611-05.01	TRENCH DRAINS	240.000	L.F.
611-07.01	CLASS A CONCRETE (PIPE ENDWALLS)	72.000	C.Y.
611-07.02	STEEL BAR REINFORCEMENT (PIPE ENDWALLS)	3,392.000	LB.
611-07.54	18IN ENDWALL (CROSS DRAIN) 3:1	1.000	EACH
611-07.56	18IN ENDWALL (CROSS DRAIN) 6:1	3.000	EACH
611-07.58	24IN ENDWALL (CROSS DRAIN) 4:1	1.000	EACH
611-07.60	30IN ENDWALL (CROSS DRAIN) 3:1	3.000	EACH
611-07.62	30IN ENDWALL (CROSS DRAIN) 6:1	1.000	EACH
611-09.03	CAPPING EXISTING CATCHBASIN	2.000	EACH
611-40.02	CATCH BASINS, TYPE 40, > 4' - 8' DEPTH	1.000	EACH
611-42.01	CATCH BASINS, TYPE 42, 0' - 4' DEPTH	1.000	EACH
611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	1.000	EACH
621-03.02	18" TEMPORARY DRAINAGE PIPE	15.000	L.F.
621-03.03	24" TEMPORARY DRAINAGE PIPE	515.000	L.F.
621-03.04	30" TEMPORARY DRAINAGE PIPE	140.000	L.F.
621-03.05	36" TEMPORARY DRAINAGE PIPE	1,633.000	L.F.
621-03.06	42" TEMPORARY DRAINAGE PIPE	78.000	L.F.
705-06.01	W BEAM GR (TYPE 2) MASH TL-3	7,120.000	L.F.
705-06.10	GR TERMINALTRAILING END (TYPE 13) MASH TL-3	8.000	EACH
705-06.11	GR TERMINAL (IN-INLINE) MASH TL-3	8.000	EACH
705-06.20	TANGENT ENERGY ABSORBING TERM MASH TL-3	8.000	EACH
705-06.25	THRIE BEAM BRIDGE TRANSITION MASH TL-3	2.000	EACH
706-01	GUARDRAIL REMOVED	4,001.000	L.F.
706-06.03	RADIUS RAIL	196.000	L.F.
706-10.80	MICHIGAN AND MODIFIED MICHIGAN END SHOE	2.000	EACH
707-01.11	CHAIN LINK FENCE (6 FOOT)	4,936.000	L.F.
707-01.12	END & CORNER POST ASSEMBLY(CHAIN-LINK FENCE 6')	20.000	EACH
707-06.01	REMOVAL OF FENCE (DESCRIPTION) (EXIST. INTERSTATE R.O.W. FENCE)	3,543.000	L.F.
707-08.11	HIGH-VISIBILITY CONSTRUCTION FENCE	17,747.000	L.F.

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
708-02.01	MARKERS (CONCRETE R.O.W. POSTS)	50.000	EACH
709-05.05	MACHINED RIP-RAP (CLASS A-3)	450.000	TON
709-05.06	MACHINED RIP-RAP (CLASS A-1)	1,780.000	TON
709-05.08	MACHINED RIP-RAP (CLASS B)	640.000	TON
709-05.09	MACHINED RIP-RAP (CLASS C)	549.000	TON
710-02	AGGREGATE UNDERDRAINS (WITH PIPE)	20,890.000	L.F.
710-05	LATERAL UNDERDRAIN	2,940.000	L.F.
710-06.11	LATERAL UNDERDRAIN ENDWALL (2:1)	8.000	EACH
710-06.12	LATERAL UNDERDRAIN ENDWALL (3:1)	11.000	EACH
710-06.13	LATERAL UNDERDRAIN ENDWALL (4:1)	7.000	EACH
710-06.15	LATERAL UNDERDRAIN ENDWALL (6:1)	58.000	EACH
712-01	TRAFFIC CONTROL	(1)	LS
712-02.12	PORTABLE BARRIER RAIL, REDUCED DEFLECTION (MASH TL-3)	29,520.000	L.F.
712-02.60	TEMPORARY WORK ZONE CRASH CUSHION (MASH TL-3)	13.000	EACH
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	322.000	EACH
712-04.50	BARRIER RAIL DELINEATOR	311.000	EACH
712-05.01	WARNING LIGHTS (TYPE A)	4.000	EACH
712-06	SIGNS (CONSTRUCTION)	1,273.000	S.F.
712-07.03	TEMPORARY BARRICADES (TYPE III)	60.000	L.F.
712-08.03	ARROW BOARD (TYPE C)	4.000	EACH
712-08.10	MOBILE MESSAGE SIGN UNIT W/ATTENUATOR	3,840.000	HOUR
712-09.02	REMOVABLE PAVEMENT MARKING (8" BARRIER LINE)	9,918.000	L.F.
712-09.04	REMOVABLE PAVEMENT MARKING (STOP LINE)	72.000	L.F.
712-09.08	REMOVABLE PAVEMENT MARKING (6" line)	83,193.000	L.F.
712-09.30	REMOVABLE BLACK-OUT TAPE (6")	83,193.000	L.F.
712-09.31	REMOVABLE BLACK-OUT TAPE (8IN)	3,717.000	L.F.
713-01.01	CLASS A CONCRETE (FOUNDATION FOR SIGN SUPPORTS)	17.000	C.Y.
713-01.02	STEEL BAR REINFORCEMENT(FOUNDATION FOR	456.000	LB.

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
	SIGN SUPPORTS)		
713-06	STEEL I-BEAMS & WF-BEAMS(BREAKAWAY) SIGN SUPPORT	34,413.000	LB.
713-09.01	STEEL OVERHEAD SIGN STRUCTURE (SPAN____) (SPAN 85')	1.000	EACH
713-11.02	PERFORATED/KNOCKOUT SQUARE TUBE POST	4,292.000	LB.
713-13.02	FLAT SHEET ALUMINUM SIGNS (0.080" THICK)	369.000	S.F.
713-13.03	FLAT SHEET ALUMINUM SIGNS (0.100" THICK)	513.000	S.F.
713-14	EXTRUDED ALUMINUM PANEL SIGNS	3,175.000	S.F.
713-15	REMOVAL OF SIGNS, POSTS AND FOOTINGS	(1)	LS
713-15.02	REMOVAL & RELOCATION OF SIGN & SUPPORT	13.000	EACH
713-15.07	SUSPENDED FLAT SHEET ALUMINUM SIGN (0.080" THICK)	3.000	EACH
713-16.01	CHANGEABLE MESSAGE SIGN UNIT	2.000	EACH
713-16.07	END OF ROADWAY SIGN AND SUPPORT	2.000	EACH
716-01.21	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR) (1 COLOR)	444.000	EACH
716-01.22	SNOWPLOWABLE RAISED PAVEMENT MARKERS (MONO-DIR)(1 COLOR)	332.000	EACH
716-01.23	SNOWPLOWABLE RAISED PAVEMENT MARKERS (BI-DIR)(2 COLOR)	138.000	EACH
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	271.000	L.F.
716-02.06	PLASTIC PAVEMENT MARKING (TURN LANE ARROW)	27.000	EACH
716-02.07	PLASTIC PAVEMENT MARKING (24" BARRIER LINE)	1,940.000	L.F.
716-02.08	PLASTIC PAVEMENT MARKING (8" DOTTED LINE)	366.000	L.F.
716-04.07	PLASTIC PAVEMENT MARKING (EXIT ONLY ARROW)	2.000	EACH
716-04.08	PLASTIC PAVEMENT MARKING (OPTION LANE ARROW)	2.000	EACH
716-04.12	PLASTIC PAVEMENT MARKING (YIELD LINE)	24.000	S.F.
716-04.14	PLASTIC PAVEMENT MARKING (LANE REDUCTION ARROW)	5.000	EACH
716-09.88	CONTRAST PAVEMENT MARKING 8"	1.300	L.M.
716-12.02	ENHANCED FLATLINE THERMO PVMT MRKNG (6IN	11.800	L.M.

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
716-12.05	LINE) ENHANCED FLATLINE THERMO PVMT MRKNG (6IN DOTTED LINE)	2,275.000	L.F.
716-12.06	ENHANCED FLAT LINE THERMO (8IN LINE)	8,718.000	L.F.
716-12.09	ENHANCED FLAT LINE THERMO (12IN LINE)	1,398.000	L.F.
716-12.10	ENHANCED FLAT LINE THERMO (12IN DOTTED)	609.000	L.F.
717-01	MOBILIZATION	(1)	LS
725-21.07	PORTABLE SMART WORK ZONE SYSTEM	240.000	DAY
730-01.02	REMOVAL OF SIGNAL EQUIPMENT	2.000	EACH
730-02.03	SIGNAL HEAD ASSEMBLY (130 A3 WITH BACKPLATE)	3.000	EACH
730-02.09	SIGNAL HEAD ASSEMBLY (130 WITH BACKPLATE)	9.000	EACH
730-02.11	SIGNAL HEAD ASSEMBLY (130 A2 WITH BACKPLATE)	4.000	EACH
730-02.17	SIGNAL HEAD ASSEMBLY (150 A2H WITH BACKPLATE)	1.000	EACH
730-02.30	SIGNAL HEAD ASSEMBLY (DESCRIPTION) (POLE MOUNTED)	1.000	EACH
730-03.21	INSTALL PULL BOX (TYPE B)	2.000	EACH
730-05.01	ELECTRICAL SERVICE CONNECTION	2.000	EACH
730-08.02	SIGNAL CABLE - 5 CONDUCTOR	1,755.000	L.F.
730-08.03	SIGNAL CABLE - 7 CONDUCTOR	1,619.000	L.F.
730-08.10	SIGNAL CABLE - (DESCRIPTION) (RADAR)	4,851.000	L.F.
730-09.20	SPAN WIRE ASSEMBLY	952.000	L.F.
730-10.01	TETHER WIRE ASSEMBLY - 1/4" DIAMETER	952.000	L.F.
730-12.02	CONDUIT 2" DIAMETER (PVC SCHEDULE 40)	200.000	L.F.
730-13.12	VEHICLE DETECTOR (RADAR - STOP LINE)	6.000	EACH
730-13.13	VEHICLE DETECTOR (RADAR - ADVANCE)	4.000	EACH
730-15.32	CABINET (EIGHT PHASE BASE MOUNTED)	2.000	EACH
730-15.41	EIGHT PH ACTUATED CONTROLLER (FIBER)	2.000	EACH
730-19.01	TIME BASE COORDINATION UNIT	2.000	EACH
730-23.01	STEEL STRAIN POLE (SIGNAL SUPPORT)	8.000	EACH
730-35.06	BATTERY BACK-UP SYSTEM	2.000	EACH

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
730-40.02	TEMPORARY TRAFFIC SIGNAL SYSTEM	(1)	LS
740-10.03	GEOTEXTILE (TYPE III)(EROSION CONTROL)	7,365.000	S.Y.
740-10.04	GEOTEXTILE (TYPE IV)(STABILIZATION)	31,704.000	S.Y.
740-11.01	TEMPORARY SEDIMENT TUBE 8IN	1,075.000	L.F.
740-11.03	TEMPORARY SEDIMENT TUBE 18IN	2,993.000	L.F.
801-01.07	TEMPORARY SEEDING (WITH MULCH)	18.000	UNIT
801-03	WATER (SEEDING & SODDING)	576.000	M.G.
802-12.01	ACER NEGUNDO (BOX ELDER SEEDLNG B.R.)	105.000	EACH
802-12.16	FRAXINUS PENNSYLVANICA (GREEN ASH SEEDLNG B.R.)	105.000	EACH
802-12.26	PLATANUS OCCIDENTALIS (SYCAMORE SEEDLNG B.R.)	105.000	EACH
802-12.40	SALIX NIGRA (BLACK WILLOW SEEDLNG B.R.)	99.000	EACH
802-12.44	ULMUS AMERICANA (AMERICAN ELM SEEDLNG B.R.)	105.000	EACH
803-01	SODDING (NEW SOD)	57,519.000	S.Y.
806-02.03	PROJECT MOWING	2.000	CYCL
202-04.01	REMOVAL OF STRUCTURES (DESCRIPTION, STA.) (BRIDGE NO. 24-SR222-7.75)	(1)	LS
204-02.01	DRY EXCAVATION (BRIDGES)	1,183.000	C.Y.
303-10.04	MINERAL AGGREGATE (SIZE) (SIZE 57)	1,652.000	TON
604-03.04	PAVEMENT @ BRIDGE ENDS	442.000	S.Y.
604-05.31	BRIDGE DECK GROOVING (MECHANICAL)	431.000	S.Y.
617-04.01	TYPE 1 THIN EPOXY OVERLAY (EPOXY-URETHANE)	2,235.000	S.Y.
740-07.04	GEOGRID REINFORCEMENT TYPE 2	3,115.000	S.Y.
790-02.04	POLE 35FT CLASS 5 WOOD	2.000	EACH
790-03.01	POLE 40FT CLASS 2 WOOD	4.000	EACH
790-04.04	POLE 45FT CLASS 4 WOOD	1.000	EACH
790-06.02	POLE 55FT CLASS 2 WOOD	1.000	EACH
790-07.02	POLE 60FT CLASS 2 WOOD	4.000	EACH
790-09.05	POLE 70FT CLASS H2 METAL	1.000	EACH
790-10.05	POLE 75FT CLASS H2 METAL	1.000	EACH

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
790-21.02	1PH SGL PRIMARY SUPPORT MISC 15KV	4.000	EACH
790-21.09	1PH PRIMARY TAP 15KV	4.000	EACH
790-22.01	1PH SGL PRIMARY SUPPORT 25KV	2.000	EACH
790-25.08	3PH CROSSARM SGL LRG COND 15KV	1.000	EACH
790-25.10	3PH CROSSARM DBL PRIM SUPPORT 15KV	2.000	EACH
790-25.12	3PH CROSSARM DBL 10FT PRIM SUP 15KV	1.000	EACH
790-25.21	3PH CROSSARM DEADEND SGL 15KV	2.000	EACH
790-25.24	3PH CROSSARM DDE LRG COND 15KV	4.000	EACH
790-25.27	3PH CROSSARM DDE 10FT ARMS LRG COND 15KV	1.000	EACH
790-26.13	3PH CROSSARM DBL SM ANGLE LRG COND 25KV	2.000	EACH
790-26.26	3PH CROSSARM DEAD END 25KV	1.000	EACH
790-26.27	3PH CROSSARM DBL DDE 25KV	2.000	EACH
790-26.28	3PH DBL 10FT XARM DDE 25KV	1.000	EACH
790-32.02	DOWN GUY - THROUGH BOLT TYPE HEAVY DUTY	33.000	EACH
790-32.06	DOWN GUY - INSULATED	34.000	EACH
790-32.07	OH GUY - THROUGH BOLT TYPE	2.000	EACH
790-32.23	GUY GUARD	18.000	EACH
790-33.04	SCREW TYPE ANCHOR 10,000LB-12,000LB	5.000	EACH
790-36.14	TRANSFER CONDUCTOR	26.000	EACH
790-40.01	OH COND 4 7/1 ACSR SWANATE	649.000	L.F.
790-40.02	OH COND 2 7/1 ACSR SPARATE	903.000	L.F.
790-40.03	OH COND 1/0 6/1 ACSR RAVEN	2,623.000	L.F.
790-40.09	OH COND 336.4 18/1 ACSR MERLIN	13,242.000	L.F.
790-46.02	1PH TRANSFORMER CONV W/POLE MTD FUSE & LA	1.000	EACH
790-54.03	10KVA 1PH OH XFORMER 14.4KV 120/240	1.000	EACH
790-60.05	3 - 1PH SECTIONALIZERS OR RECLOSERS 15KV	1.000	EACH
790-68.01	POLE GROUND ROD TYPE	12.000	EACH
790-71.35	DBL CKT SGL ARM W/ SUSP INS 69KV MAX	1.000	EACH
790-71.85	DOUBLE CIRCUIT SMALL ANGLE SUSPENSION INSULATOR 69KV MAX	1.000	EACH

Contract ID CNY204 - FAYETTE

Item No.	Description	Quantity	Units
790-72.01	ANCHOR POWER SCREW	13.000	EACH
790-98.01	REMOVE WIRE	17,283.000	L.F.
790-98.02	REMOVE POLES	12.000	EACH
790-98.03	REMOVE FRAMING/ASSOCIATED APPARATUS	175.000	EACH
793-10.20	EXPOSE EXISTING CABLE/CONDUIT (ALL DEPTHS)	5.000	L.F.
793-11.04	6IN PEDESTAL	2.000	EACH
793-11.06	8IN PEDESTAL	1.000	EACH
793-11.19	MARKER POST	7.000	EACH
793-11.20	HANDHOLE 30INX48IN	3.000	EACH
793-11.31	REMOVE HANDHOLE	3.000	EACH
793-12.01	DIG SPLICE PIT 80 C.F.	2.000	EACH
793-13.09	2IN SCHEDULE 40 PVC	23.000	L.F.
793-13.22	3 DUCT FORMATION @ 36IN DEPTH	72.000	L.F.
793-14.13	1 1/2IN INNERDUCT	2,656.000	L.F.
793-16.22	GROUND BED	3.000	EACH
793-16.41	DIRECTIONAL BORE 1.5IN INNERDUCT X 3	821.000	L.F.
793-98.06	REMOVE PEDESTALS	5.000	EACH

() Item will be bid as lump sum.

