



**STATE OF TENNESSEE  
DEPARTMENT OF TRANSPORTATION**

**CONSTRUCTION DIVISION**  
SUITE 700, JAMES K. POLK BUILDING  
505 DEADERICK STREET  
NASHVILLE, TENNESSEE 37243-1402  
(615) 741-2414

**JOHN C. SCHROER**  
COMMISSIONER

**BILL HASLAM**  
GOVERNOR

**November 27, 2017**

**Re:           ADDENDUM #6**  
**Contract No. DB1601**  
**County:     Maury**

To Whom It May Concern:

This addendum revises the procurement schedule/submittal deadlines and revises the RFP Books  
Also, this addendum revises Project No. 3

"The Design Builder shall install Controlled Access fencing from where it currently ends on SR-396  
(Saturn Parkway) to beyond the GM Entrance / Exit Intersection as depicted in the attached exhibit.  
Attached is an exhibit that depicts the limits of CA Fence. The CA fence shall be 6' chain link fence as  
specified in Std. Dwg. S-F-10B."

Attached are the revised sheets.

It is the bidder's responsibility to notify all affected manufacturers, suppliers and subcontractors of this  
change.

Sincerely,

A handwritten signature in cursive script, appearing to read "Lia Obaid".

Lia Obaid, P.E.  
Construction Division

DATE	2014	PROJECT	SR 396
TIME	TS	LOCATION	MAURY COUNTY
FILE NO.		DATE	11/10/14



OFFICE OF TRANSPORTATION  
 DEPARTMENT OF TRANSPORTATION  
 FIGURE 3  
 SATURN  
 PARKWAY  
 EXTENSION

PROP. CA  
 FENCE

TECHNICAL SUPPORT  
 SATURN PARKWAY EXTENSION  
 PIN 123399.00  
 MAURY COUNTY



DATE	11/10/14
PROJECT	SR 396

PROJECT LOCATION: SR 396, MAURY COUNTY, TN  
 PROJECT NUMBER: 123399.00

**DESIGN-BUILD  
RFP CONTRACT BOOK 1  
INSTRUCTIONS TO  
DESIGN-BUILDERS (ITDB)**

**State Route 396, Saturn Parkway Extension,  
Maury County- TENNESSEE**

**PROJECT IDENTIFICATION NUMBER (PIN 114169.00)  
CONTRACT NUMBER: DB1601**



**August 31, 2017**

**Addendum#1 September 6, 2017**

**Addendum#3 October 16, 2017**

**Addendum#5 November 17, 2017**

**Addendum#6 November 27, 2017**

Department, city(ies) and county(ies) in which the Project or any part of it are located.

Prohibited communications do not include contact with regulatory/county/city officials for the limited purpose of obtaining information regarding available detour routes and conditions associated with such use or regulatory/county/city guidelines.

## 5. **PROCUREMENT SCHEDULE/SUBMITTAL DEADLINES**

The Procurement Schedule and submittal deadlines are set out below. The Department will not consider requests on any submittal received by the Department after the deadline for its submittal date stated below. The Department will not consider requests on any submittals pertaining to an Addendum after the deadline established in the Addendum.

Deadline for Submittal of Alternate Technical Concepts (Dependent on Completion the NEPA Document)	<b>On or before September 29, 2017 4:00 p.m., CT.</b>
Deadline for Response to Alternate Technical Concepts	<b>October 20, 2017 4:00 p.m., CT.</b>
Deadline for Submittal of Initial Right-Of-Way Acquisition(Exhibit)	<b>October 27, 2017</b>
Deadline for Response to Initial Right-Of-Way Acquisition	<b>November 3, 2017</b>
Deadline for Submittal of Question Requests, and Requests for QPL Determination	<b>November 9, 2017 4:00 p.m., CT.</b>
Anticipated Deadline for Issuance of Last Addendum	<b>November 27, 2017 4:00 p.m., CT.</b>
Technical Proposal and Price Proposal Due Date and Time	<b>December 15, 2017 4:00 p.m., CT.</b>
Public Price Proposal Opening	<b>December 22, 2017 9:00 a.m., CT.</b>
Anticipated Award of DB contract, or rejection of all proposal	<b>On or before December 29, 2017</b>
Anticipated Issuance of Initial Notice to Proceed	<b>January 12, 2018</b>

The Department will not consider any late Proposals. Proposals received after the Proposal Due Date will be returned to the unopened. The Department will not consider

**DESIGN-BUILD  
RFP CONTRACT BOOK 2  
CONTRACT**

**TENNESSEE DEPARTMENT OF TRANSPORTATION**

**State Route 396, Saturn Parkway Extension,**

**Maury County- TENNESSEE**

**CONTRACT NUMBER: DB1601**



**August 31, 2017**

**Addendum#6 November 27, 2017**



## APPENDIX A

### *SUPPLEMENTAL SPECIFICATIONS TO THE STANDARD SPECIFICATIONS*

The following, revised as noted, incorporates the Supplemental Specifications by reference for bidding purposes and will be printed with the contract after award. These Supplemental Specifications may be obtained from the Department’s website:

<http://www.tn.gov/tdot/section/tdot-construction-division>

Supplemental Specifications to the Standard Specifications Revision    Date

Supplemental Specification to Section 100 -----	11/06/2017
Supplemental Specification to Section 200 -----	5/15/2017
Supplemental Specification to Section 300 -----	5/15/2017
Supplemental Specification to Section 400 -----	11/06/2017
Supplemental Specification to Section 500 -----	11/06/2017
Supplemental Specification to Section 600 -----	11/06/2017
Supplemental Specification to Section 700 -----	11/06/2017
Supplemental Specification to Section 900 -----	11/06/2017

**S T A T E**

**O F**

**T E N N E S S E E**

(Rev. 3-30-15)

(Rev. 11-16-15)

(Rev. 6-27-16)

(Rev. 12-2-16)

(Rev. 5-15-17)

(Rev. 11-6-17)

January 1, 2015

**Supplemental Specifications - Section 100**

**of the**

**Standard Specifications for Road and Bridge Construction**

**January 1, 2015**

**Subsection 101.03** (pg. 10) 5-15-17; Add the following definition for Specialty Items:

“**Specialty Item.** Work items identified in the contract which are not bid normally associated with highway construction and require highly specialized knowledge, abilities, craftsmanship, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract in general, these items are to be limited to minor components of the overall contract.”

**Subsection 102.11** (pg. 18), 3-30-15; Add the following to the second paragraph:

“The Department may retain the Proposal Guaranty, not as a penalty, but as liquidated damages in the event a bidder does not have a license at the time of award.”

**Subsection 104.04** (pg. 27), 3-30-15; Add the following as the first full paragraph on page 27:

“If a holiday falls on Saturday or Sunday, do not close lanes or restrict traffic from the preceding Friday at 6 am to the following Monday at 6 am.”

**Subsection 105.03** (pg. 38), 12-2-16; Add the following to the end of the section:

“Products listed on the QPL which fail to comply with Departmental performance expectations shall be removed from the QPL. Products removed from the QPL shall be replaced with an equivalent product from the QPL. At the Departments discretion, an equitable adjustment may be made to the contract for invoice price deviations.”

**Subsection 105.03** (pg. 38), 6-27-16; Add the following to the end of the section:

“All products must be listed on the Qualified Products List (QPL) and perform as specified at the time of use regardless of Letting date. Any products removed from the QPL or that do not perform as specified, must be supplied or replaced at the Contractor’s expense.”

**Subsection 105.06** (pg. 40), 3-30-15; Replace 2<sup>nd</sup> sentence of 1<sup>st</sup> paragraph with

“The contractor must attend a preconstruction conference arranged by the Engineer.”

**Subsection 105.10** (pg. 46), 5-15-17; Revise 2<sup>nd</sup> sentence of the first paragraph:

“Such inspection may extend to any part or to all of the Work and to the preparation, fabrication, or manufacture of materials to be used.”

**Subsection 105.11** (pg. 46), 5-15-17; Revise the 1<sup>st</sup> sentence:

“The Engineer or its representative will inspect all materials and each part or detail of the Work .”

**Subsection 105.13** (pg. 48), 5-15-17; Remove the 2<sup>nd</sup> paragraph.

**Subsection 105.15** (pg. 49), 5-15-17; Remove last paragraph:

**Subsection 106.06** (pg. 61), 5-15-17; Revise the first paragraph of A. and subsection A.2:

“Provide a Type A Laboratory consisting of a building, room, or dedicated area having at least 120 square feet of floor area with a minimum width of 8 feet and a minimum height of 7 feet. Provide laboratory space that is floored, roofed, sealed inside, weather-tight, and furnished with electricity. Furnish the space with adequate work benches, cabinets, and drawers. Provide suitable heat and air conditioning, and equip the laboratory with a laboratory oven capable of maintaining a temperature of 230 °F ± 9 °F. Stove tops and hot plates may be used to determine moisture conditions of aggregates. Provide lights, electrical outlets, and adequate ventilation for the tests being performed.

When the determination of aggregate gradation is required, furnish the following equipment:

1. Scales of appropriate capacity and design to weigh the required samples. Scales are to be sensitive to within 0.2% of the sample to be weighed. Provide standard weights for scale calibration.
2. Screens of appropriate size and mesh to separate the samples into the required series of sizes. Woven wire cloth shall conform to AASHTO M 92. Screens for running gradations of coarse aggregates shall meet AASHTO T27.
3. A mechanical shaker approved by the Engineer and suitable for running both coarse and fine aggregate.



4. Facilities to perform wash tests according to AASHTO T 11 that include an adequate and suitable water supply.”

**Subsection 107.08** (pg. 69), 5-15-17; Add the following to the end of the third paragraph:

“All costs associated with any support activities including obtaining permission from landowners, permits, and compliance are to be included in the bid cost for the project.”

**Subsection 107.08** (pg. 71), 11-6-17; Add the following as section E:

“E. Migratory Birds

The following procedure will be automatically implemented by TDOT, unless FWS approves in writing deviations due to special circumstances, or for a specific variance.

Cliff swallow and barn swallow nests, eggs, or birds (young and adults) will not be disturbed between April 15 and July 31. From August 1 to April 14, nests can be removed or destroyed, and measures implemented to prevent future nest building at the site (i.e., closing off area using netting).

Exceptions:

(1) If there are no eggs in the nests prior to April 15, TDOT will be allowed to destroy the nests and prevent further nest building at the site, by installing netting. Net openings shall be ½ inch or smaller after installation, and shall be installed securely and in such a manner that it will not pose a safety hazard. Absence of eggs prior to net installation must be documented by using appropriate means for determination, such as, but not limited to, site visits and photographs.

(2) If there are no birds (young or adult) left in any of the nests at a specific site prior to July 31, the nests can be removed or destroyed. Absence of birds must be documented by using appropriate means for determination, such as, but not limited to, site visits, photographs, and observations of no birds using the nests.

Osprey, Double Crested Cormorants, Great Horned Owls, Barn Owls, Black Vulture, and Eastern Phoebes:

If these avian species are encountered on a bridge project, TDOT Ecology should be contacted immediately for further assistance.

The Contractor will be assessed the amount of any and all fines and penalties assessed against and cost incurred by TDOT which are the result of the Contractor’s failure to comply with this Special Provision. TDOT will not be responsible for any delays or costs due to the Contractor’s failure to comply. Additional compensation or contract time due to noncompliance will not be granted.

All costs incurred with this specification will not be measured or paid for separately, but will be considered included in the contract unit prices bid for other items of the contract.”

**Subsection 108.01** (pg. 78) 5-15-17; Subletting of Contract, Add the following list of specialty items:

“Do not sublet, allow second tier sublet, sell, transfer, assign, or otherwise dispose of the Contract or any portion thereof or a right, title, or interest in the Contract without the Engineer’s written consent. If the Engineer consents to subletting or second tier

subletting a portion of the Contract, the Contractor shall self-perform work amounting to not less than 30% of the total original Contract cost. For items designated in the Contract as “specialty items,” the Contractor may sublet or second tier sublet this work and deduct the cost of such specialty items from the total original cost before computing the amount of the Work required to be self-performed by the Contractor with its own organization.

As stated above, unless there is a Special Provision 108A in the proposal, the following items are designated as Specialty Items:

- Item 105-01 - Construction Stakes, Lines and Grades
- Item 202-01.02 – Removal of Asbestos
- Item 209 - EPSC Item 411-12.\*\*Shoulder Scoring
- Item 501-03.12 – Concrete Shoulder Rumble Strip
- Item 602-03 - Steel Structures
- Item 602-04 - Steel Structures
- Item 602-10.13 / .14 - Navigational LightingItem 602-10.81 – Heat Straightening
- Item 603-02 - Repainting Steel Structures
- Item 603-05 - Containment and Disposal of Waste
- Item 604-04.01 - Applied Texture Finish (New Structures),
- Item 604-04.02 - Applied Texture Finish (Existing Structures)
- Item 604-04.62 - Clean and Texture Finish Median Barrier
- Item 604-05.31 - Bridge Deck Grooving (Mechanical)
- Item 604.07 – Retaining Wall
- Item 604-42.01 – Underwater Divers
- Item 606-26.05 – Core Drilling for Piles (Abandoned)Item 617 - Bridge Deck Sealant
- Item 624 – Retaining Wall Items
- Item 625-01.08,10,11 – Inclinator, Drilled Shaft Inspections
- Item 640 - Weigh Station Items
- Item 705 - Guardrail, Anchors, etc.
- Item 706 - Guardrail Items
- Item 707 - Fencing ItemsItem 712 - Traffic Control Items
- Item 713 - Signing Items
- Item 714 - Lighting Items
- Item 716 - Pavement Marking Items
- Item 720-03, 720-04, 720-05, 720-06, 720-07, 720-08, 720-09 – Railroad Highway Crossing
- Item 721-01.06 – Irrigation System Repair
- Item 721-10, 721-11.20, 721-11.30, 721-12 – Landscape and Irrigation Item 725 – ITS items
- Item 730 - Traffic Signal Items
- Item 7\*\* - Utility Items
- Item 750.01 – Mitigation Site
- Item 801 - Seeding
- Item 802 - Landscaping Items
- Item 803-01 - Sodding
- Item 805 - Erosion Control
- Item 806 - Project Mowing”

**Subsection 109.01** (pg. 98-100) 11-16-15; Measurement of Quantities, E. Weight; Remove the 12<sup>th</sup> paragraph and replace with the following:

“The scales shall be checked by an independent certified scale company. The check shall be performed on a semiannual basis; January through June and July through December. The results shall be maintained onsite and made available for review to Departmental personnel. If deficiencies are reported, all corrections shall be performed, documented, and verified prior to supplying material for TDOT projects.”

**Subsection 109.01** (pg. 98-99) 5-15-17; Measurement of Quantities, E. Weight, Modify the 6<sup>th</sup> paragraph to the following:

“Employ a Certified Public Weigher as defined in the Certified Public Weigher Law of 1981, Tennessee Code Annotated, Section 47-26-801, et seq., as amended. The Engineer will measure all applicable materials in accordance with the Certified Public Weigher Law and Department policy on scales approved by the Engineer. Provide weight (haul) tickets in accordance with Department policy and as directed by the Engineer. These requirements apply to entities located both inside and outside the state of Tennessee”

**Subsection 109.01** (pg. 98-100) 5-15-17; Measurement of Quantities, E. Weight, Modify the 12<sup>th</sup> paragraph to the following:

“The scales shall be calibrated and certified by an independent certified scale company. The calibration and certification shall be performed on a semiannual basis; January through June and July through December. Scales shall be validated on a quarterly basis to ensure their continued accuracy. Validation shall be made by a verified known weight, or other scales that are approved by the Department or other State agency. A verified known weight shall be checked for continued accuracy each time the scales are calibrated. The results shall be maintained onsite and made available for review to Departmental personnel. If deficiencies are reported, all corrections shall be performed, documented, and verified prior to supplying material for TDOT projects.”

**Subsection 109.01** (pg. 98-100), 11-9-17; E. Weights, Revise subsection to the following:

“E. Weight

The term “ton” will mean the short ton consisting of 2,000 pounds avoirdupois.

~~The Engineer will measure cement by the ton.~~

Unless otherwise specified, the Engineer will accept certified weights for materials measured or proportioned by weight that are shipped by rail or truck transport, provided that only the actual weight of the material used is paid for.

For bituminous materials, net certified scale weights or weights based on certified volumes in the case of rail or truck transport shipments, unless otherwise specified, will be used as a basis of measurement, subject to correction when bituminous material has been lost, wasted, or otherwise not incorporated in the Work.

In all cases where measurement of materials is based on certified weights, provide the Engineer with certified weigh bills showing the net tons of materials received in each shipment. The

Engineer will not pay for materials in excess of the amounts represented by the certified weigh bills.

When Certified Weigh Tickets are required for Asphalt Mixtures and Aggregate Materials, the following shall be listed on the ticket:

1. Date
2. Time
3. The ticket number
4. Gross weight of the loaded truck
5. Tare weight of the truck
6. Net weight of the material to be paid
7. Running Daily Total for the particular material
8. Truck number
9. Truck Legal limit

Employ a Certified Public Weigher as defined in the Certified Public Weigher Law of 1981, Tennessee Code Annotated, Section 47-26-801, et seq., as amended. The Engineer will measure all applicable materials in accordance with the Certified Public Weigher Law and Department policy on scales approved by the Engineer. Certified Weigher licenses shall be posted near the scale beam or weight indicator in full view at all times. Certified Weigher shall be the only person allowed to operate the scale or weigh recording equipment. Provide weight (haul) tickets in accordance with Department policy and as directed by the Engineer. These requirements apply to entities located both inside and outside the state of Tennessee.

Certified Weigher shall weigh each load with the maximum load not to exceed the legal limit established by law. The proposed haul route shall be known prior to deployment.

Provide a standard brand of platform truck scales with a sufficient rated capacity to weigh the maximum gross load to which they will be subjected. Do not use truck scales to measure weights in excess of the manufacturer's rated capacity. Clearly post the manufacturer's rated capacity on the scale manufacturer's plate and in the shelter provided for the weigher.

At the time of installation or modification of existing scales, test the scales before using to ensure they are within the allowable tolerances. Use a qualified scale technician to perform any alteration (e.g., electrical readout) or change in the rated capacity. Document all changes or alterations made by the scale technician and furnish a copy of the documentation to the Department.

House the recording mechanism of the scale in a suitable shelter furnished with adequate light, heat, chairs, tables, and storage drawers as needed for the convenience of the weigher. In addition, keep the scale platform and scale pit free of debris that could affect the accuracy of the scales.

Provide digital readout and scale printers as the primary weight indicator or as accessory equipment. The Department will inspect and approve all scale control and recording equipment.

Ensure the scale's accuracy within a tolerance of 0.5% ~~and with a minimum graduation value not greater than 100 pounds~~. Provide a straight approach at each end of the platform scale in the same plane as the platform and of sufficient length and width to ensure the level positioning of vehicles longer than the scale platform during weight determinations. Weigh each truck and trailer with no brakes set on any wheel. Locate the scale platform so that surface water will drain away from it and to allow for an adequate foundation of concrete or other approved materials. Construct the foundation of sufficient strength and durability to withstand repeated capacity loading without affecting the accuracy of the scales.

Check the scales as often as necessary to ensure their continued accuracy. If the scales cannot be checked within the time frame set by Department policy, the Engineer may give tentative approval, based on check truckloads weighed on other scales that are approved by the Department or other State agency. The scales shall be calibrated and certified by an independent certified scale company. The calibration and certification shall be performed on a semiannual basis; January through June and July through December. Scales shall be validated on a quarterly basis to ensure their continued accuracy. Validation shall be made by a verified known weight, or other scales that are approved by the Department or other State agency. A verified known weight shall be checked for continued accuracy each time the scales are calibrated. The results shall be maintained onsite and made available for review to Departmental personnel. If deficiencies are reported, all corrections shall be performed, documented, and verified prior to supplying material for TDOT projects.

Weigh tickets shall be certified either manually or electronically. If certified manually, the Certified Weigher shall sign his official registered signature and place his seal on the original ticket. The ticket shall be filled out in ink and delivered to the project site with the material.

~~Trucks used to haul material being paid for by weight shall be weighed empty at such times as the Engineer directs, and each truck shall bear a plainly legible identification mark.~~

For materials directly paid for by the ton, the Engineer will be furnished a daily recap of all materials delivered to the project. The daily recap sheet must list the ticket number, type of material by item number, and a quantity of materials for each load hauled. Any discrepancy between the certified weigh bills and the daily recap will be reviewed along with the contractor's initialed copy of weigh bills.

Due to possible variations in the specific gravity of aggregates, the tonnage used may vary from the proposal quantities and the Department will not make adjustments in the Contract unit price because of such variations.

The truck tare to be used in the weighing operation shall be the weight of the empty truck determined with full tank(s) of fuel and the operator seated in the cab. A daily weight shall be recorded at the beginning of each work day prior to use of truck. If preferred, a new tare may be determined for each load. When a new tare is obtained for each load, the requirement for full tank(s) of fuel shall be waived.

All weight of trucks shall be recorded to the nearest 20 pounds.

The cost of providing facilities and equipment for the accurate weighing, proportioning, or measuring of materials is incidental to the associated pay items in the Contract.”

**Subsection 109.02** (pg. 100-101), 11-9-17; Replace the last paragraph:

“Document on the Prompt Payment Certification Form the actual amount paid to all subcontractors, ~~ny certified Disadvantaged Business Enterprise (DBE) or certified Small Business Enterprise (SBE)~~ during the estimate period for which the certification is being made. Ensure all Disadvantaged Business Enterprise (DBE) or certified Small Business Enterprise (SBE) are listed and classified on the form, including DBE or SBE off-site haulers and DBE or SBE material suppliers”

**Subsection 109.04** (pg. 106), 3-30-15; Replace C. Force Account, 4. Equipment, c. with:

“Idle or standby cost will not be paid for more than 8 hours in a day or 40 hours in a week”.



**S T A T E**

**O F**

**T E N N E S S E E**

(Rev. 5-18-15)

(Rev. 7-13-15)

(Rev.11-16-15)

(Rev. 6-27-16)

(Rev. 12-2-16)

(Rev. 1-6-17)

(Rev. 5-15-17)

(Rev. 11-6-17)

January 1, 2015

**Supplemental Specifications - Section 400**

**of the**

**Standard Specifications for Road and Bridge Construction**

**January 1, 2015**

**Subsection 402.03** (pg. 282) 5-27-16; revise 0.2 to 0.05 in the range as shown in the 2<sup>nd</sup> paragraph:

“The distributor shall be designed, equipped, maintained, and operated so that bituminous material at even heat may be applied uniformly on variable surface widths at readily determined and controlled rates from 0.05 to 0.5 gallons per square yard, with uniform pressure, and with an allowable variation from any specified rate of plus or minus 0.02 gallons per square yard.”

**Subsection 403.02** (pg. 285-286) 12-2-16; Bituminous Materials, remove trackless tack information from specifications and reference the QPL for approved Emulsified Trackless Tacks, remove trackless tacks from Table 403.02-1:

“Emulsified Asphalt, SS-1, SS-1h, CSS-1, CSS-1h, TST-1P, CQS-1h, CQS-1hp.....904.03 or Approved Emulsified Trackless Tack from the QPL.

**Table 403.02-1: Tack Coat Application Temperatures**

<b>Material</b>	<b>Temperature Range</b>
SS-1, SS-1h, CSS-1, TST-1P, CQS-1h, CQS-1hp and CSS-1h	60 to 140 °F

**Subsection 403.02** (pg. 285-286) 11-16-15; Bituminous Materials, update the reference to 904.03, add TTT-3 to Table 403.02-1:

“Emulsified Asphalt, SS-1, SS-1h, CSS-1, CSS-1h, TST-1P, CQS-1h, CQS-1hp, TTT-1, TTT-2, TTT-3 .....904.03”

Table 403.02-1: Tack Coat Application Temperatures

Material	Temperature Range
SS-1, SS-1h, CSS-1, TST-1P, CQS-1h, CQS-1hp and CSS-1h	60 to 140 °F
TTT-1	160 to 180 °F
TTT-2	120 to 160 °F
TTT-3	100 to 180 °F

Subsection 403.05 (pg. 286) 11-16-15; A. Emulsified Asphalt, Add the following paragraph at the end of the subsection:

“Take a minimum of 3 cores throughout the length of the project for informational tack coat shear testing. Include the underlying layer. Not required for mats less than one inch thick.”

Subsection 403.05 (pg. 287) 11-16-15; ) B. Test Strip, modify the 2<sup>nd</sup> paragraph to update the rate as 0.08 and 0.12:

“If placing the bituminous material upon a milled surface, apply the tack material at a rate of between 0.08 and 0.12 gallons of applied emulsion per square yard.”

Subsection 403.05 (pg. 287) 6-27-16; revise the last sentence of the 2<sup>nd</sup> paragraph:

“If placing the bituminous material upon a milled surface, apply the tack material at a rate of between 0.08 and 0.12 gallons applied emulsion per square yard.”

Subsection 403.05 (pg. 287), 11-6-17; Revise the 1<sup>st</sup> sentence of the 1<sup>st</sup> paragraph:

“When the Contract requires bituminous material for fog sealing of shoulders, provide emulsified asphalt [meeting 403.02 or an item from QPL 40A](#) ~~meeting 403.02.~~”

Subsection 404 (pg. 289-293) 1-6-17; Remove the entire subsection. All specifications regarding Double Bituminous Surface Treatment has been incorporated into subsection 405. All references shall be updated to subsection 405.

Subsection 405 (pg. 294-298) 1-6-17; replace subsection 405 with the following:

“405.01 Description

This work consists of constructing a bituminous seal coat consisting of one or more applications each of bituminous material and cover aggregate.

*MATERIALS*

405.02 Materials

Provide materials as specified in:

Mineral Aggregate, Size Nos. 7, 8, 78, 89.....	903.13
Mineral Aggregate.....	903.14
Emulsified Asphalt, CRS-2p .....	904.03

Apply seal coat at a temperature range of 60 to 140 °F.

*EQUIPMENT*

405.03 Equipment

*Provide a power broom or other mechanical sweeping equipment, equipment for heating bituminous material, a pressure distributor meeting the requirements of 402.03, pneumatic-tire and steel-wheel rollers, self-propelled mechanical aggregate spreading equipment that can be adjusted so as to spread accurately at the specified rate, and such other equipment and small tools as may be required to perform the work in a satisfactory manner.*

*CONSTRUCTION REQUIREMENTS*

405.04 Limitations

Only apply bituminous material:

1. When the designated surface is dry, firm, and properly cured;
2. Between April 15 and October 1; and, unless otherwise directed,
3. When the ambient temperature in the shade and away from artificial heat is 70°F or more.

405.05 Preparing the Designated Surface

Before placing seal coat, clean all surfaces to be sealed by sweeping with a motorized broom to remove any loose material. Clean depressions and cracks not reached by the power broom using hand brooms or pressurized air.

Cover any utility installations to prevent adherence of the bituminous mixture. Suitable covering includes plywood disks, sand, craft paper, roofing felt or other approved methods. Remove the protective coverings before opening the road to traffic. The cost for these adjustments shall be included in the bid price for other items.

The Plans will indicate whether the surface is to be constructed on a treated or untreated subbase, a granular base, an asphalt base, or on an existing surface. The surface of the base or sub-base upon which the construction is to be placed shall meet the requirements of the applicable Section of Part 3, Bases and Subgrade Treatments, of these Specifications.

Condition existing surface, if called for on the Plans, as specified in 407.10. Condition existing mineral aggregate base as specified in 310.

Construct and maintain Prime Coat or Tack Coat, if shown on the Plans, as specified in 402 or 403, respectively.

405.06 Application

A. Applying Bituminous Material:

Have all equipment calibrated prior to starting work. The TDOT inspector shall be present during calibration to determine aggregate spread rate and distributor rates. Distributor trucks shall have proper calibration of spray equipment. Spray nozzles should be clean, properly angled, and appropriately sized for the desired application rate. Stop work if the distributor is not applying material properly, such as gaps in application or streaking.

Place a 500 ft. test strip for the bituminous seal coat at the beginning of the project to assure proper coverage and proper equipment calibration. The test section is to verify break time of emulsion and chip retention. The test strip shall be able to carry normal traffic within 3 hours. If normal traffic cannot be carried, the emulsion shall be adjusted and another test strip is required.

At least 14 working days before the scheduled start of construction of any bituminous seal coat, submit a sample of aggregate intended for use for the determination of the appropriate application rates of bituminous material and aggregate. Apply emulsified asphalt by pressure distributor at a uniform rate in accordance with Table 405.06-1 below. The exact rate will be established by the Engineer.

Table 405.06-1: Application Rates for Bituminous Material

Aggregate Size (per 903.22)	Aggregate Spread Rate (lb/yd <sup>2</sup> )	Emulsion Shot Rate (gal/yd <sup>2</sup> )
7	25 – 30	0.30 – 0.45
78	22 – 28	0.28 – 0.38
8	20 – 25	0.20 – 0.35
89	17 – 23	0.17 – 0.28

Before beginning each spread, place building paper across the roadway surface with the forward edge exactly coinciding with the end of the preceding covered spread. Start distributors on the paper, the width of which shall allow the full force of all nozzles to be in effect before the forward edge of the paper is reached. If required by the Engineer, also stop the spread on building paper. Remove the paper immediately after its use, and dispose of properly. Immediately correct all defects in application.

The length of spread of bituminous material shall not exceed that which trucks loaded with cover material can immediately cover.

The spread of bituminous material shall not extend more than 6 inches wider than the width covered by the cover material. Do not allow the bituminous material to chill or otherwise impair retention of the cover material.

Do not allow traffic on the bituminous material until it has been covered with mineral aggregate.

Treat areas that are inaccessible to the distributor with either hand sprays or pouring pots as directed by the Engineer.

#### B. Application of Double Bituminous Surface Treatment:

##### First Application

Apply the first application of emulsified asphalt using pressure distributors at a uniform rate established by the Engineer within the range of 0.30 to 0.38 gallons per square yard. Apply each spread of bituminous material so as not to be more than 6 inches wider than the width covered by the immediate spread of cover aggregate. Each width of spread shall not be less than half the surface to be treated.

Before beginning each spread, place building paper across the roadway surface with the forward edge exactly coinciding with the end of the preceding covered spread. Start distributors on the paper, the width of which shall allow the full force of all nozzles to be in effect before the forward edge of the paper is reached. If required by the Engineer, also stop the spread on building paper. Remove the paper immediately after its use, and dispose of properly. Immediately correct all defects in application.

Treat areas that are inaccessible to the distributor with hand sprays or pouring pots as directed by the Engineer.

If treating less than the full width of the roadway, do not spread the aggregate on the inside 6 inches of either the first or second application until the adjacent lane has been treated. Immediately following each application, uniformly cover the applied bituminous material with Size No. 7 mineral aggregate that is reasonably free of surface moisture.

Spread the aggregate at a rate between 24 and 30 pounds per square yard, as established by the Engineer, using a self-propelled mechanical spreader; except on short projects of 1/2 mile in length or less, self-propelled mechanical spreading equipment will not be required. Back the truck on the aggregate being spread, without driving on or over uncovered bituminous material.

The length of bituminous material spread shall not exceed that which trucks loaded with cover material can immediately cover.

##### Second Application

Apply the second application of emulsified asphalt in the same manner as the first application, at a uniform rate established by the Engineer within the range of 0.20 and 0.35 gallons per square yard.

Spread mineral aggregate, Size No. 8, in the same manner as the first spread at a rate established by the Engineer within the range of 16 to 28 pounds per square yard.

Immediately after each spread of cover aggregate, broom to achieve uniform coverage. Use a power source, which is independent of the drive train that propels the equipment, to power the revolving brooms of mechanical sweeping equipment. Place additional aggregate by hand on thin or bare areas.

**405.07 Spreading and Rolling Aggregate****A. Spreading**

Immediately after bituminous material has been applied, no more than two minutes, spread and embed the mineral aggregate cover in the bituminous material. Spread the aggregate as close to the application of bituminous material as is practicable, and cover each distributor load applied immediately. Aggregates shall be moistened and visually damp at the time of placement.

Spread the aggregate in accordance with the rates specified in Table 405.06-1. The exact rate will be established by the Engineer. Back the truck on the aggregate being spread, without driving on or over uncovered bituminous material. If treating less than the full width of roadway, do not spread the aggregate on the inside 6 inches of the bituminous spread until the adjacent lane is treated. Immediately after spreading the aggregate, perform hand-brooming to achieve uniform coverage. Place additional aggregate by hand on thin or bare areas.

The speed of the spreader shall be such that the aggregates are not rolling over, and starting and stopping of the spreader is minimized. Use of previously used (swept) aggregates is not permitted.

**B. Rolling – Bituminous Seal Coat**

Immediately after distributing the aggregate, roll the entire surface by moving in a longitudinal direction, beginning at the outer edges and progressing toward the center of the roadway, with each trip of the roller overlapping the previous trip by half the width of the rear wheel. Perform initial rolling with a self-propelled pneumatic tire roller, and follow with steel-wheel rolling. The amount and sequence of rolling shall be as directed by the Engineer. Complete the initial rolling of the aggregate within 1 hour after applying the bituminous material.

Use power brooms to correct irregularities by sweeping the aggregates from areas of thick or heavy distribution to areas of thin or light distribution. Then continue rolling using both steel-wheel and pneumatic rollers until the aggregate is thoroughly embedded in the bituminous material. The Engineer may require additional rolling at a later date. Redistribute excess or loose aggregate that was thrown out of place.

Slow moving traffic may use the section or roadway upon which the aggregate has been spread.

**Rolling and Curing – Double Bituminous Seal Coat**

Immediately after spreading and brooming the cover aggregate, roll the entire surface, beginning at the edges and progressing to the center. Begin rolling within 30 minutes after spreading the aggregate. Perform initial rolling with a self-propelled pneumatic tire roller, and follow with steel-wheel rolling. The amount and sequence of rolling shall be as directed by the Engineer.

Allow the first application of bituminous material and aggregate to cure for as long as deemed necessary by the Engineer before beginning the second application. Immediately before the second application of bituminous material, roll the surface with a steel-wheel roller.

For the second application of bituminous material and cover aggregate, repeat the same rolling and curing procedures as required for the first application.



The Contractor may allow slow-moving traffic to use sections of the roadway where the bituminous material has been covered with mineral aggregate.

**405.08 Shoulders**

Restore shoulders that have been disturbed by the Contractor’s construction operations at no cost to the Department. Remove all objectionable material placed on the shoulders by the Contractor as directed by the Engineer.

Construct shoulders, when specified, as provided for under **208**.

405.09 Maintenance and Protection

Maintain in a satisfactory condition each completed section of seal coat until the entire Project is complete. Maintenance shall include making repairs where failures occur, and maintaining the seal coat in a smooth uniform condition; and brooming, dragging, and rolling when required.

After the final application, maintain the work in a satisfactory condition for at least 10 calendar days. If all other requirements of the Contract have been fulfilled, the Department will not charge working time during the 10-day maintenance period against the Contract time.

For final cleanup, sweep up all excessive quantities of loose, dislodged cover aggregate that may have collected along the edge of the completed seal coat, and dispose of this material as directed by the Engineer.

405.10 Method of Measurement

The Department will measure Mineral Aggregate and Bituminous Material by the ton in accordance with **109**. The Department may use net certified weights as a basis of measurement for mineral aggregate, subject to correction for aggregate that is lost, wasted, or otherwise not incorporated into the Work.

405.11 Basis of Payment

The Department will pay for accepted quantities of Bituminous Seal Coat, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Bituminous Material	Ton
Mineral Aggregate	Ton

The Department will measure and pay for the work required to prepare the designated surface, as provided for under **405.05**, in accordance with the applicable Section or Subsection under which the work is performed.”

**Subsection 407.02** (pg. 300-301) 12-2-16; Replace the 4<sup>th</sup> paragraph:

“If anti-stripping additive, other than hydrated lime, meeting 921.06.B.1 is required, use approved in-line blending equipment, as specified in 407.04.A.6, to add it at the mixing plant or inject it at the asphalt terminal. Manufacture’s documentation that asphalt binders will continue to meet requirements listed in subsection **904** after the anti-stripping additive is added shall be provided

by the contractor with the mix design submittal. For mix designs submitted more than six months in advance, the documentation shall be resubmitted prior to use of the mix design with updated test results.”

**Subsection 407.02** (pg. 300) 11-16-15; Materials, add the following at the end of the fourth paragraph:

“If anti-stripping additive, other than hydrated lime, meeting **921.06.B.1** is required, use approved in-line blending equipment, as specified in **407.04.A.6**, to add it at the mixing plant or inject it at the asphalt terminal. Provide manufacture’s documentation ensuring asphalt binders will continue to meet requirements listed in Subsection **904** after anti-stripping additives are added.”

**Subsection 407.06** (pg. 327), 5-18-15; - A. Pavers. Replace the entire first paragraph with the following:

“Bituminous pavers shall be self-contained, power-propelled units provided with an activated screed, equipped to be heated, and capable of spreading and finishing courses of bituminous plant mix material in lane widths applicable to the specified typical section and thickness shown on the Plans. All screed extensions shall be full assembly extensions, including activated and heated screeds. Pavers shall include throw-back blades, reverse augers, or equivalent to place mix beneath the auger gearbox. Auger extensions shall be incorporated in a manner such that the maximum distance from the augers to the end plate shall be 18 inches. Screed extensions may extend beyond the 18-inch maximum from auger extensions only when extending for short-term temporary deviations in pavement width such as driveways. Do not use strike-off boxes, with the exception of sections with continuously varying width.”

**Subsection 407.11** (pg. 332) 12-2-16; Add the following to the paragraph below Table 407.11-1:

“Minimum temperature for OGFC mixes shall be 280°.”

**Subsection 407.15, C. Test Strips.** (pg. 340-341) 11-16-15; Add the following paragraph after the 7<sup>th</sup> paragraph of the subsection:

“Take an additional 3 cores after placement of the surface layer on the tack coat test strip described in subsection **403.05.B**. Include the underlying pavement layer for shear testing. These cores will be for informational testing only. Not required for mats less than one inch thick”

**Subsection 407.15** (pg. 341) 6-27-16; remove the 2<sup>nd</sup> sentence of the 8<sup>th</sup> paragraph:

“Take cores on the test strip at ten randomly selected locations as designated by the Engineer. Provide these cores to the Department for use in calibrating the nuclear gauge and to verify that the average density of the test strip meets the density requirements of the specifications. The Department will report all densities using the corrected nuclear gauge readings. Correction factors are specific to the nuclear gauges used during the test strip construction. If a different nuclear gauge needs to be used for acceptance, it will be necessary to cut new cores from the ongoing pavement construction to calibrate the new gauge.”

**Subsection 407.15** (pg. 341) 12-2-16; remove “randomly selected” from 1<sup>st</sup> sentence of the 8<sup>th</sup> paragraph as follows:

“Take cores on the test strip at ten locations as designated by the Engineer.”

**Subsection 407.15 A. 3. c.** (pg. 337-338) 5-15-17; update 10,000 square yards to 1,000 tons:

“c. Projects containing less than 1,000 tons or bituminous pavement.”

**Subsection 407.20 A.** (pg. 345), 11-6-17; Revise the second paragraph as follows:

“The Department will pay for liquid anti-strip additive and hydrated lime anti-strip additive based on certified ~~documentation invoices~~ of material costs not to exceed \$15 per gallon and \$90 per ton, respectively.”

**Subsection 407.20** (pg. 346) 5-18-15; Basis of Payment; B. Acceptance of Mixture; Modify the last paragraph to revise 500 tons to 1000 tons:

“When the total plan quantity of any mix is less than 1000 tons, the Department will accept the mix on the basis of visual inspection and Contractor Quality Control certification. The Department may run extraction, gradation analysis, or other tests deemed necessary for acceptance purposes.”

**Subsection 407.20** (pg. 348) 11-16-15; Table 407.20 – 2, make the following changes:

**Table 407.20-2: Acceptance Schedule of Payment  
(Asphalt Plant Mix Characteristics)**

Characteristics	Pay Factor	Average Arithmetic Deviation of the Lot Acceptance Test from the JMF	
		1 Test	2 Tests or more
Asphalt Cement Content <sup>(1)</sup>	1.00	0.00-0.30	0.00-0.25
(Extraction or ignition oven)	0.95	0.31-0.35	0.26-0.30
	0.90	0.36-0.40	0.31-0.35
	0.80 <sup>(2)</sup>	over 0.40	over 0.35
Gradation	1.00	0.00-6.50	0.00-5.70
3/8 inch sieve and larger	0.95	6.51-7.08	5.71-6.20
	0.90	7.09-7.66	6.21-6.69
	0.80 <sup>(2)</sup>	over 7.66	over 6.69
Gradation	1.00	0.00-4.62	0.00-4.00
No. 4 sieve <sup>(3)</sup>	0.95	4.63-5.20	4.01-4.50
	0.90	5.21-5.77	4.51-5.00
	0.80 <sup>(2)</sup>	over 5.77	over 5.00

**Subsection 407.20** (pg. 350) 11-16-15; B. 5. Acceptance for Mix Density on the Roadway, Replace the entire 2<sup>nd</sup> paragraph with the following:

“For density testing purposes, the Department will divide the pavement into lots of 1,000 tons. Five density tests will be performed in each lot and the average results compared with the requirements specified in Tables 407.15-1 to 407.15-4. At the beginning of a project or at any

time it is deemed advisable, the Department may consider smaller lots to evaluate compaction methods or for other reasons as approved or directed by the Engineer.”

**Subsection 411.03** (pg. 363) 11-16-15; 2. Recycled Asphalt Shingles (RAS), change 5% to 3% in the 1<sup>st</sup> sentence of the 1<sup>st</sup> paragraph.

“Recycled Asphalt Shingles (RAS) may be included to a maximum of 3% of the total weight of mixture.”

**Subsection 411.03 B. Anti-strip Additive** (pg. 365) 6-27-16; revise the 2<sup>nd</sup> paragraph:

“Mix an approved anti-strip agent with the asphalt cement at the dosage as specified in **921.06.B.**”

**Subsection 414.02** (pg. 369) 11-16-15; Materials, add the following paragraph to the end of the subsection:

“Ensure that no deleterious material is introduced into aggregate stockpiled at project site.”

**Subsection 414.02** (pg. 369) 11-6-17; Revise the last sentence:

“For a slurry seal, use a Type CQS-1h emulsified asphalt. For micro-surfacing use a type CQS-1hp or CSS-1hp emulsified asphalt.”

**S T A T E**

**O F**

**T E N N E S S E E**

(Rev. 5-18-15)

(Rev. 11-16-15)

(Rev. 5-15-17)

(Rev. 11-6-17)

January 1, 2015

**Supplemental Specifications - Section 500**

**of the**

**Standard Specifications for Road and Bridge Construction**

**January 1, 2015**

**Subsection 501.03** (pg. 395), 5-18-15; 3. Mix Design Submittal, Replace the first paragraph with the following:

“Instead of the above mix design submittal, a request to use an existing design may be submitted for approval provided the design has been used on a state funded project within the last six (6) months. The approval of this concrete design submittal will not relieve the Contractor of the responsibility of providing concrete meeting the requirements of these Specifications. A temporary mix design may be issued if the 7-day or 14-day compressive strengths exceed the required 28-day strengths.”

**Subsection 501.03 A. Proportioning** (pg. 395) 5-15-17; Add water as 22. on the list of Design Submittal requirements, update the paragraph below the list to add water requirements:

**“A. Proportioning**

**3. Design Submittal.** Include the following information as a minimum in the proposed concrete design submittal:

1. Source of all aggregate
2. Brand and type of cement
3. Source and class of fly ash (if used)
4. Source and grade of ground granulated blast furnace slag (if used)
5. Specific gravity of cement
6. Specific gravity of fly ash (if used)
7. Specific gravity of ground granulated blast furnace slag (if used)
8. Admixtures (if used)
9. Gradation of aggregates
10. Specific gravities of aggregates (saturated surface dry)
11. Air content (if air entrainment is used)
12. Percentage of fine aggregate of the total aggregate (by volume)
13. Slump
14. Weight per cubic yard
15. Yield
16. Temperature of plastic concrete
17. Water/cement ratio (pound/pound)
18. 7-day compressive strength [minimum of two 4-inch x 8-inch cylinders]
19. 14-day compressive strength [minimum of two 4-inch x 8-inch cylinders]

- 20. 28-day compressive strength [minimum of two 4-inch x 8-inch cylinders]
- 21. Weight of each material required to produce a cubic yard of concrete
- 22. Water – submit testing results per Tables 921.01-1 & 921.01-2

Instead of the above mix design submittal, a request to use an existing design may be submitted for approval provided the design has been used on a state funded project within the last six (6) months. When submitting for the use of an existing mix design, the most current water testing results per 921.01 shall accompany the submittal. The approval of this concrete design submittal will not relieve the Contractor of the responsibility of providing concrete meeting the requirements of these Specifications. A temporary mix design may be issued if the 7-day or 14-day compressive strengths exceed the required 28-day strengths.”

**Subsection 501.03** (pg. 399-402) 11-16-15; B. Quality Control and Acceptance of Concrete, adjust the following:

- “1. Test to determine aggregate gradations (AASHTO T 27 with AASHTO T 11 when required). Conduct a combined belt gradation before work starts and at least daily to verify consistency if using a dynamic, multi-aggregate feed system.
- 3. Calibrate the weighing systems, aggregate feed flow rate and weigh bridges, water meters, and admixture dispensing systems before starting production.
- 4. Ensure accurate weighing or flow rate of the aggregates and cement, the proper metering of water and admixtures, and the quality of water.
- 6. Adjust mix proportions due to actual moisture content of both coarse and fine aggregates, with moisture content determined according to AASHTO T 255. If using a dynamic aggregate weighing system, multi-aggregate proportioning adjustments are to be made by using an in-bin moisture sensor.”
- 7. Conduct slump (AASHTO T119) or slump flow (ASTM C1611) and air tests (AASHTO T152).

Page 401- “Make, cure, and transport all early break cylinders (7-14 day, etc.) according to AASHTO T 23, and deliver to the Regional laboratory or other established satellite laboratories for testing. Make all early break cylinders (7-14 day, etc.) for self-consolidating concrete according to ASTM C1758, and deliver to the Regional laboratory or other established satellite laboratories for testing.”

Page 402 - “Correct batch weights or aggregate feed flow rates to compensate for surface moisture on the aggregate at the time of use. The Contractor...”

**Subsection 501.04** (pg. 402) 11-16-15; replace the following:

**“A. Batching Plant, Multi-Aggregate Feed System, and Equipment,**

- 1. General. The batching plant shall include bins, weighing hoppers or belt feeds with weigh bridges and load cells, and scales. If using cement in bulk,...
- 2. Bins and Hoppers- Add the following new paragraph under the existing paragraph

For multi-aggregate feed systems, provide bins as noted with variable size openings and variable speed belts. Each bin must have a calibrated moisture sensor to adjust aggregate feed flow rates. Assure consistent, uninterrupted aggregate flow and consistent belt speeds once aggregate feed system is calibrated.

- 3.Scales- Add the following new paragraph under the last paragraph in the section.

For multi-aggregate feed systems, provide a dual idler weight bridge with load cells to accurately weigh the actual aggregate flow rate.”



**Subsection 501.04 A. 1.** (pg. 402), 11-6-17; General, Add the following after the first paragraph:

“All producers of concrete shall be on the Department’s approved producer list and be actively certified by the National Ready Mixed Concrete Association (NRMCA) Plant Certification Program.”

**Subsection 501.04 B. 3.** (pg. 403), 11-6-17; Truck Mixers and Truck Agitators, Add the following to the beginning of the first paragraph:

“Truck mixers shall be certified by the National Ready Mix Concrete Association (NRMCA) Delivery Vehicle Certification Program Option A or Option B.”

**Subsection 501.04** (pg. 404) 11-16-15; B. Mixers, removed the complete 4th paragraph.

**Subsection 501.12 – Placing Concrete** (pg. 413-415) 5-15-17; replace the subsection:

#### **“501.12 Placing Concrete**

Either unload the concrete into an approved spreading device, or deposit it directly on the base, and mechanically spread the concrete in a manner that prevents segregation of the materials. When using central or transit mixed concrete, deposit it in an approved spreader. Place the mixture so as to minimize rehandling and relocation from point of placement. The mechanical spreader will not be required on areas too small to accommodate the paving equipment, projects that contain 10,000 square yards or less of concrete paving, and on variable width sections and ramps. Placing shall be continuous between transverse joints without the use of intermediate bulkheads. Do not place concrete on frozen grade.

Perform any necessary hand spreading with shovels or other approved tools. Do not allow workmen to walk in the freshly mixed concrete with boots or shoes coated with earth or other foreign substances.

If placing concrete adjacent to a previously constructed lane of pavement and mechanical equipment is to be operated on this existing lane of pavement, that lane shall meet the requirements for opening to traffic specified in **501.22**. If the existing lane is to only carry finishing equipment, the Contractor may begin paving the adjoining lanes after 7 days.

Deposit concrete as near to expansion and contraction joints as possible without disturbing them; do not dump concrete from the discharge bucket or hopper onto a joint assembly unless the hopper is well centered on the joint assembly.

Immediately remove all concrete materials that may fall on or be worked into the surface of a completed slab using approved methods.

When using the slip-form method of concrete paving, place the concrete with an approved slip-form paver meeting the requirements of **501.04.D.11**.

Ensure that the sliding forms are rigidly held together laterally to prevent spreading of the forms. The forms shall trail behind the paver for such a distance that no appreciable slumping of the concrete will occur and so that necessary finishing can be accomplished while the concrete is still within the forms. Before the concrete has hardened, correct any edge slump of the pavement, exclusive of edge rounding, in excess of 1/4 inch.

Operate the slip-form paver with as nearly a continuous forward movement as possible, and coordinate all operations of mixing, delivering, and spreading of concrete so as to provide uniform progress while minimizing the stopping and starting of the paver. If, for any reason, it is necessary to stop the forward movement of the paver, also immediately stop the vibratory and tamping elements. Apply no tractive force

to the machine, other than that which is controlled from the machine. Replace slabs with random cracks before completion of paving operations.

Contractor may choose to utilize a single lift or two lift paving process according to the following requirements.

#### **A. Single Lift Pavement**

Use vibrators to thoroughly consolidate the concrete against and along the faces of all forms and along the full length and on both sides of all joint assemblies. Do not allow vibrators to come in contact with a joint assembly, the grade, or a side form. Do not operate the vibrator for longer than 5 seconds in any one location.

The Contractor may only use hand-operated vibrators on projects containing 10,000 square yards or less of concrete paving and on variable width sections. Only operate vibrators mounted on a machine while the machine is in motion.

Equip the slip-form paver with vibrators meeting the applicable requirements of **501.04.D.1** to vibrate the concrete for the full width and depth of the strip of pavement being placed.

#### **B. Two Lift Composite Pavement**

When placing two lift composite pavements, the upper lift shall be of a lesser thickness as designated by contract design. It shall be placed such that the result is a wet-on-wet application. The lower lift will be one foot less in width than the upper lift.

Paving operations shall be adjusted and approved by the Engineer as necessary to assure a wet-on-wet monolithic pavement section. If the bonding between lifts or the consolidation of concrete is determined to be unsuitable by the Engineer, the lower lift shall be removed and replaced prior to the upper lift placement.

**1. Lower Lift.** Uniformly spread concrete with a spreader or slipform machine. Internal vibration will be required for the lower lift. Tie bars and dowel bars (with the use of dowel baskets) shall be placed in the lower lift at mid-depth of the finished concrete pavement thickness. The lower lift shall not require curing, texturing, or sawing before the upper lift is placed. The lower lift shall be struck off to provide a nominal lower lift thickness that complies with the pavement design. The upper lift shall be struck off to allow for the finished total pavement to conform to the cross section shown in the contract plans.

**2. Upper Lift.** Place the upper lift within 45 minutes following the placement of the lower lift. Placement of the upper lift shall be such that intermingling of the two concrete mixtures is minimal. External vibration for the upper lift will be allowed if proper consolidation and finishing can be demonstrated in accordance with **501.16**. Dowel bars can be inserted during the placement of the upper lift. Cure the upper lift only in accordance with **501.18**. At no time shall the total thickness be less than shown on the pavement design and the cross section shown in the contract plans.

Frequency of the vibrators shall be established based on the workability of the concrete mixture and past experiences. Electronic, internal, T-shaped, poker vibrators shall be used. Other types of vibrating equipment may be approved by the Engineer. Vibrator impulses shall be delivered directly to the concrete and the intensity of vibration shall be sufficient to consolidate the concrete thoroughly and uniformly throughout the depth and width of the lift. Increase in the speed of the vibrators will be allowed with the permission of the Engineer.

A paving plan shall be supplied to the Engineer for review and approval prior to pouring. The plan shall document procedures to ensure consistency of material properties during concrete placement and finishing,

identify and eliminate potential for load misidentification, and maintain speed of production and paving. Concrete for each lift shall be produced from the same ready-mix facility.”

**Subsection 501.17** (pg. 424) 11-16-15; A. Surface Testing, modify the following:

- “3. Ramps where the design speed is greater than 40 miles per hour
  - (a) Test sections shall terminate 100 feet from a stop or slow speed yield condition
  - (b) Superelevated sections greater than 40 miles per hour design speed must be ground in accordance with **Table 501.17-1**
- 4. Ramps where the design speed is 40 miles per hour or less
  - (a) Test sections shall terminate 100 feet from a stop or slow speed yield condition
  - (b) Superelevated sections with a design speed of 40 miles per hour or less must be ground in accordance with **Table 501.17-2**

**Subsection 501.17** (pg. 425) 11-16-15; B. Pay Factors and Required Corrective Action, modify the following:

“Payment factors and required corrective actions relative to profile indexes for ramps with design speeds of 40 MPH or less shall conform to Table 501.17-2.

Table 501.17-2: Pay Factors & Corrective Action for Ramps with Design Speeds of 40 mph or less

<b>Profile Indexes</b>	<b>Pay Factor</b>	<b>Corrective Action</b>
<10 inches per mile	105%	None
10 to < 20 inches per mile	100%	None
20 to < 23 inches per mile	98%	Grind to 20 inches per mile
23 plus inches per mile	95%	Grind to 20 inches per mile

**Subsection 501.26 – Basis of Payment** (pg. 434) 5-15-17; add the following sentence to the 7<sup>th</sup> paragraph of the subsection:

“The Department will pay for additional concrete, measured in accordance with **501.25**, at the purchase price, F.O.B. the unloading point, as verified by invoices, with no compensation allowed for further handling. The State will be reimbursed from monies due the Contractor for a decrease in concrete measured in accordance with **501.25** in an amount equal to the purchase price of the cement, F.O.B. the unloading point. No payment will be allowed for any changes in the proportions of the aggregates. **No additional payment will be made if two-lift composite pavement alternate is selected.**”

**S T A T E**

**O F**

**T E N N E S S E E**

(Rev. 5-18-15)

(Rev. 11-16-15)

(Rev. 6-27-16)

(Rev. 12-2-16)

(Rev. 5-15-17)

(Rev. 11-6-17)

January 1, 2015

**Supplemental Specifications - Section 600**

**of the**

**Standard Specifications for Road and Bridge Construction**

**January 1, 2015**

**Subsection 602.17** (pg.459-477), 12-2-16; Entire Subsection: Replace all references to AASHTO M164 and AASHTO M253 with ASTM F3125, Grade A325 and A490

**Subsection 602.17** (pg. 459) 12-2-16; modify the first paragraph of A.:

“All high strength bolts, or equivalent fasteners, tightened to a high tension shall be coated with permitted coatings in accordance with ASTM F3125 for their -respective grade. Use the bolts in holes conforming to 602.06, 602.07, and 602.08. All Grade A325 and A490 bolts, except Type 3 bolts used in weathering steel, shall be coated. Permitted coatings for Grade A325 and Grade A490 bolts are listed in ASTM F3125, Annex A1.”

**Subsection 602.17** (pg. 465–469), 12-2-16; Update Tables:

**Table 602.17-1: Minimum Bolt Tension <sup>(1)</sup>**

<b>Bolt Diameter (inches)</b>	<b>Bolt Tension (pounds)</b>	
	<b>(GradeA325)</b>	<b>GradeA490 Bolts</b>
½	12,000	15,000
5/8	19,000	24,000
¾	28,000	35,000
7/8	39,000	49,000
1	51,000	64,000
1-1/8	64,000	80,000
1-1/4	81,000	102,000
1-3/8	97,000	121,000
1-1/2	118,000	148,000

<sup>(1)</sup> Equal to 70% of the specified minimum tensile strength of bolts.

Bolt Diameter (inches)	Grade A325	Grade A490
	Snug Tension (kips)	Snug Tension (kips)
1/2	1	1
5/8	2	2
3/4	3	4
7/8	4	5
1	5	6
1-1/8	6	8
1-1/4	8	10
1-3/8	10	12
1-1/2	12	15

Table 602.17-3: Minimum Installation Tension

Bolt Diameter (inches)	Grade A325	Grade A490
	Tension (kips)	Tension (kips)
1/2	12	15
5/8	19	24
3/4	28	35
7/8	39	49
1	51	64
1-1/8	64	80
1-1/4	81	102
1-3/8	97	121
1-1/2	118	148



Table 602.17-4: Rotation from Snug Condition

<b>Bolt Length (measured in Step 1)</b>	<b>Grade A325 Required Rotation</b>	<b>Grade A490 Required Rotation</b>
Up to and including 4 diameters	2/3	2/3
Over 4 diameters, but not exceeding 8 diameters	1	5/6
Over 8 diameters to 12 diameters	1-1/6	1

Table 602.17-5: Turn Test Tension

<b>Bolt Diameter (inches)</b>	<b>Grade A325 Tension (kips)</b>	<b>Grade A490 Tension (kips)</b>
1/2	14	17
5/8	22	28
3/4	32	40
7/8	45	56
1	59	74
1-1/8	74	92
1-1/4	94	117
1-3/8	112	139
1-1/2	136	170

Table 602.17-6

<b>Bolt Length (measured in Step 1)</b>	<b>Required Rotation (All Grades)</b>
Up to and including 4 diameters	1/3
Over 4 diameters, but not exceeding 8 diameters	1/2

Table 602.17-7

Bolt Diameter (inches)	Grade A325 Torque (ft-lbs)	Grade A490 Torque (ft-lbs)
1/2	150	180
5/8	290	370
3/4	500	630
7/8	820	1020
1	1,230	1540
1-1/8	1,730	2160
1-1/4	2,450	3050
1-3/8	3,210	3980
1-1/2	4,250	5310

Table 602.17-8

Bolt Length (measured in Step 1)	Additional Required Rotation Grade A325	Additional Required Rotation Grade A490
Up to and including 4 diameters	1/3	¼
Over 4 diameters, but not exceeding 8 diameters	1/2	1/3

Table 602.17-9: DTI Requirements for A325 Bolts

Bolt Diameter (inches)	Verification Tension (kips)	Maximum Verification Refusals	DTI Spaces	Minimum Installation Refusals
1/2	13	1	4	2
5/8	20	1	4	2
3/4	29	2	5	3
7/8	41	2	5	3
1	54	2	6	3
1-1/8	67	2	6	3
1-1/4	85	3	7	4
1-3/8	102	3	7	4
1-1/2	124	3	8	4

Table 602.17-11

Bolt Diameter (inches)	Bolt Tension (kips)	
	AASHTO M 164 Bolts (ASTM A325)	ASTM A490 Bolts
1/2	13	16
5/8	20	25
3/4	29	37
7/8	41	51
1	54	67
1-1/8	67	84
1-1/4	85	107
1-3/8	102	127
1-1/2	124	155

Table 602.17-12

Bolt Diameter (inches)	Number of Spaces	
	Bolts (GradeA325)	Grade A490 Bolts
1/2	4	N/A
5/8	4	N/A
3/4	5	6
7/8	5	6
1	6	7
1-1/8	6	7
1-1/4	7	8
1-3/8	7	8
1-1/2	8	N/A

**Subsection 602.19** (pg. 478), 6-27-16; add the following as the 2<sup>nd</sup> paragraph:

“All welders shall be qualified in accordance with the AASHTO/AWS D1.5, Bridge Welding Code, current edition. Welders shall be certified for each weld process and position which they will be using.”

**Subsection 602.39** (pg.488), 6-27-16; revise the title as follows:

“CONSTRUCTION REQUIREMENTS – ERECTION – REMOVAL”

**Subsection 602.42** (pg.489), 6-27-16; revise as follows:

“All contractors and subcontractors directly engaged in the erection or removal of structural steel, precast prestressed or mild steel reinforced concrete bridge beams or girders over active highway traffic lanes, on any route, railroad or any stream deemed navigable to commercial or pleasure water craft, shall submit an erection or removal plan prepared and stamped by a Professional Engineer licensed in the State of Tennessee. Include the following in these plans: the sequences of erection or removal, the generalized location of all pick points, and the plan to adequately stabilize the structure throughout the erection or removal process. Submit this plan to the Engineer at least 30 days before starting erection. At each stopping point in the erection or removal sequence, have a competent contractor’s representative inspect the beams to ensure adequate stability.

Do not begin any erection or removal work without the Engineer’s approval. The Engineer’s approval does not relieve the Contractor of the responsibility for the safety of its method or equipment or from carrying out the work in accordance with the Plans and Specifications.”

**Subsection 604.02** (pg. 519), 11-16-15; C. 2<sup>nd</sup> paragraph, 1<sup>st</sup> sentence:

“Prior to construction, submit for approval shop drawings of the proposed precast structure and design calculations for any details which deviate from the standard box culvert drawings.”

**Subsection 604.02** (pg. 517-518), 5-15-17; A. General, add Class DS Concrete to the index:

**604.02 Materials**

**A. General**

Provide materials as specified in:

Hydraulic cement <sup>1</sup> .....	<b>901.01</b>
Fine Aggregate, (all Classes of concrete).....	<b>903.01</b>
Coarse Aggregate	
For Class A Concrete: Size No. 57 .....	<b>903.03</b>
For Class D Concrete: Size No. 57 .....	<b>903.03</b>

<sup>1</sup>Use Type I, Type IL, or Type IS unless otherwise specified or permitted, or Type I or Type IL cement with either fly ash and/or ground granulated blast furnace slag as a partial cement replacement unless otherwise specified or permitted. When using Type I or Type IL cement with either fly ash and/or ground granulated blast furnace slag as a partial cement replacement, comply with the requirements of **604.03**.

**Subsection 604.02 C.** (pg. 519), 11-6-17; Precast Box Sections, remove mylar reference in second paragraph:

“Submit shop drawings of the proposed precast box section and design calculations for approval before construction. As a minimum, the shop drawings shall include a plan and elevation view of the box culvert showing all precast sections, a typical precast box section showing dimensions and reinforcing, and notes and details required for construction. After obtaining the necessary approval, furnish the Structures Division ~~a permanent, 4 mil mylar reproducible of the design for their file~~ **a reproducible design file**. The Department will pay the Contractor for the precast box based on the price bid for the quantity of the items in the cast-in-place structure it replaces. Manufacture the precast reinforced box sections in accordance with Departmental procedures.”

For Class DS Concrete: Size No. 57 .....	<b>903.03</b>
For Class L Concrete.....	<b>903.19</b>
Joint Filler, Preformed Type .....	<b>905.01</b>
Steel Bar Reinforcement .....	<b>907.01</b>
Welded Steel Wire Fabric .....	<b>907.03</b>
Structural Steel.....	<b>908.01</b>
Permanent Steel Bridge Deck Forms .....	<b>908.03</b>
Steel Castings.....	<b>908.05</b>
Gray Iron Castings .....	<b>908.07</b>
Bronze Bearing Plates, Plain.....	<b>908.09</b>
Bronze Bearing Plates, Self-Lubricating.....	<b>908.10</b>

**Subsection 604.03** (pg. 520-521), 5-15-17; Table 604.03-1: Composition of Various Classes of Concrete and Table 604.03-2: Use of Chemical Admixtures, Add class DS to the Tables, revise footnotes 2 and 3 of Table 604.03-1 and the note below Table 604.03-3; Update Table 604.03-4: Composition of Self-Consolidating Concrete and Table 604.03-5: Use of Chemical Admixtures to add SH-SCC, update :

**Table 604.03-1: Composition of Various Classes of Concrete**

Class of Concrete	Min 28-Day Compressive Strength (psi)	Min Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design $\pm$ production tolerance)	Slump (inches)
A	3,000	564	0.45	6 $\pm$ 2	3 $\pm$ 1 <sup>(1)</sup>
D, DS <sup>(2,3)</sup>	4,000	620	0.40	7 <sup>(3)</sup>	8 max <sup>(4)</sup>
L <sup>(3,5)</sup>	4,000	620	0.40	7 <sup>(3)</sup>	8 max <sup>(4)</sup>
S (Seal) <sup>(6)</sup>	3,000	682	0.47	6 $\pm$ 2	6 $\pm$ 2
X <sup>(7)</sup>					

<sup>(1)</sup> For slip forming, the slump shall range from 0 to 3 inches.

<sup>(2)</sup> Use Class DS concrete in riding surfaces as described in 903.03 and in accordance to Specification 903.24 requirements. Use Class D concrete in all other bridge decks except box and slab type structures unless otherwise shown on the Plans.

<sup>(3)</sup> Design Class D, Class DS, and Class L concrete at 7% air content. Acceptance range for pumping and other methods of placement is 4.5-7.5%. Sampling will be at the truck chute.

<sup>(4)</sup> Water reducing admixtures are acceptable; however, do not exceed the maximum water/cement ratio in order to achieve the required slump.

<sup>(5)</sup> The unit weight of air dried Class L concrete (lightweight concrete) shall not exceed 115 pounds per cubic foot as determined according to ASTM C567.

<sup>(6)</sup> The use of fly ash as a cement replacement will be allowed in Class S (Seal) concrete.

<sup>(7)</sup> Plan specific requirements.

Include chemical admixtures in the concrete mixture as specified in Table 604.03-2 based on the ambient air temperature and expected weather conditions.

**Table 604.03-2: Use of Chemical Admixtures**

Class of Concrete	Temperature less than 85 °F and falling	Temperature 85 °F or greater and rising
A	Type A or F	Type D or G or A and B
D, DS	Type A or F	Type A or F and B or G
L	Type F	Type F and B or G
S	Type D or G or A and B	Type D or G or A and B

**Table 604.03-3: Type I or Type II Cement Modified by Fly Ash or Ground Granulated Blast Furnace Slag (GGBFS)**

Modifier	Maximum Cement Replacement Rate % (by weight)	Minimum Modifier Cement Substitution Rates (by weight)
GGBFS (grade 100 or 120)	35.0	1:1
Class "F" Fly Ash	25.0	1:1
Class "C" Fly Ash	25.0	1:1

The Contractor may use ternary cementitious mixtures (mixtures with Portland cement, ground granulated blast furnace slag, and fly ash) for Class A, Class D, and Class DS concrete provided that the minimum Portland cement content is 50%. The maximum amount of fly ash substitution in a ternary cementitious mixture shall be 20%. The Department will allow Type IS cement with ternary cementitious mixtures. When using a Type IS cement, do not use any additional slag as a partial replacement for the hydraulic cement.

**Table 604.03-4: Composition of Self-Consolidating Concrete**

Class of Concrete	Min 28-Day Compressive Strength (psi)	Min Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design $\pm$ production tolerance)	Slump Flow (inches)
SCC (2,3,4,5)	3,000 <sup>(1)</sup>	564	0.45	6 $\pm$ 1	25 $\pm$ 4
SH-SCC (2,3,4,5,6)	4,500	620	0.45	6 $\pm$ 1	25 $\pm$ 4

(1) Or as shown on the Plans or approved shop drawings.

(2) Acceptance range for the T50 test in accordance with ASTM C1611 shall be between 2-7 seconds.

(3) Passing ability in accordance with ASTM C1621 shall be less than 2 inches for acceptance.

(4) Visual Stability Index (VSI) shall not exceed 1.0 as per ASTM C1611 for acceptance.

(5) Static segregation as measured by ASTM C 1610 shall not exceed 20%.

(6) Air Content may be reduced if placed under water or underground if approved by the Engineer

**Table 604.03-5: Use of Chemical Admixtures**

Class of Concrete	Temperature less than 85 °F and falling	Temperature 85 °F or greater and rising
SCC, SH-SCC	Type A or F Type S (Viscosity Modifying)	Type D or G or A and B Type S (Viscosity Modifying)

**Subsection 604.03** (pg. 522-523) 5-15-17; A. Classification and Proportioning and Quality Assurance: Add 22.-28, add sentence to 5<sup>th</sup> paragraph:

2. **“Mix Design Submittal.** Submit the proposed concrete design to the Engineer for approval. Develop the design using saturated surface dry aggregate weights and trial batches meeting the requirements of these Specifications. The concrete design shall be prepared by a TDOT certified Class 3 concrete technician or approved independent testing laboratory under the direction of a registered civil engineer licensed by the State of Tennessee. The concrete plant technician or the civil engineer shall certify that the information contained on the design is correct and is the result of information gained from the trial batches. The concrete design shall produce an average compressive strength to indicate that the specified 28-day strength can be obtained in the field. Make all strength determinations using equipment meeting the requirements of, and in the manner prescribed by, AASHTO T 22. Provide concrete of the design strength specified in all applicable Special Provisions, Plans, and Standard Specifications. Build trial batches for design no more than 90 days before submitting the concrete design. The approved mix design will expire after 6 months if it is not used on a Department funded project and meet the minimum 28-day strength requirements. Assume responsibility for all costs of concrete design, preparation, and submittal.

As a minimum, include the following information in the proposed concrete design submittal:

1. Source of all aggregates
2. Brand and type of cement
3. Source and class of fly ash (if used)
4. Source and grade of ground granulated blast furnace slag (if used)
5. Specific gravity of cement
6. Specific gravity of the fly ash (if used)
7. Specific gravity of the ground granulated blast furnace slag (if used)
8. Admixtures (if used)
9. Gradations of aggregates
10. Specific gravity of aggregates (saturated surface dry)
11. Air content (if air entrainment is used)
12. Percentage of fine aggregate of the total aggregate (by volume)
13. Slump
14. Weight per cubic yard
15. Yield
16. Temperature of plastic concrete
17. Water/cement ratio (pound/pound)
18. 7-day compressive strength (minimum of two 4-inch x 8-inch cylinders)
19. 14-day compressive strength (minimum of two 4-inch x 8-inch cylinders)
20. 28-day compressive strength (minimum of two 4-inch x 8-inch cylinders)
21. Weight of each material required to produce a cubic yard of concrete
22. Water – submit testing results per Tables 921.01-1 & 921.01-2



In addition to the above mentioned items, for self-consolidating concrete include as a minimum the following information in the proposed SCC design submittal:

23. Slump flow, VSI, and T50, in accordance with ASTM C1611, shall be required in place of the slump test.
24. Passing ability in accordance with ASTM C1621.
25. Static segregation in accordance with ASTM C1610.
- 26. 7-day compressive strength (minimum of **two** 4-inch x 8-inch cylinders), in accordance with ASTM C1758.
27. 14-day compressive strength (minimum of **two** 4-inch x 8-inch cylinders), in accordance with ASTM C1758.
28. 28-day compressive strength (minimum of **two** 4-inch x 8-inch cylinders), in accordance with ASTM C1758.

Self-consolidating concrete (Classes SCC, SH-SCC and P-SCC) shall be verified prior to placement either at the ready mix facility or prestressed plant. The submitted mix design shall be reviewed by Headquarters Materials and Tests for specification compliance. The concrete producer shall then perform a trial batch verification of the submitted mix design in the presence of Regional Materials and Tests. The trial batch will ensure that all batch quantities and target admixture dosage rates are acceptable and meet TDOT specification prior to full mix design approval. If using a previously approved SCC design additional verification of the trial batch is not required. All quantities and identified admixture target dosage rates shall meet the tolerances specified in **501.09**

Instead of the above mix design submittal, an existing design may be submitted for approval provided the design has been used on a state funded project within the last six (6) months. **When submitting for the use of an existing mix design, the most current water testing results per 921.01 shall accompany the submittal.** The approval of this concrete design submittal will not relieve the Contractor of the responsibility of providing concrete meeting the requirements of these Specifications. A temporary mix design may be issued if the 7-day or 14-day compressive strengths exceed the required 28-day strengths.”

**Subsection 604.03** (pg. 522 and 523), 5-18-15; 2. Mix Design Submittal; Replace the first sentence of the last paragraph on page 522 with the following:

“Instead of the above mix design submittal, an existing design may be submitted for approval provided the design has been used on a state funded project within the last six (6) months.”

**Subsection 604.03** (pg. 519-522), 11-16-15; A. Classification and Proportioning and Quality Assurance, modify the following:

**“1a. Design and Production Parameters.** Proportion the concrete based on a pre-determined minimum cement content, and a water-cement ratio that does not exceed the maximum shown in **Table 604.03-1**. Below this limit, adjust the quantity of water to meet the slump requirements. The fine aggregate shall not exceed 44% by volume calculation of the total aggregate, with the exception of slip formed Class A concrete incorporated into parapets and median barriers. For slip formed parapet and median barriers exclusively, the percentages of fine and coarse aggregate in an approved concrete mix design may be adjusted plus or minus 2%, such that the....

**1b. Self-Consolidating Concrete (SCC) Design and Production Parameters.** Proportion the concrete based on a pre-determined minimum cement content, and a water-cement ratio that does not exceed the maximum shown in **Table 604.03-4**. The fine aggregate shall not exceed 50% by volume calculation of the total aggregate volume. Maximum size of coarse aggregate shall not exceed a No. 67 stone. The Contractor may elect to use SCC as an alternate option in replacement of Class A concrete.

Document mixture adjustments in the field book and daily concrete report. Ensure that the adjusted mix complies with all of the performance criteria specified in **Table 604.03-4**.

**Table 604.03-4: Composition of Self-Consolidating Concrete**

Class of Concrete	Min 28-Day Compressive Strength (psi)	Min Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design $\pm$ production tolerance)	Slump Flow (inches)
SCC (2,3,4,5)	3,000 <sup>(1)</sup>	564	0.45	6 $\pm$ 1	25 $\pm$ 4

(1) Or as shown on the Plans or approved shop drawings.

(2) Acceptance range for the T50 test in accordance with ASTM C1611 shall be between 2-7 seconds.

(3) Passing ability in accordance with ASTM C1621 shall be less than 2 inches for acceptance.

(4) Visual Stability Index (VSI) shall not exceed 1.0 as per ASTM C1611 for acceptance.

(5) Static segregation as measured by ASTM C 1610 shall not exceed 20%.

Include chemical admixtures in the self-consolidating concrete mixture as specified in **Table 604.03-5** based on the ambient air temperature and expected weather conditions. Approved viscosity modifying admixtures (VMA) may be used as part of the chemical admixtures if they are shown in the approved mixture design.

**Table 604.03-5: Use of Chemical Admixtures**

Class of Concrete	Temperature less than 85 °F and falling	Temperature 85 °F or greater and rising
SCC	Type A or F Type S (Viscosity Modifying)	Type D or G or A and B Type S (Viscosity Modifying)

Dosage rates for any admixtures incorporated into the concrete shall be stated during the mix design submittal process. All admixtures shall be compatible and from the same manufacturer.

2.Mix Design Submittal. Submit the proposed concrete design to the Engineer for approval. Develop the design using saturated surface dry aggregate weights and trial batches meeting the requirements of these Specifications....

As a minimum, include the following information in the proposed concrete design submittal:

1. Source of all aggregates
2. Brand and type of cement

3. Source and class of fly ash (if used)
4. Source and grade of ground granulated blast furnace slag (if used)
5. Specific gravity of cement
6. Specific gravity of the fly ash (if used)
7. Specific gravity of the ground granulated blast furnace slag (if used)
8. Admixtures (if used)
9. Gradations of aggregates
10. Specific gravity of aggregates (saturated surface dry)
11. Air content (if air entrainment is used)
12. Percentage of fine aggregate of the total aggregate (by volume)
13. Slump
14. Weight per cubic yard
15. Yield
16. Temperature of plastic concrete
17. Water/cement ratio (pound/pound)
18. 7-day compressive strength (minimum of three 4-inch x 8-inch cylinders)
19. 14-day compressive strength (minimum of three 4-inch x 8-inch cylinders)
20. 28-day compressive strength (minimum of three 4-inch x 8-inch cylinders)
21. Weight of each material required to produce a cubic yard of concrete

In addition to the above mentioned items, for self-consolidating concrete include as a minimum the following information in the proposed SCC design submittal:

22. Slump flow, VSI, and T50, in accordance with ASTM C1611, shall be required in place of the slump test.
23. Passing ability in accordance with ASTM C1621.
24. Static segregation in accordance with ASTM C1610.
25. 7-day compressive strength (minimum of three 4-inch x 8-inch cylinders), in accordance with ASTM C1758.
26. 14-day compressive strength (minimum of three 4-inch x 8-inch cylinders), in accordance with ASTM C1758.
27. 28-day compressive strength (minimum of three 4-inch x 8-inch cylinders), in accordance with ASTM C1758.

Self-consolidating concrete (Classes SCC and P-SCC) shall be verified prior to placement either at the ready mix facility or prestressed plant. The submitted mix design shall be reviewed by Headquarters Materials and Tests for specification compliance. The concrete producer shall then perform a trial batch verification of the submitted mix design in the presence of Regional Materials and Tests. The trial batch will ensure that all batch quantities and target admixture dosage rates are acceptable and meet TDOT specification prior to full mix design approval. If using a previously approved SCC design additional verification of the trial batch is not required. All quantities and identified admixture target dosage rates shall meet the tolerances specified in **501.09**.

**Subsection 604.03** (pg. 522), 12-2-16; Mix Design Submittal, modify the following:

- “18. 7-day compressive strength (minimum of two 4-inch x 8-inch cylinders)  
 19. 14-day compressive strength (minimum of two 4-inch x 8-inch cylinders)  
 20. 28-day compressive strength (minimum of two 4-inch x 8-inch cylinders)”

**Subsection 604.03 B.** (pg.524), 11-6-17; B. Quality Control and Acceptance of Concrete, Add the following as the last sentence of the 1<sup>st</sup> paragraph:

“If the quantity exceeds 2 cubic yards, prior approval must be obtained from the Engineer prior to placement.”

**Subsection 604.13** (pg. 541), 5-15-17; Mixing Concrete, add Class DS concrete to the 2<sup>nd</sup> paragraph, 3<sup>rd</sup> sentence:

“Do not retemper concrete by adding water or by other means. However, the Contractor may withhold a portion of the mixing water or chemical admixtures from transit mixers and add at the work site if all requirements of the approved mix design are met. Water added at the placement site for Class A, Class D, Class DS and Class L concrete shall not exceed 1 gallon per cubic yard. The total amount of water in the mix shall not exceed the maximum in the approved mix design. To achieve additional slump, use a water reducing admixture. If water, air entrainers, or chemical admixtures are added at the placement site, mix the concrete a minimum of 30 revolutions at mixing speed after making the additions. Do not use concrete that is not within the specified slump limits, air content limits, temperature limits, or time limits at the time of placement.”

**Subsection 604.14** (pg. 542), 11-16-15; Consistency of Concrete, modify the following:

“The slump of the concrete when measured according to AASHTO T 119 shall meet 604.03 - 1A. The slump flow of self-consolidating concrete when measured according to ASTM C1611 shall meet **604.03 1B.**”

**Subsection 604.15** (pg. 542-543), 11-16-15; B. Concrete Acceptance Cylinders, modify the following:

“The Department will test the specimens for compressive strength according to AASHTO T 22. Provide the necessary concrete for making test specimens and adequate curing and storage facilities at no additional cost to the Department.

Concrete cylinders submitted for testing beyond 28 days shall comply with the strength requirements specified in Table 604.15-1.

**Table 604.15-1: Strength Requirements**

Class of Concrete	Compressive Strength (psi) at:		
	Less than 31 days	31 to 42 days	43 days to 56 days
A, S, CP, SCC	3,000	3,300	3,500
D, L	4,000	4,400	4,600
X	Plans Requirement (Req)	Req. + Req. * (10%)	Req. + Req. * (15%)

If the acceptance cylinders fail to meet the specified strengths, the Contractor may drill core samples from the hardened concrete as verification of concrete strength instead of using the concrete cylinders. The Contractor must provide QC data from companion cylinders that meet or exceed the required strength, and TDOT Materials and Test shall perform a nondestructive test

using a Swiss Hammer on the concrete to prove required strength is achieved. If the above mentioned requirements are met, the Contractor may then elect to drill a maximum of three core samples per set of cylinders from the hardened concrete. The Contractor shall obtain the cores in accordance with the Department's Standard Operating Procedure 4-2, and bear all costs of obtaining the cores and repairing the core holes."

**Subsection 604.15** (pg. 543), 5-15-17; Table 604.15-1: Strength Requirements, Add Class DS to Table, update 2<sup>nd</sup> paragraph 3<sup>rd</sup> sentence to remove "cylinders and":

**Table 604.15-1: Strength Requirements**

Class of Concrete	Compressive Strength (psi) at:		
	Less than 31 days	31 to 42 days	43 days to 56 days
A, S, CP, SCC	3,000	3,300	3,500
D, DS, L	4,000	4,400	4,600
SH-SCC	4,500	4,950	5,175
X	Plans Requirement (Req)	Req. + Req. * (10%)	Req. + Req. * (15%)

If the acceptance cylinders fail to meet the specified strengths, the Contractor may drill core samples from the hardened concrete as verification of concrete strength instead of using the concrete cylinders. The Contractor must provide QC data from companion cylinders that meet or exceed the required strength, and TDOT Materials and Test shall perform a nondestructive test using a Swiss Hammer on the concrete to prove required strength is achieved. If the above mentioned requirements are met, the Contractor may then elect to drill a maximum of three core samples per set of cylinders from the hardened concrete. The Contractor shall obtain the cores in accordance with the Department's Standard Operating Procedure 4-2, and bear all costs of obtaining the cores and repairing the core holes.

Acceptance for payment may be based on cores provided by the Contractor at its expense. These cores shall meet the strength requirements specified in Table 604.15-1. The Engineer will not accept concrete cores submitted for testing beyond 56 days.

**Subsection 604.16** (pg. 545) 5-15-17; Placing Concrete, A. General – revise the 1<sup>st</sup> paragraph to add Class DS in the first sentence:

"Unless otherwise specified, before placing a bridge deck overlay of Class D , Class DS, or Class L concrete, machine scarify the surface to be covered to a minimum depth of 1 inch. In areas inaccessible to machine scarifying, and in areas of spalling where steel reinforcement is exposed, remove deteriorated concrete using hand tools or other methods approved by the Engineer. After scarifying, clean the deck of all deleterious material. Do not allow traffic on the scarified deck."

**Subsection 604.27** (pg. 560), 11-16-15; Rideability of New or Resurfaced Bridge Decks and Roadway Approaches, A. General, revise the 1<sup>st</sup> paragraph to the following:

“On all highway sections with a posted speed greater than 40 miles per hour, the following rideability provisions shall apply to new or resurfaced bridge decks and roadway approaches.”

**Subsection 604.31** (pg. 567-568) 5-15-17; Basis of Payment, add Class DS to item and pay unit list:

**604.31 Basis of Payment**

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Class A Concrete (Description)	Cubic Yard
Class D Concrete (Description)	Cubic Yard
<b>Class DS Concrete (Description)</b>	<b>Cubic Yard</b>
Class L Concrete (Description)	Cubic Yard
Class S Concrete (Description)	Cubic Yard
Steel Bar Reinforcement	Pound
Epoxy Coated Reinforcing	Pound
Scarifying	Square Yard
Applied Texture Finish	Square Yard
Hydro-demolition	Square Yard

**Subsection 606.04.B.1(b)** (pg. 578), 6-27-16; replace 1.b. with the following:

“(b) Except as provided in paragraph 2(b) below, develop an energy per blow in foot-pounds not less than 250 multiplied by R, where R is the required minimum bearing resistance of the pile in tons.”

**Subsection 606.07.A.** (pg. 581), 6-27-16; revise the 1<sup>st</sup> paragraph:

“Construct cast-in-place concrete piles of the design shown on the Plans and that consist of concrete cast in drilled holes or in steel shells or pipes driven to the required bearing. Use Class A concrete meeting **604**, or use Class X concrete, as required by design, meeting **604**. Provide and place suitable casing when required to prevent caving of the hole before concrete is placed.

**Subsection 611.02** (pg. 620), 11-6-17; Materials, revise the last sentence of the last paragraph to remove the mylar reference:

“After obtaining the necessary approval, furnish the Engineer an electronic reproducible design file, ~~4 mil mylar reproducible of the design.~~”

**Subsection 613.02** (pg. 633), 6-27-16; add the following section:

“Brick Paving Units .....912.05”

**Subsection 615.09** (pg. 644), 11-16-15; Proportioning and Mixing of Concrete, update Table 615.09-1 and add the 3<sup>rd</sup> paragraph below the table, modify the last paragraph:

**Table 615.09-1: Composition of Prestress Concrete Classes**

Class of Concrete	Minimum 28-Day Compressive Strength (psi)	Minimum Pounds Cement per Cubic Yard	Maximum Water/Cement Ratio (pound/pound)	Air Content %	Slump or Slump Flow (inches)
P	5,000 <sup>(1)</sup>	658	0.45	0-8 <sup>(2)</sup>	2 ± 1 <sup>(3)</sup>
P-SCC <sup>(4)</sup>	5,000 <sup>(1)</sup>	658	0.45	0-6 <sup>(2)</sup>	25 ± 4

<sup>(1)</sup> Or as shown on the Plans or approved shop drawings.

<sup>(2)</sup> Air entraining is optional with the Contractor, unless otherwise shown on the Plans or shop drawings.

<sup>(3)</sup> Not to exceed 3 inches before the addition of high range admixtures, and not to exceed 10 inches after the addition of high range admixtures. If water-cement ratio is equal to or less than 0.35 then the maximum slump is 10 inches. If the water-cement ratio is 0.36 – 0.45, the maximum slump is 8 inches.

<sup>(4)</sup> Maximum coarse aggregate size of a No. 67 stone.

Comply with all applicable provisions of **604.03** except as modified herein.

Submit a concrete design to the Department for review and approval. In addition to the proportions, identify in the design submittal the source or brand of all materials and the type of cement to be used. The Contractor may use Type I or Type III cement, unless otherwise specified. Do not use calcium chloride. Use a retardant admixture when the ambient temperature is 75 °F or higher. The slump of the concrete shall be 2 inches with a tolerance of ±1 inch at the time of placement. When an approved superplasticizer is to be used, the slump of the concrete shall be the same as above before the superplasticizer is added to the mix. After the addition of the superplasticizer, the slump may be increased to a maximum of 8 inches at the time of placement.

The slump flow of self-consolidating concrete shall be determined and within the design and production tolerances stated in **Table 615.09-1**. Include chemical admixtures in the self-consolidating concrete mixture as specified in **Table 604.03-5** based on the ambient air temperature and expected weather conditions. Approved viscosity modifying admixtures (VMA) may be used as part of the chemical admixtures if they are shown in the approved mixture design.

Handle, measure, and batch materials; mix concrete; and comply with the limitations of mixing as specified in **501.09**, **501.10**, and **501.11**, respectively.

Make concrete test specimens for Class P and Class P-SCC, in accordance with AASHTO T 23 and ASTM C1758 respectively, to determine the adequacy of the concrete design and the minimum time at which the stress may be applied to the concrete. Cure the test specimens used to determine the time at which stress may be applied in the same manner and under the same conditions as the bridge members. The initial curing of specimens to determine the design strength of the concrete shall be as specified above with additional curing water, as provided in AASHTO...

**Subsection 615.17** (pg. 652), 5-18-15; Table 615.17-1: Manufacturing Tolerances in Standard Sections, Update Table 615.17-1:

**Table 615.17-1: Manufacturing Tolerances in Standard Sections**

Description	Tolerance	
	I-Sections	Box Sections
Nominal Depth	± 1/2 inch	± 1/2 inch
Nominal Width	± 1/2 inch	± 1/2 inch
Nominal Length	Computed Elastic Shortening ±1/2 inch	Computed Elastic Shortening ±1/2 inch
Variation in Straightness, inches	1/4 inch x (Total Length in feet)/10	1/4 inch x (Total Length in feet)/10
Variation in Camber, inches	Beams in any 1 span not more than: 1/8 inch x (Total Length in feet )/10	Beams in any 1 span not more than: 1/8 inch x (Total Length in feet )/10
Location of Voids	-----	Length ± 1/2 in Wall Thickness ± 1/2 in
Bearing	Full Bearing - Full Width of Beam	Full Bearing on at Least 2/3 of Width of Beam
Tendon Placement	± 1/2 inch	± 1/2 inch
Reinforcing Steel Placement	± 1/2 inch	± 1/2 inch
Reinforcing Steel Concrete Cover	± 1/2 inch	± 1/2 inch
Reinforcing Steel Splice Lengths	Minus 1-1/2 inches	Minus 1-1/2 inches

**Subsection 622.03** (pg. 686) 12-2-16; Add the following paragraph at the beginning of the section:

“Same-as designs shall not be submitted for Shotcrete.”



**STATE**

**OF**

**TENNESSEE**

(Rev. 6-27-16)

(Rev. 12-2-16)

(Rev. 5-15-17)

(Rev. 11-6-17)

January 1, 2015

**Supplemental Specifications - Section 700**

**of the**

**Standard Specifications for Road and Bridge Construction**

**January 1, 2015**

**Subsection 712.04** (pg. 759), 12-2-16; A. Flaggers, add ABET Accredited University Programs to the list of flagger training:

- “1. American Traffic Safety Services Association (ATSSA)
- 2. National Safety Council (NSC)
- 3. Tennessee Transportation Assistance Program (TTAP)
- 4. ABET Accredited University Programs”

**Subsection 712.04** (pg. 759). 11-6-17; A. Flaggers, replace the last paragraph with the following:

“The Department will review and determine if an alternative training program is acceptable prior to use. Alternative training programs shall meet all MUTCD requirements and follow FHWA guidance.

The Department will consider flaggers to be a general requirement of traffic control and will not make direct payment for such.

Coordinate flagging operations in a manner that causes as little delay to the traveling public as possible. Delays shall be kept within 2 minutes or ¼ mile, but shall not exceed 5 minutes or a 1 mile maximum, unless prior authorization is granted by the Department.”

**Subsection 712.04.B** (pg.759-760) 12-2-16; revise the first paragraph of B. THP Troopers and Uniformed Law Enforcement Officers:

“B. THP Troopers and Uniformed Law Enforcement Officers

When a THP Trooper is not available, the Contractor may provide a Uniformed Law Enforcement Officer if approved by the Engineer and the Regional Safety Coordinator or Regional Operations Office. All Uniformed Law Enforcement Officers shall provide marked law enforcement vehicle equipped with blue lights and have the authority to write traffic tickets and make arrests within the project site. The Uniformed Law Enforcement Officer shall maintain a detailed written log of enforcement activities and shall submit the log to the Engineer for verification each month.”

**Subsection 712.04 G.** (pg. 762), 11-6-17; G. Lane Closures, add the Type of Facility and Requirement table to the end of the subsection, revise the last sentence:

“G. Lane Closures

Hold the length of a lane closure to the minimum length required to accomplish the Work. Locate advanced warning signs for the Project so as to not overlap with the advanced warning signs for lane shifts and lane closures.

Use drums in all transition tapers for lane closures on multi-lane roads.

Contractor’s Staff performing lane closure shall have the following certifications to close lanes on TDOT facilities and shall be onsite during each lane closure performed.

<u>Type of Facility</u>	<u>Requirement</u>
<u>Two Lane</u>	<u>Flagging Operations Certification (Shall comply with Subsection 712.04 A)</u>
<u>Multi-Lane</u>	<u>*ATSSA Traffic Control Technician Training or equivalent</u>
<u>Controlled Access Freeways &amp; Expressways</u>	<u>*ATSSA Traffic Control Technician Training or equivalent</u>

\*Proof of certification shall be provided to the Engineer at the Pre-Construction Meeting.

**Subsection 712.09** (pg. 769), 12-2-16; change Uniformed Police Officer to Uniformed Law Enforcement in the last paragraph:

“The Department will pay for Uniformed Law Enforcement Officers provided by the Contractor at the invoice price of the work plus 5%, not to exceed \$50 per hour for the hours present on the Project. No compensation will be made for drive time.”

**Subsection 713.04** (pg. 772) 5-15-17; Construction Methods and Requirements; add steel requirement as the last paragraph:

“Ensure steel meets all specifications in **602.04.**”

**Subsection 713.04.C.6** (pg. 774), 6-27-16; replace C.6. with the following:

“6. Concrete. Use either (1) Class A concrete meeting 604.03 or (2) Class X concrete with a f’c as identified in the plans or required by the design. If Class X concrete is required, use a mix meeting the minimum requirements of **604.03** for Class A concrete, but with a cementitious material quantity necessary to produce the specified strength.”

**Subsection 713.04.C.8** (pg. 774), 6-27-16; add sentence to the end of 8.:

“8. Setting Anchor Bolts and Stubs. Set anchor bolts and stubs for sign supports to proper locations and elevations with templates, and carefully check them after constructing the sign foundation and before the concrete has set. Anchor rods shall conform to the requirements of section **730.11**”

**Subsection 714** (pg. 779-800), 11-6-17; Revise the subsection as follows:

**“MATERIALS**

**714.02 Materials**

Provide materials as specified in **917** and as follows:

Portland Cement Concrete, Class A .....	<b>604</b>
Crushed Stone Grading D.....	<b>903.05</b>
Steel Bar Reinforcement for Concrete Structures.....	<b>907.01</b>
Welded Steel Wire Fabric .....	<b>907.03</b>
Gray Iron Castings.....	<b>908.07</b>

Inorganic Zinc Paint ..... **910.03**  
 Cement Concrete Curing Materials ..... **913**  
 Conduit ..... **917.05 or 917.07**

Within 30 days after the issuance of the work order, submit to the Engineer, four collated sets of the manufacturer’s descriptive literature and technical data, fully describing the types of lighting equipment proposed for use. In the descriptive literature, identify the manufacturer and model, and include sufficient information for the Engineer to determine if the equipment or material meets the requirements of the Plans and these Specifications. Include with these sets of submittal data a list of the materials submitted along with descriptive material for, but not limited to, the following items when applicable:

1. Complete photometric data of luminaires as published by the manufacturer with independent testing laboratory results.
2. Computer printouts showing illumination levels throughout each interchange area where high mast luminaires are to be installed.
3. General details of light standards, breakaway bases, and bracket arms. For light standards taller than 30 feet, submit one set of design calculations and six prints of “Design” or “Shop” drawings to the Division of Structures for approval purposes. The Department will review these drawings at the earliest possible date, and will return two prints marked “Approved for Fabrication,” or “Returned for Revisions as Noted.” Respond by taking appropriate action to ensure the earliest possible correction of these items so as not to delay the installation.
4. Highmast tower details with a set of design calculations for each height including access hole, base, anchorage, head frame, and lowering device. Include specification references for materials and location, type, size, and extent of welds. In addition to the set of design calculations, submit six prints of “Design” or “Shop” drawings for each highmast tower height to the Division of Structures for approval purposes, in a manner similar to that specified in Item 3 above for light standards taller than 30 feet.
5. Dimension sheets and performance data on all related equipment.

The Engineer will retain one copy and forward one copy each to the ~~Regional Materials and Tests Division~~ the local entity (city or county engineer) and the ~~Traffic Operations Design~~ Division for their review.

Also include with the submittal sets detailed scale drawings of all non-standard or special equipment and of all proposed deviations from the Plans. Deviations from the Plans or Specifications require approval from the ~~Traffic Operations Design~~ Division. Include a letter requesting deviations or alternate materials in the submittal for ~~Traffic Operations Design~~ Division approval. Upon request, submit for approval sample articles of materials proposed for use. The Department will not be liable for any materials purchased, labor performed, or delay to the Work prior to such approval.

In addition to the above, include with each submittal a notarized letter certifying that all lighting system materials listed in the submittal conform to the Plans and Specifications. Also submit to the Engineer a statement from the Maintaining Agency that the system is acceptable to the Agency.

**714.03 Codes**

Furnish material and perform all work in strict accordance with the latest revision of the National Electrical Code, the National Electrical Safety Code, the Illuminating Engineering Society (IES) publications, ANSI standards, and the codes, regulations, and rules prevailing in the area in which the Work is being performed, as applicable.

**714.04 Reserved****CONSTRUCTION REQUIREMENTS****714.05 Conduit**

Install conduit of the type and size specified at the locations shown on the Plans, or as directed by the Engineer. Install pull or drag wires of the type and size specified in conduit at the locations shown on the Plans.

**A. Underground Conduit**

- 1. General.** Underground conduit shall consist of encased or direct burial conduit. Install conduit in a trench excavated to the dimensions and lines specified.

Before beginning any excavation, determine the location of all electrical, drainage, and utility lines in the vicinity, and perform work so as to avoid damaging these facilities. Ensure that the conduit will be located so as to avoid conflict with proposed guardrail, sign posts, and other features.

Build conduit runs in straight lines where possible. Where sweeps are necessary, use standard long sweep conduit bends when feasible, and meet the minimum radius required by the National Electric Code. Install pull boxes at intervals so that the tensile strength of the conductors will not be exceeded.

Obstructions encountered when excavating trenches for underground conduit may require minor changes, such as in locations of conduit runs and pull boxes. Obtain the Engineer's approval before making such changes. Where possible, provide a minimum of 12 inches between the finished lines of conduit runs and utility facilities, such as gas lines, water mains, and other underground facilities not associated with the electrical system. Where the conduit run is adjacent to concrete walls, piers, footings, and similar structures, maintain a minimum of 4 inches of undisturbed earth or firmly compacted soil between the conduit and the adjacent concrete or, when the conduit is encased, between the encasement and the adjacent concrete.

Unless shown on the Plans, do not excavate trenches in existing pavement or surfaced shoulders to install conduit. If it is necessary to place a conduit under an existing pavement, install the conduit by jacking or other approved means with galvanized rigid steel conduit or schedule 80 PVC conduit.

Keep jacking and drilling pits at least 10 feet from the edge of the paved shoulder or sidewalk unless otherwise directed by the Engineer. When the Plans specifically allow excavation of a trench through an existing pavement or surfaced shoulder, restore the pavement and/or surface and base to their original condition. Do not leave boring pits open for extended periods of time.

Unless otherwise specified, cut trenches for conduit on a slight grade for drainage, and make the walls of the trench essentially vertical. Tamp the bottom of the trench as necessary to produce a firm foundation for the conduit.

Excavate trenches for rigid metallic conduit, with or without encasement, to a minimum depth of 18 inches, plus conduit diameter, measured from the finished subgrade.

Sheet and brace the trenches as required, and adequately support all pipe and other structures exposed in trenches as necessary to prevent damage.

Ream metallic conduit after threads are cut. Ream other conduit as necessary. Cut all ends square and to butt solidly in the joints to form a smooth raceway for cables.

Ensure that conduit joints form a water-tight seal. Coat metallic conduit threads with pipe compound and then securely connect. Make conduit joints with the materials and in the manner recommended by the conduit manufacturer and as approved by the Engineer.

Install conduit bushings in conduit where necessary and required for protection of the conductors. When the conduit is installed for future use, ensure that the ends of metallic conduit runs are properly threaded and capped, and that the ends of non-metallic conduit runs are satisfactorily plugged or capped to prevent water or other foreign matter from entering the conduit system.

**a. Encased Conduit.** Place encased conduit under roadway and paved shoulders unless trenching is required for installation at the locations shown on the Plans. Unless otherwise specified, construct encasement as follows:

- (1) Construct the encasement of Class A concrete meeting the requirements of **604**, ~~except that the coarse aggregate shall be size 67 or 78.~~
- (2) Extend the encasement of conduit under roadway pavements or surfaces to the outer edges of the surfaced or paved shoulders, or 1 foot beyond the outer edge of the sidewalk, or 1 foot beyond the outer edge of the curb when no shoulder or sidewalk is indicated.
- (3) Extend the conduit at least 6 inches beyond the encasement.
- (4) Encase the pipe with a minimum of 3 inches of concrete.
- (5) Plug the ends of the conduit temporarily to prevent the entrance of concrete or other foreign material.
- (6) Do not encase any conduit with concrete until inspected and approved by the Engineer.
- (7) Cure concrete encasement as specified in **604.23**, except that the curing period may be reduced to 24 hours if backfilling is to proceed at the time specified in **714.05.A.2**.

**b. Direct Burial Conduit.** When rock is encountered in the bottom of the trench, install the conduit on a bed of well compacted fine grain soil at least 4 inches thick.

**2. Backfilling Conduit.** Do not backfill encased conduit until the concrete encasement has cured a minimum of 24 hours. After the Engineer has inspected and approved the installation of direct burial conduit, promptly backfill to the required grade with approved material in layers not exceeding 6 inches in loose depth, and compact each layer as directed by the Engineer.

**B. Conduit on Structures**

Install conduits, conduit fittings, hangers, expansion fittings, and accessories on as shown on the Plans and, unless otherwise specified, in accordance with the following:

1. Run conduit parallel to beams, trusses, supports, pier caps, and similar features in the most direct manner.
2. Install horizontal runs on a slight grade, without forming low spots, to ensure proper drainage.

3. Run conduits with smooth, easy bends.
4. Hold conduits in boxes with locknuts and provide bushings for protection of the conductors.

### **C. Testing Conduit**

After completing the installation of conduit, test it with a metallic mandrel in the presence of the Engineer. Use a mandrel having a diameter 1/4 inch smaller than the conduit, and a length of 2 inches. Repair, to the Engineer's satisfaction, all conduits that will not allow passage of the mandrel. If repairs cannot be accomplished, remove and replace the conduit at no additional cost to the Department.

After the mandrel test, scour all conduits with a stiff wire brush having a slightly larger diameter than the conduit.

Test conduits that have been installed under a previous contract with a mandrel and clean as described above before installing the cables.

### **714.06 Pull Boxes**

Construct pull boxes in accordance with the design, dimensions, and at the locations shown on the Plans. Construct concrete pull boxes of Class A concrete meeting the requirements of **604**. Place non-metallic pull boxes only in non-traffic bearing locations and not in paved areas.

Provide a cast iron frame and cover or reinforced concrete cover, as shown on the Plans, with each pull box.

Plug unused conduit entrance holes and openings for conduit to be extended by others with suitable plugs of plastic, bituminous fiber, or other approved material to prevent the entrance of foreign matter.

### **714.07 Underground Cable for Lighting Circuits**

Underground cable for lighting circuits shall consist of direct burial cable, preassembled cable in duct, or cable in conduit, as shown on the Plans.

If it is necessary to install a cable under an existing pavement or surfaced shoulder, install conduit, when specified, in accordance with the applicable provisions of **714.05**, and place the cable within the conduit.

Construct walls of trenches for cables to be essentially vertical. Unless otherwise specified, install underground cable as follows:

1. Excavate trenches for direct burial cable to a minimum depth of 24 inches plus the cable diameter as measured from finished subgrade.
2. In general, locate the trenches to avoid conflict with proposed guardrail, sign posts, and other features.
3. Protect direct burial cable, and preassembled cable in duct, in trenches by cushioning with sand or earth that passes a 1/4-inch screen. Place the cable, or preassembled cable in duct, and sand or earth in the trench so that a minimum 3-inch thickness of the cushion material will completely surround each cable.

**A. Direct Burial Cable**

Do not unreel cables and pull into the trench from one end. Unreel the cables, lay them alongside the trench, and then lay in the trench. Allow the cables to “snake” slightly in the trench to provide adequate slack for settling of earth. Ensure that there are no crossovers of cable in the trench. Where cable is brought up into the base of the lighting standard, leave sufficient slack for making the connections inside the standard.

**B. Preassembled Cable in Duct**

When installing in the trench, do not pull preassembled cable in duct taut, but allow it to “snake” in the ditch to provide not less than 18 inches slack per 100 feet of trench. The minimum bending radius on the cable duct shall be 18 inches. Where the duct is brought into the base of the lighting standard or into a pull box, leave sufficient length for trimming the duct to expose enough cable to allow for the connections to be made inside the standard or pull box.

**C. Cable in Conduit**

Carefully pull cables in conduits into place using approved methods so that the cable will be installed without electrical or mechanical damage. Pull all cables within a single conduit at the same time. If necessary to ease the pulling, ~~the Contractor may~~ use a lubricant of the type recommended by the cable manufacturer. When cables are pulled through hand holes in pole shafts, place a pad of firm rubber or other suitable material between the cable and the edges of the opening to prevent cable damage.

After the cable has been installed in the conduit, seal the ends of buried conduit with approved pliable and non-hardening material to prevent the entrance of dirt, moisture, or other foreign material.

**D. Splices**

Splice conductors as shown on the Plans. Only make splices at accessible points, such as handholes and pull boxes, unless otherwise shown on the Plans. After making a conductor splice, insulate it with heat-shrinkable tubing, supplied by the manufacturer, with an adhesive coating on the inner wall.

**E. Ground Wire**

Install ground conductors of the type and size shown on the Plans, and to be continuous in trenches with direct burial cable, and continuous inside preassembled cable in duct, and in conduit. Connect the ground conductors to the ground rod at all control points, to the ground lug in pole foundations, and to all metallic conduit runs using a grounding bushing, except that the connections to conduit in pole foundations may be omitted. Make all connections as shown on the Plans.

**F. Backfilling Underground Cable**

Backfill cable as specified in **714.05**.

**G. Cable Identification**

To assist in the identification of circuits at the pull boxes, mark the phase conductors with colored rubber-based, or equivalent, paint. When final connections are made, provide permanent tape wire markers to identify the branch circuit conductors (X1A, X1B, etc.), neutral (X1N, etc.), and the ground (g).

**714.08 Light Standards**

Install light standards of the designated design, kind, size, and class in accordance with and at the locations shown on the Plans. Ensure that the installed standards, complete with the bracket arm(s) and luminaire(s) as specified, provide the mounting height shown on the Plans. Determine the pole height as required by bracket arm upsweep, slope conditions, and similar characteristics.

**A. Foundations for Light Standards**

Consider transformer bases to be an integral part of the lighting standard unless otherwise specified.

**1. Bolt-Down Base Pole Foundations**

- a. Concrete Foundations.** Excavate a hole of the size and depth shown on the Plans. Remove and dispose of all excavated material as directed by the Engineer. Place anchor bolts of the type and size specified according to the pole manufacturer's recommendations, and securely hold to ensure proper position in the completed foundation. Ensure that no realignment of anchor bolts will occur after the foundation is poured. Accurately place reinforcing steel and securely hold to avoid displacement.

Accurately place conduits in foundations, orient them in the proper direction to accommodate service cables, and securely hold to avoid displacement.

Place Class A concrete in the excavated area against undisturbed earth to an elevation 4 inches below the finished ground line, and in an approved form from 4 inches below said ground line to the finished top of foundation elevation, as specified. Construct the foundation with a continuous concrete pour. Chamfer the edges of the top and formed portion of the foundation. Apply a Class 2 finish, as specified in **604.21.B**, to the portion of the foundation above grade and within 4 inches of grade.

- b. Metal Foundations.** Install metal foundations where shown on the Plans and, if desired, at locations where installation is possible without predrilling the hole.

- 2. Prestressed Concrete Butt Base Pole Foundations.** ~~EThe Contractor may~~ excavate prestressed concrete butt base lighting standard foundations using manual or mechanical methods. Dig or drill the holes to the depth and the diameter shown on the Plans. Place and compact in the bottom of the hole 6 inches of crushed stone, meeting the requirements of **903.05**, Grading D.

- 3. Wood Poles.** Excavate for wood poles as specified for prestressed concrete butt base pole foundations in **714.08.A.2**. Dig or drill the holes to the depth shown on the Plans and in such diameter to allow satisfactory use of mechanical tamping equipment.

**B. Light Standard Installation**

Handle the standards or poles as recommended by the manufacturer and approved by the Engineer. Accomplish erection without marring the finish or otherwise damaging the standard. Ground the light standards as shown on the Plans. When installing lighting on a bridge, review the proposed bridge plans or the completed structure before ordering the standards.

- 1. Bolt-Down Base Poles.** Set standards with bolt-down bases on foundations constructed as specified in **714.08.A.1**. Use metal shims supplied with the poles to plumb the pole, if the twin bracket arm type is



used; and, unless otherwise specified, to rake or lean the pole backward 4 inches, if the single bracket arm type is used.

2. **Prestressed Concrete Butt Base Poles.** Place prestressed concrete butt base lighting standards in the hole and on the layer of crushed stone prepared as specified in **714.08.A.2**. Position the pole in the center of the hole at grade and hold in place. Rake the lighting standards with single bracket arms as specified for poles with bolt-down bases in **714.08.B.1**. Set lighting standards with two bracket arms plumb. Fill the space surrounding the pole butt-base with crushed stone, applied in 6-inch layers. The crushed stone shall meet the same requirements specified for the stone foundation in **714.08.A.2**. Moisten the stone backfill material as necessary, and thoroughly compact each layer with mechanical tamping equipment. Continue the backfill with crushed stone to the depth of the bottom edge of the cable entrance in the butt-base. After completing the installation of the electrical cable, continue placing the crushed stone backfill in 6-inch layers, and compact to a depth of 1 foot below grade. Backfill the remaining 12 inches with soil in two equal layers, and thoroughly compact each layer.
3. **Wood Poles.** Place wood poles in holes excavated as specified in **714.08.A.2**. Set the pole in the center of the hole, with any vertical curvature of the pole located in the plane of the lines, and rake in a direction opposite that of the unbalanced stress where a guy or underbrace is specified. Backfill the hole with approved material applied in 6-inch layers, and thoroughly compact each layer with mechanical tamping equipment. Install cross arms and guying components, when specified, as shown on the Plans.

#### C. Highmast Tower Installation

Install standards with lowering devices on foundations constructed as shown on the Plans. Ensure that the standards are plumb. Assemble the shaft in the Engineer's presence. Do not perform any field welding between sections of the shaft. Erect the tower according to the manufacturer's recommended procedures and under the manufacturer's supervision. Make adjustments to align all parts and ensure operation. Arrange for the manufacturer or its representative to instruct the local utility in the proper operation of the lowering device.

#### 714.09 Bracket Arms

Install, on the lighting standards, bracket arms of the specified type, design, kind, dimensions, and number as shown on the Plans.

#### 714.10 Luminaires

Use the following luminaire types on the roads and bridges: High Intensity Discharge (HID) which includes High Pressure Sodium (HPS) and Metal Halide (MH); Fluorescent and Induction lamps; and Light Emitting Diode (LED).

Install luminaires of the design and size shown on the Plans, and level according to the manufacturer's recommendations, as shown on the Plans and as approved by the Engineer. Provide glare shields on luminaires when shown on the Plans.

Clamp the pole and bracket cable in the proper terminals on the terminal board in the luminaire, and then splice the cable to the proper phase and neutral conductors outside of the handhole in the pole base. After other required circuit splices are made outside of the handhole, place all of the wire inside the handhole.

Leave slack in all cables for future maintenance. Attach a suitable identification tag to each of the phase cables.

Clean luminaire reflector surfaces and glassware after installation. Perform cleaning, if required, according to the luminaire manufacturer's recommendations.

Ensure that luminaires for sign lighting are adjustable both horizontally and vertically.

**High Intensity Discharge (HID)**

High Intensity Discharge (HID) luminaires shall meet IES standards from LM-51-00 to LM-35-02. The HID luminaire shall be covered by a one-year written warranty starting from the system acceptance date. All of the other electrical and mechanical component parts of the HID shall be covered by a five-year written warranty starting from the system acceptance date. The signed warranty certificate shall be submitted prior to final payment.

**Light Emitting Diode (LED)**

Light Emitting Diode (LED) luminaires shall be manufactured in accordance with ANSI C136.37-2011 (or recent version). All testing and data sheets for proposed LEDs shall be included in the submittal package and shall include, but not limited to, the following: Illuminating Engineering Society of North America (IESNA): LM-79-08, LM-80-08, RP-8-14, TM-3-95 and TM-15-07 (all should be up-to-date versions). In addition to these requirements, the LEDs shall meet the following requirements:

1. Finished surface: Furnish luminaires with the color mentioned in the plans. The surface of luminaire housing shall meet UL-1598 listed for wet locations, ASTM B117 for salt chamber exposure, and ASTM D1654 for rust creepage.
2. Thermal Management: the luminaire shall start and operate in the ambient temperature range of -25C to +25C.
3. Optical Assembly: The LED optical assembly package shall have a minimum Ingress Protection rating of IP 66 according to ANSI/IEC 60529. The luminaire shall have a standardized refractor/reflector to meet the required optical distribution as required by the plans. The optical assembly shall utilize high brightness, long life, minimum 70 color rendering index (CRI), (3000 K-5700 K) color temperature (+/-300 K) LEDs binned according to ANSI C78.377. Lenses shall be UV-stabilized acrylic or glass. Provisions for house-side shielding shall be provided when specified.
4. Prevent the entrance of wildlife by limiting openings around the pipe tenon mounting area.
5. Electrical Parts (including Safety Testing) shall comply with an ANSI C136.41 with 7-pin receptacle that is fully pre-wire for LED driver's control.
6. Documents for the materials submitted need a certification from a National Voluntary Laboratory Accreditation Program (NVLAP) and that lab must be recognized by the U.S. Department of Energy.

**LED Luminaire Warranty**

The entire LED luminaire and all of its component parts shall be covered by a 10 year written warranty covering materials, fixture finish, and workmanship. Failure is when one or more of the following occur:

1. Negligible light output from more than 10 percent of the LED packages.
2. Condensed moisture inside the optical assembly.
3. Driver that continues to operate at a reduced output below 15 percent of the rated nominal output. The warranty period shall start from the system acceptance date. The signed warranty certificate shall be submitted prior to final payment.

**714.11 Lamps**

Install lamps of the design, type, and size, and at the locations shown on the Plans.

**714.12 Installation of Overhead Wires**

Install overhead wiring, when specified, as shown on the Plans.

**714.13 Cable Markers**

When shown on the Plans, place precast or cast-in-place concrete cable markers, of the dimensions indicated, at all locations where lighting cables make an abrupt change in direction. Construct the markers of Class A concrete meeting **604**. Imprint an arrow on each marker to indicate the direction of the cable run as it approaches and leaves the marker. Also imprint the circuit number on the marker.

Recess the markers into the ground approximately 3 inches, unless otherwise specified.

**714.14 Control Center**

Furnish and install a service pole or poles of the design, type, size, and class, and at the locations shown on the Plans. Install the service pole(s) as specified in **714.08** and as shown on the Plans. Set the service pole(s) plumb.

Notify the power company, at least 30 days before connection, of the need to furnish power to operate the lighting system.

Unless otherwise specified, furnish and install all the control center equipment and electrical supply facilities. The electrical supply facilities shall include the necessary service conduit from the control cabinet to the delivery point designated on the Plans.

Construct a concrete slab, of the dimensions and thickness indicated, around the service pole foundation. Construct the slab of Class A concrete meeting the requirements of **604**, and reinforce the slab, if specified, as shown on the Plans.

Construct a 6-foot chain-link fence and gate of the size specified around the control center as shown on the Plans and as specified in **707**.

**714.15 Field Painting**

After erection is completed, thoroughly clean steel standards that are not galvanized, and then apply two coats of inorganic zinc paint meeting the requirements of **910.03**. Perform painting as specified in **603**.

If the shop coat of prime paint is damaged, cover the damaged areas with a coat of the same type of paint as used for the original primer coat, and allow it to completely dry before applying the first coat of aluminum paint.

If the finish on galvanized steel materials is scratched, chipped, or otherwise damaged, the Engineer will reject the material, or may allow ~~it to be repaired~~~~the Contractor to repair it~~ as specified in **713.04.B**.

**714.16 Testing After Installation**

Install all materials and equipment to form a complete installation ready for operation, unless otherwise specified.

After the installation is completed, test the lighting system in the presence of a Department representative and the Maintaining Agency. Tests shall include insulation resistance, voltage, current, and performance tests. Unless otherwise specified, perform the tests in accordance with the following:

**D. Voltage Tests**

Take a voltage reading at the control center at the load side of the circuit protection device and the last lighting standard served in each branch circuit. In cases where the circuit feeds in two or more directions, take the voltage reading at the light most remote from the control point or as directed by the Engineer. Unless otherwise specified, with the complete lighting system energized and all lamps operating, the voltage of this last standard shall not be less than 90% of the nominal rated voltage of the luminaire supply circuit, and the voltage at the last underpass luminaire in each branch circuit shall not be less than the minimum operating voltage recommended by the manufacturer of the luminaire ballast.

**E. Current Test**

Conduct current tests at each control center at the load side of each circuit protection device, using a clamp-on type ammeter. Current, in amperes, in each supply conductor shall not be greater than the rated current of a luminaire times the number of luminaires in the circuit.

**F. Grounding Resistance Test**

Conduct ground resistance tests with a “megger,” manufactured by the James H. Biddle Company, or a “vibraground” manufactured by Associated Research Incorporated or approved equal.

Adhere to the following when conducting this test:

1. Ensure that no equipment, such as ballast or oil switches, is connected at the time of the test.
2. Test only one conductor at a time.
3. Isolate the conductor being tested from ground.
4. Ensure that the other phase conductor and the neutral are grounded during each test.

**G. Performance Tests**

Prior to acceptance and after all faults have been corrected, ~~the Contractor shall~~ operate the lighting system, including automatic control equipment and other specified apparatus, for a continuous 48-hour period without interruption or failure attributable to poor workmanship or defective material. After the 48 hours

of continuous operation, the Engineer will inspect all lights and equipment for normal operation. Make all necessary repairs or replacements to the Engineer's satisfaction.

Make arrangements with the Servicing Agency to purchase the electric power necessary to conduct all tests.

Furnish the Engineer five copies of the test results, together with five copies of a statement from the Maintaining Agency that the system is acceptable to the Agency.

**714.17 Repair of Seeded and Sodded Areas**

If areas previously seeded or sodded are disturbed during the performance of the work described in this Section, reseed (with mulch) or re-sod such areas as specified in **801** or **803**, respectively. Perform these repairs as the work progresses to minimize erosion of disturbed areas.

**H. 714.18 Disposal of Excess or Unsuitable Material**

Dispose of excess or unsuitable material as specified in **203.07**.

**714.19 Final Cleanup**

Perform final cleanup as specified in **104.10**. Remove existing foundations, designated for removal, to a minimum of 6 inches below grade. Before final inspection, touch-up finishes, clean surfaces including signs that are lighted, and perform such other work as directed by the Engineer to ensure the effectiveness and neat appearance of the work.

**COMPENSATION****714.20 Method of Measurement**

When the bid schedule contains an item for Roadway and Structure Lighting on a lump sum basis, measurement will be for the sum total of all items to be furnished and installed.

When the bid schedule contains items for various elements of Roadway and Structure Lighting, the Department will make measurement for payment as follows:

**A. Conduit**

The Department will measure:

1. Encased Conduit and Direct Burial Conduit by the linear foot of conduit for each kind, number, and size installed as indicated, and
2. Conduit (Structures) of the kind and size specified by the linear foot of each individual kind and size of conduit placed.

**B. Pull Boxes**

The Department will measure Pull Boxes by the unit, per each.

**C. Cable**

The Department will measure Cable of the type, and number and size of conductors specified, by the linear foot from the center to center of pull boxes, light standards, and similar features, for each type and number and size of conductors. No additional allowance will be made for slack length, length inside equipment or standards, and similar instances requiring additional length of wire.

**D. Preassembled Cable in Duct**

The Department will measure Preassembled Cable in Duct by the linear foot from the center to center of pull boxes, light standards, and similar features. No additional allowance will be made for slack length.

**E. Light Standards**

The Department will measure Light Standards of the kind and design specified by the unit, per each.

**F. Luminaires**

The Department will measure Luminaires of the size, type, and design specified by the unit, per each, regardless of their classifications (i.e. LED, HID).

**G. Overhead Conductors**

The Department will measure Overhead Conductors of the gauge, type, and kind specified by the linear foot between supports. No allowance will be made for slack length.

**H. Cable Markers**

The Department will measure Cable Markers by the unit, per each.

**I. Control Center**

The Department will measure the Control Center on a lump sum basis. Such measurement will be for the sum total of all items to be furnished and installed at the control center, except as specified in **714.20.J** and **714.20.K**.

**J. Class A Concrete**

The Department will measure Class A Concrete used to construct the concrete slab around the service pole at the control center by the volume in cubic yards, as determined from the specified thickness shown on the Plans and surface measurements for width and length. The Department will not measure reinforcement for the concrete slab for payment, but will consider the costs thereof as incidental to the item for Class A Concrete.

**K. Chain-Link Fence and Gate**

The Department will measure and pay for Fence and Gates in accordance with **707.08** and **707.09**, respectively.

**L. Navigational Lighting and Overhead Sign Lighting**

The Department will measure Navigational Lighting and Overhead Sign Lighting furnished and installed in accordance with the Plans on a lump sum basis.

**M. Incidental Items**

The Department will consider incidental, and will not directly measure, the following:

1. Excavation and backfilling performed in connection with this construction.
2. The removal and satisfactory disposal of existing pavement, surface, and base required to install conduit, and for restoring the base, pavement, and surface to their original condition.
3. Furnishing, installing, and subsequently removing sheeting, bracing, and supports needed to install conduit.
4. Labor, materials, equipment, electrical energy, and incidentals required to conduct the performance tests specified in **714.16.D**.
5. Reseeding, resodding, and otherwise restoring to their original condition areas that were disturbed during the performance of the work described in this Section.

**714.21 Basis of Payment**

When the bid schedule indicates payment will be made for Roadway and Structure Lighting on a lump sum basis, such payment is full compensation for all materials, labor, equipment, and incidentals necessary to produce a completely integrated, operative, and finished installation of a Roadway and Structure Lighting System, as shown on the Plans.

When the bid schedule contains items for various elements of Roadway and Structure Lighting, the Department will make payment as follows:

**A. Conduit**

1. **Encased Conduit.** The Department will pay for Encased Conduit at the contract unit price per linear foot, complete in place, for each kind, number, and size installed as indicated. Such payment is full compensation for all excavation, sheeting when required, backfilling, disposal of excess or unsuitable material, furnishing and placing or installing all materials and accessories, including grounding materials, concrete, and reinforcement when specified, all bends, joints, fittings and appurtenances, and installing the encased conduit complete.
2. **Direct Burial Conduit.** The Department will pay for Direct Burial Conduit of the kind, number, and size specified at the contract unit price per linear foot, complete in place. Such payment is full compensation for all excavation, sheeting when required, backfilling, jacking of conduit, disposal of excess or unsuitable material, furnishing and placing or installing all materials and accessories, including grounding materials, bedding materials when required, all bends, joints, fittings and appurtenances, and installing the conduit complete.
3. **Conduit (Structures).** The Department will pay for Conduit (Structures) of the kind and size specified at the contract unit price per linear foot, complete in place. Such payment is full compensation for furnishing

and installing all materials, including conduits, hangers, expansion fittings, grounding materials, and associated hardware and accessories, and installing the conduit complete.

**B. Pull Boxes**

The Department will pay for Pull Boxes at the unit price per each, complete in place. Such payment is full compensation for furnishing and installing or constructing pull boxes and for all excavation, backfilling, and other work connected therewith.

**C. Cable**

The Department will pay for Cable of the type, and number and size of conductors, as specified, at the contract unit price per linear foot, complete in place. Such payment is full compensation for furnishing and installing the cable and grounding materials, making splices, joints and connections, and for trenching, furnishing, and placing cushion and backfill material, and disposing of excess or unsuitable excavated material.

**D. Preassembled Cable in Duct**

Preassembled Cable in Duct of the kind and size specified will be paid for at the contract unit price per linear foot, complete in place. Such payment is full compensation for furnishing and installing the cable duct, grounding materials, making splices and connections, and for trenching, furnishing, and placing cushion and backfill material, and disposing of excess or unsuitable excavated material.

**E. Light Standards**

The Department will pay for Light Standards of the type specified at the contract unit price per each, complete in place. Such payment is full compensation for furnishing and installing the complete light standards, including the foundation, standard, bracket arm or arms, associated hardware and wiring, grounding materials, excavation, backfilling materials, and backfilling. The Department will measure foundations for high mast towers separately.

**F. Luminaires**

The Department will pay for Luminaires of the size and type specified at the contract unit price per each, regardless of their classifications (i.e. LED, HID), complete in place. Such payment is full compensation for furnishing and installing the complete luminaire, including the ballast(s), lamp(s), glare shields where required, and associated hardware and wiring.

**G. Overhead Conductors**

The Department will pay for Overhead Conductors of the gauge, type, and kind specified at the contract unit price per linear foot, complete in place.

**H. Cable Markers**

The Department will pay for Cable Markers of the design specified at the contract unit price per each, complete in place. Such payment is full compensation for furnishing and installing the marker complete, including the excavation, backfilling, and removal and disposal of excess or unsuitable excavated materials.



**I. Control Center**

The Department will pay for the Control Center at the contract unit price per lump sum, complete in place. Such payment is full compensation for furnishing and installing all equipment and materials, including service pole(s) when specified, and photoelectric relays, relay cabinets, multiple relays, lightning arrestors, fuse cutouts, and all other equipment, materials, associated hardware, and accessories, as shown on the Plans. Payment for the Control Center is full compensation for furnishing and installing all electrical supply facilities from the delivery point for electrical energy, as shown on the Plans, to the control center.

**J. Class A Concrete**

The Department will pay for Class A Concrete, measured as specified in **714.20.J**, at the contract unit price per cubic yard, complete in place.

**K. Navigational Lighting and Overhead Structure Lighting**

The Department will pay for Navigational Lighting and Overhead Structure Lighting by the lump sum complete in place including all materials and labor.”

**Subsection 730.11** (pg. 835), 6-27-16; Revise the title:

“AnchorRods”

**Subsection 730.11** (pg. 835), 6-27-16; revise the first paragraph:

“Furnish, with anchor-base type poles, anchor rods meeting the requirements of ASTM F1554, Grade as required by design. Fit each anchor bolt with two heavy hex nuts. Hot-dip galvanize all nuts and not less than 10 inches of the threaded ends of anchor bolts according to ASTM A153. The anchor bolts shall be capable of resisting at yield strength stress the bending moment of the shaft at its yield strength stress.”

**Subsection 730** (pg. 828-880), 11-6-17; replace section with the following:

|

SECTION 730 – TRAFFIC SIGNALS

730.01 Description of Work .....19

730.02 Regulations and Code .....19

730.03 Submittal Data Requirements .....19

730.04 Mill Test Reports and Certification .....20

730.05 Working Drawings.....20

730.06 Guarantee .....21

730.07 Training .....21

730.08 Excavating and Backfilling .....21

730.09 Removing and Replacing Improvements .....22

730.10 Foundations .....22

730.11 Anchor Bolts.....22

730.12 Pull Boxes .....22

730.13 Transformer Base .....23

730.14 Conduit .....23

730.15 Conductors .....25

730.16 Cable .....25

730.17 Wiring.....25

730.18 Service Connection .....25

730.19 Sealant .....25

730.20 Strand Cable .....26

730.21 Bonding and Grounding.....26

730.22 Field Test .....26

730.23 Inspection .....26

730.24 Signal Heads .....27

730.25 Controllers.....30

730.26 ~~Traffic Actuated Controllers~~Cabinets .....39

730.27 Auxiliary Equipment for Traffic ~~Actuated-Signal~~Controllers.40

730.28 ~~Flashing School~~Miscellaneous Traffic Signals .....42

730.29 Detectors .....46

730.30 ~~Coordination~~(Reserved) .....50

730.31 ~~Time-Based Coordination Units~~(Reserved) .....51

730.32 Cantilever Signal Supports .....52

730.33 Steel Strain Poles.....54

730.34 Pedestal Support Signal Poles.....54

730.35 Wooden Pole Signal Supports.....55

730.36 Pole Location .....55

730.37 Method of Measurement .....56

730.38 Basis of Payment .....60

**DESCRIPTION****730.01 Description of Work**

This work consists of furnishing and installing all necessary materials and equipment to complete in-place traffic signal systems, modify existing systems, or both, all as shown on the Plans or the Standard or Special Details, and as specified in these Specifications. Unless otherwise shown on the Plans or specified in the Special Provisions, all materials shall be new.

Where existing systems are to be modified, incorporate the existing material into the revised system, salvage it, or abandon it as specified or as directed by the Engineer.

Furnish and install all incidental parts that are not shown on the Plans or specified herein, but that are necessary to complete the traffic signal or other electrical systems, or that are required for modifying existing systems, as though such parts were shown on the Plans or specified herein. Include the costs of such incidentals in bid price for other items. All systems shall be complete and in operation to the Engineer's satisfaction at the time of completion of the work.

**GENERAL REQUIREMENTS****730.02 Regulations and Code**

Ensure that all equipment provided conforms to NEMA Standards Publication, Traffic Control Systems, latest revision, or the Radio Manufacturers Association, whichever is applicable. In addition to the requirements of these Specifications, the Plans, and the Special Provisions, all material and work shall conform to the requirements of the NEC and the NESC; the Standards of ASTM, ANSI, ITE, and IMSA; the MUTCD; and other applicable local ordinances.

Wherever reference is made to the NEC, or the Standards mentioned above, consider the reference to mean the code or standard that is in effect on the date of advertising the bids or authorization for force account.

**730.03 Submittal Data Requirements**

Within 30 days after the issuance of the work order, submit to the Engineer, the Traffic Operations Division ~~of Materials and Tests~~, and the local entity (city or county engineer), one collated set of the manufacturer's descriptive literature and technical data that fully describes the types of signal equipment proposed for use. In the descriptive literature, identify the manufacturer and models and include sufficient information for the Engineer to determine if the equipment or material meets the requirements of the Plans and these Specifications. Include with these sets of submittal data a list of the materials submitted along with descriptive material for, but not limited to, the following items:

1. Controller
2. Cabinet and Exhaust Fan
3. Detectors
4. Signal Heads including Lamp Information and Mounting Hardware
5. Loop Wire and Loop Sealant
6. Shielded Detector Cable
7. Signal Cable
8. Cable for Span Wire, Guys, and similar features
9. Pull Boxes
10. Conduit
11. Coordination Equipment

Also include in the submittal sets detailed scale drawings of all non-standard or special equipment and of all proposed deviations from the Plans. Upon request, submit for approval sample articles of materials proposed for

use. The Department will not be liable for any materials purchased, labor performed, or delay to the Work prior to such approval.

In addition to the above, submit to the Engineer a notarized letter certifying that all traffic signal materials listed in the submittal conform to the Plans and Specifications along with a copy of a statement from the maintaining agency that the system is acceptable to the agency. Any material substitutions requested by the maintaining agency shall meet minimum Department standards and shall be approved by the Department in writing prior to purchase or installation. The Department will not be liable for any materials purchased, labor performed, or delay to the Work regarding such approval.

Submit ~~six prints~~ an electronic copy in PDF format of “Design” or “Shop” drawings, indicating the proposed dimensions and material specification for each of the supports and mast arms involved, to the Division of Structures for approval purposes within 30 days after the work order is issued. The Department will review these drawings at the earliest possible date, and will return ~~two prints~~ the electronic copy marked “Approved for Fabrication,” or “Returned for Revisions as Noted.” Respond by taking appropriate action to ensure the earliest possible correction of these items so as not to delay the installation.

**730.04 Mill Test Reports and Certification**

Provide Mill Test Reports (MTR) or Certifications of Conformance to the Specifications for Materials and Design for all materials incorporated into the Work. Supply the following prior to acceptance of the structures:

1. MTRs for MAJOR structural items only, as identified in Table 730.04-1, shall include both physical and chemical descriptions of the material as supplied to the fabricator. When physical properties are altered during the fabrication, supplement the MTR covering chemical composition with certified test reports indicating the physical properties of this material after fabrication.
2. Certifications of Conformance to the Specifications for all remaining material not covered by MTR as identified in Table 730.04-1.
3. Certification that all welding was performed by operators qualified as follows: Steel welders to AWS and aluminum welders to ASME.
4. Certification of Conformance to the Specification for the Design of all components not completely dimensioned and detailed on the Standard Drawing.

**Table 730.04-1: Required Mill Test Reports and Certifications**

<b>Component Materials</b>	<b>MTR</b>	<b>Certification</b>
Tubes for arms and poles	X	
Base Castings	X	
Anchor Bolts	X	
Pole tops, misc. fittings, and hardware		X
Fabricated or cast-type arm connections		X
Galvanizing		X

**730.05 Working Drawings**

Provide within the controller cabinet and to the local maintaining agency an electrical schematic diagram of the cabinet and system wiring. Submit manufacturer’s instructions for installation, maintenance, and operation of all equipment to the local maintaining agency and also place a copy within the controller cabinet. Place all such materials inside a plastic envelope mounted in the cabinet.

**730.06 Guarantee**

Guarantee the Traffic Signal System(s) installed under these Specifications, including all equipment, parts, and appurtenances in connection therewith, to the City or County and State against defective workmanship and materials for a period of not less than 1 year following the date the signal system is installed and made operational, except in no case shall this guarantee expire prior to 3 months after the final acceptance of the Project. Upon completion of the Project, turn over to the government agency responsible for maintaining the signal installation all warranties or guarantees on equipment and materials that are offered by the manufacturers as normal trade practice ~~and that have not expired.~~

**730.07 Training**

Provide to the maintaining agency and/or the Department a training session on the controller and associated cabinet equipment to be supplied on the Project. The training session shall last for a minimum 4 hours unless the maintaining agency and/or the Department determines a lesser time is adequate. Train the user in the complete operation and programming features of all controllers. Provide this training prior to the acceptance of the Project at a facility agreed upon by the maintaining agency.

After the required training, certify to the Engineer that training has been completed.

This training requirement shall not apply if a training program meeting these criteria has been provided to the maintaining agency by this vendor and/or manufacturer on the equipment being bid within 18 months prior to the date of the invitation to bid. This requirement shall apply if the bidder is proposing new, upgraded, or modified equipment not covered in the previous training program.

**MATERIALS AND INSTALLATION****730.08 Excavating and Backfilling**

Perform excavation needed to install conduit, foundations, and other equipment, so as to cause the least possible damage to the streets, sidewalks, and other improvements. Excavate trenches no wider than necessary to properly install the electrical equipment and foundations. Do not begin excavating until immediately before installing conduit and other equipment. Place the material from the excavation where it will cause the least disruption and obstruction to vehicular and pedestrian traffic and the least interference with the surface drainage.

Backfill the excavations and compact to at least the density of the surrounding material. Remove all surplus excavation material and dispose of outside the highway right-of-way, in accordance with **203.07**, or as directed by the Engineer.

After backfilling, keep excavations well-filled, and maintain in a smooth and well-drained condition until permanent repairs can be made.

At the end of each day's work, and at all other times when construction operations are suspended, remove all equipment and other obstructions from that portion of the roadway used by public traffic, and park a minimum of 30 feet from the edge of pavement unless otherwise protected by guardrail, bridge rail, or barriers installed for other purposes.

Perform excavation in the street or highway so as to restrict no more than one traffic lane in either direction at any time. Do not obstruct traffic during hours of peak flow unless otherwise approved by the Engineer. Incorporate construction signing in accordance with the MUTCD.

**730.09 Removing and Replacing Improvements**

Replace or reconstruct, with the same kind of materials as found on the Work, improvements, such as sidewalks, curbs, gutters, Portland cement concrete and asphalt concrete pavement, bituminous surfacing, base material, and all other improvements removed, broken, or damaged by the Contractor.

Before removing the sidewalk and pavement material, use an abrasive type saw to cut, to a minimum depth of 2 inches, the outline of all areas to be removed in Portland cement concrete sidewalks and in all pavements. Use any method satisfactory to the Engineer to cut the remainder of the required depth. Make cuts neat and true with no shatter outside the removal area.

Whenever a part of a square or slab of existing concrete sidewalk or driveway is broken or damaged, remove the entire square or slab and reconstruct the concrete as specified above.

Perform all work in accordance with these Specifications, or the applicable local ordinance, whichever is of a higher standard. Consider this removal and replacement work to be incidental to other items.

**730.10 Foundations**

Construct foundations for posts, standards, and cabinets of Class A Portland cement concrete.

Pour foundations for posts, standards, and pedestals after the post, standard, pedestal, or anchor bolts or reinforcing steel is in proper position. Form the exposed portions to present a neat appearance. Rest the bottom of concrete foundations on firm undisturbed ground.

Construct forms to be true to line and grade. Finish tops of footings for posts and standards, except special foundations, to curb or sidewalk grade or as ordered by the Engineer. Use rigid forms, securely braced in place. Place conduit ends and anchor bolts by means of a template until the concrete sets. Moisten both the forms and the ground that will be in contact with the concrete before placing concrete. Do not remove forms until the concrete has cured for at least 12 hours and hardened sufficiently to allow form removal without causing damage to the concrete.

Apply an ordinary surface finish to exposed surfaces of concrete. Wherever the edge of a concrete foundation or sidewalk section is within 18 inches of any existing concrete improvement, extend the sidewalk section to meet the existing improvement.

Where obstructions prevent the construction of planned foundations, construct a foundation satisfactory to the Engineer.

**730.11 Anchor Rods**

Furnish, with anchor-base type rods, anchor bolts meeting the requirements of ASTM F1554, grade as required by design. Fit each anchor bolt with two heavy hex nuts. Hot-dip galvanize all nuts and not less than 10 inches of the threaded ends of anchor bolts according to ASTM A153. The anchor bolts shall be capable of resisting at yield strength stress the bending moment of the shaft at its yield strength stress.

Set standards, posts, and pedestals plumb by adjusting the nuts before the foundation is finished to final grade. Do not use shims or similar devices for plumbing or raking. After plumbing or raking has been completed, cut off anchor bolts 1/4 inch above the top nut, and paint the exposed surface with rust protective paint.

Furnish all anchor bolts and nuts required for relocating existing standards and posts.

**730.12 Pull Boxes**

Construct and install pull boxes as shown on the Plans and the Standard Drawings or as directed by the Engineer. Additional pull boxes may be required where conduit runs are more than 150 feet long. The maximum spacing

between pull boxes shall be 150 feet, unless otherwise directed by the Engineer. Install pull boxes wherever practicable out of the line of traffic. Set covers level with the pavement, or with the curb or sidewalk grade, or with the surrounding ground as required.

Place electrical conductors within pull boxes so as to be clear of the metal frame and cover.

Rest the bottom of the pull box firmly on a bed of crushed stone with a minimum depth of 12 inches below the bottom, and extending 6 inches beyond the outside edge of the pull box, unless otherwise directed by the Engineer.

#### **A. Concrete Pull Boxes**

Construct concrete pull boxes of a mixture of one part cement, two parts sand, and four parts gravel or 1-inch crushed stone with reinforcement placed as shown on the Standard Drawings. Reinforcement shall consist of welded wire reinforcement, 4 x 4 inches - No. 4/4 at 85 pounds per 100 square feet, meeting the requirements of **907.03**. Pull boxes may be poured in place or precast. The color of the pull box concrete material shall match the surrounding concrete color.

Install a cast iron frame and cover of the dimensions shown on the Drawings in each pull box. Provide castings of Class 30, meeting the requirements of **908.07**. The covers shall have a roughened top surface of 1/8 inch in relief. Provide notches for removing the cover. Inscribe the words "TRAFFIC SIGNALS" on top of the covers with letters 1-1/2 inches high and 1/8 inch in relief as shown on the Drawings.

The frame shall have a minimum weight of 42 pounds. The cover shall be of the "Extra Heavy" type with a minimum weight of 54 pounds.

#### **B. Reinforced Plastic or Epoxy Mortar Pull Boxes**

Ensure that pull boxes composed of reinforced plastic or epoxy mortar are designed and tested to temperatures of -50 °F and meet the requirements of the following: ASTM D543, ASTM D570, ASTM D790, and ASTM D635, and are based on a 30,000-pound single axle load over a 10 x 20 inch area. The top of the pull box shall consist of a concrete frame (ring) and cover. The color of the pull box concrete material shall match the surrounding concrete color. Inscribe the words "TRAFFIC SIGNALS~~Traffic Signals~~" on top of the covers.

### **730.13 Transformer Base**

Fabricate the transformer base from steel plate and sheet, and design it to harmonize with the shaft. Provide each transformer base with:

1. One 7-1/2 x 9 inch minimum handhole, with a cover secured with stainless steel fastening screws;
2. Four galvanized steel bearing plates to fasten the base to the anchor bolts;
3. Four galvanized steel bolts, nuts, and washers to fasten base and standard; and
4. One 1/2-inch, 13 UNC grounding nut welded to the inside of the base opposite the handhole opening.

Ensure that the strength of the transformer base is comparable with that of the shaft.

When a transformer base is required, no handhole will be required in the shaft.

### **730.14 Conduit**

Furnish and install plastic and steel conduit in accordance with these Specifications and close conformity with the lines shown on the Plans or as established by the Engineer.

Threads shall be clean cut, straight, and true and of sufficient length to allow proper coupling. Do not use long running threads on any part of the Work. Protect threads in transit and during installation, and provide conduit with proper supports and protection during construction to prevent damage. Properly thread, ream, and cap all ends of pipe installed for future connections to prevent water and foreign matter from entering the conduit system. Provide threaded ends with approved conduit bushings.

Signal conduit shall be a minimum 2 inches in diameter, and detector conduit a minimum 1 inches in diameter, unless otherwise specified or directed by the Engineer. Conduit for service connections shall be 1-1/4 inches in diameter. Do not use conduits smaller than 1 inch in diameter unless otherwise specified, except grounding conductors at service points shall be enclosed in 3/4-1/2-inch diameter conduit. Larger-sized conduit may be used. The Contractor may, at no additional cost to the Department, use larger size conduit, in which case it shall be for the entire length of the run with no reducing couplings allowed.

#### A. Materials

Provide conduits and fittings of the type as shown in the construction plans or as directed by the Engineer and as follows:

##### 1. Steel Conduit

- a. Rigid conduit and fittings shall be heavy-wall, hot dipped galvanized steel conforming to Federal Specification WW-C-581-d(3) and ANSI C80.1. It shall be galvanized inside and out and shall meet the requirements of ASTM A53. Each length shall bear the label of Underwriters Laboratories, Inc.
- b. Flexible conduit shall be galvanized flexible steel meeting Federal Specification WW-C-581-d(3), ANSI C80.1 and UL Standard 6 with a minimum 40-mil thickness of polyvinyl chloride (PVC) coating conforming to ASTM D746.

2. Plastic Conduit. For plastic conduit, provide high impact PVC, Schedule 40 or Schedule 80.

2.3. High-Density Polyethylene (HDPE). Materials used for the manufacture of HDPE conduit and fittings shall be per ASTM F2160 and consist of a Standard Dimension Ratio (SDR) 9-11. No other substitutions shall be allowed unless directed by the Engineer. HDPE conduit can be used with preassembled cable and rope-in-conduit.

#### B. Installation

All bends shall be in strict compliance with the NEC.

Lay conduits to a minimum depth of 6 inches below subgrade but not less than 24 inches below pavement grade except when approved by the Engineer; conduit may be laid at a depth of not less than 24 inches below top of curb when placed in back of the curb. Place conduit runs for detectors parallel to existing or proposed curbs and not more than 18 inches behind the curb face unless other specified. Place steel conduit or Schedule 80 PVC conduit under existing pavements by approved jacking or drilling methods. Do not disturb pavements without the Engineer's approval. Where trenching is allowed in a traffic bearing area, use PVC conduit (Schedule 40) encased in concrete.

Conduits shall be continuous and extend from end point (i.e. pull box, foundation signal pole, pedestal pole, etc.) to another end point, or as directed by the Engineer. Conduit splicing shall not be permitted between end points.

After completing the installation of the conduit, test all conduits installed under the Contract with a mandrel having a diameter 1/4-inch smaller than the conduit and a length of 2 inches. Repair, to the Engineer's satisfaction, all conduits that will not allow passage of the mandrel; if repairs cannot be accomplished, remove



and replace the conduit at no additional cost to the Department. After the mandrel test, scour all conduits with a stiff wire brush slightly larger in diameter than the conduit. Clear all conduits in the Engineer's presence.

Extend conduits terminating in anchor base standards and pedestals approximately 2 inches above the foundation and slope them toward the hand-hole opening. Conduits shall enter concrete pull boxes from the bottom and shall terminate not less than 2 inches nor more than 4 inches above the bottom of the box and near the box walls to leave the major portion of the box clear.

Clean existing underground conduit to be incorporated into a new system by blowing with compressed air, or by other means approved by the Engineer.

### **730.15 Conductors**

Furnish and install conductors in accordance with these Specifications and close conformity as shown on the Plans, or as directed by the Engineer.

Traffic Control Conductors shall be rated at 600 volts. Run all conductors, except loop conductors and cables run along messengers, in conduit, except where run inside poles. Where signal conductors are run in lighting standards containing high voltage street lighting conductors, encase the signal conductors in flexible or rigid metal conduit. Where telephone circuits are introduced into controller foundations, encase the telephone conductors in flexible metal conduit and in conformance with the NEC.

Conductors for traffic loops shall be continuous AWG No. 14 XLP stranded wire to the detector terminals or spliced with shielded detector cable within a pull box, conduit, or pole base.

Detector cable shall be two conductor twisted pair shielded AWG No. 14 stranded meeting IMSA Specification No. 1950-2.

### **730.16 Cable**

All signal cable shall conform to applicable IMSA Specification No. 19-1 or 20-1. Use stranded cable color coded AWG No. 14 for all signal and accessory circuits. Retain the same color identification for the entire length of a circuit run.

### **730.17 Wiring**

1. Terminate all wiring to screw terminals using lugs.
2. Make all splices with solderless connectors, and insulate splices with weatherproof tape applied to a thickness equal to the original insulation.
3. Attach cables to messenger with non-corrosive lashing rods or stainless steel wire lashings.
4. All wiring within enclosed cabinets shall be neatly formed and harnessed and shall have sufficient length for access and servicing.

### **730.18 Service Connection**

Coordinate service connection details and metering with the local utility as directed by the Engineer and in conformance with the City and County requirements. Obtain the necessary service for each installation.

### **730.19 Sealant**

Provide sealant material selected from the Qualified Products List maintained by the Department's Material and Test Division for sealing saw-cuts. The sealant material shall resist the upward movement of loop and lead-in and shall

exhibit stable dielectric characteristics, including a low permittivity and high dielectric strength. It shall bond to the roadway paving material, preventing entry of moisture, and shall remain flexible without melting through the anticipated temperature and weather conditions.

**730.20 Strand Cable**

Span cable for suspending signal heads between pole supports shall be 7-strand, Class A, copper-covered steel wire strand or greater, meeting the requirements of ASTM A460, with a minimum breaking strength as noted on the Plans. An acceptable alternate is 7-strand steel wire with a Class A zinc coating meeting the requirements of ASTM A475, with a minimum breaking strength as shown on the Plans.

Strand cable for messenger wire (other than span wire as specified above) and pole guy cable use shall be of the diameter(s) shown on the Plans and shall meet the requirements of ASTM A475 for zinc-coated steel wire strand, 7-strand Siemens-Martin Grade with a Class A zinc coating or greater.

A Figure 8 cable combining the messenger cable and conductor cable in an insulated jacket is an acceptable alternate to conductor cable lashed to a messenger cable.

**730.21 Bonding and Grounding**

Make metallic cable sheaths, conduit, transformer bases, anchor bolts, and metal poles and pedestals mechanically and electrically secure to form a continuous system, and ensure they are effectively grounded. Bonding and grounding jumpers shall be copper wire or copper strap of not less than the same cross-sectional area as No. 6 AWG.

Furnish and install a ground electrode at each service point. Ground electrodes shall be one-piece lengths of copperweld ground rod not less than 8 feet in length and 1/2 inch in diameter, installed in accordance with the NEC. Ground the conduit and neutral as required under the NEC, except that grounding conductors shall be No. 6 AWG or approved equal, as a minimum. Enclose exposed ground conductors in 1/2-inch diameter conduit, and bond to the electrode with a copperweld ground clamp.

**730.22 Field Test**

Prior to completing the work, conduct the following tests on all traffic signal and lighting circuits in the Engineer's presence:

1. Test for ground in circuit.
2. Conduct a megger test on each circuit between the circuit and ground. The insulation resistance shall be not less than the values specified in Section 119 of the NEC.
3. Conduct a functional test to demonstrate that each part of the system functions as specified or intended herein.
4. Test all detector loops and leads before and after they are sealed in the pavement to ensure there are no shorts to ground in the system and to ensure that the loop plus lead-in inductance is within the operating range of the detector.

Replace or repair, in a manner approved by the Engineer, all faults in material or in the installation revealed by these tests. Repeat the applicable testing until no fault appears.

**730.23 Inspection**

After completion of the installation and before final acceptance of the Project, conduct a full operational check of the system under actual traffic conditions in the presence of the Engineer. The operational check shall cover a

minimum time period of 30 calendar days. During this period, perform all necessary adjustments and replace all malfunctioning parts of the equipment required to place the system in an acceptable operational condition at no additional cost to the Department. Perform all work and furnish all materials required under these Specifications subject to the direct supervision, inspection, and approval of the Engineer. Provide the Engineer and authorized representatives free access to the work, and to all plants, yards, shops, mills, and factories where, or in which, articles or materials to be used or furnished in connection with such work are being prepared, fabricated, or manufactured. Provide full and sufficient information to determine that the performance of the work, the character of materials, and the quality of workmanship and materials meets the intent of these Specifications.

Only perform work in the presence of the Engineer or the Inspector appointed by the Engineer, unless permission to do otherwise has first been obtained. The Engineer may reject any work that is performed or constructed in the absence of the Engineer or Inspector, without such permission having been granted, either expressly or by implication.

The inspection of the work shall not relieve the ~~Contractor of its~~ obligation to properly fulfill the Contract as specified. If the Engineer finds a part of the work, or the materials used in the work, to be defective or unsuitable at any time prior to final acceptance, repair or replace such defective or unsuitable work or material.

Request the presence of an Engineer or Inspector in connection with the work under these Specifications at least 24 hours before such services will be required.

## SIGNAL HEADS

### 730.24 Signal Heads

Signal heads shall meet the latest requirements published in the Equipment and Materials Standards of the Institute of Transportation Engineers (ITE) for Adjustable Face Vehicle Traffic Control Signal Heads” and the National Electrical Code. The arrangement of traffic signal heads shall be mounted as shown on the Plans or as specified by the Engineer and be in accordance with the latest versions of the MUTCD and the TDOT Traffic Design Manual.

~~Each vehicle signal head shall:~~

- ~~1. Be of the adjustable, colored lens, vertical type with the number and type of lights detailed as specified herein and as shown on the Plans;~~
- ~~2. Provide a light indicator in one direction only;~~
- ~~3. Be capable of adjustment (without attachments) through 360 degrees about a vertical axis; and~~
- ~~4. Be mounted as shown on the Plans or as directed by the Engineer.~~

~~Arrange the lenses in the signal faces in accordance with Section 4B-9 of the MUTCD. All lenses shall be glass. All circular indications shall use 12-inch lenses unless otherwise shown on the Plans. All arrow indications shall use 12-inch lenses. All new vehicle signal heads installed at any one intersection shall be of the same style and from the same manufacturer. Apply one or more coats of primer to all signal heads, signal head mountings, and outside of hoods, followed by two coats of high quality synthetic resin enamel of Traffic Signal Yellow meeting or exceeding Federal Specifications TT-C 595 Gloss Yellow. All exposed metal signal housings, doors, visors, backplates and framework parts shall be painted with a powder coated finish and be in accordance to the MUTCD specifications.~~

~~Apply one or more coats of primer to louvers as specified, signal hood interiors, and back plates, followed by two coats of Lusterless Black Enamel meeting or exceeding Master Painters Institute (MPI) Reference 94. Examine all factory enameled equipment and materials for damaged paint after installation, and repair such damaged surfaces to the Engineer’s satisfaction. Factory applied enamel finish in good condition and of appropriate color will be acceptable.~~

Suspensions for span wire mounting of multi-faced signal heads and signal head clusters (such as a 5-section signal head) shall include an approved swivel type balance adjuster for proper vertical alignment.

~~Fabricate signal heads from die cast bodies. Sand castings will not be acceptable.~~ Signal head housings shall be cast aluminum and all associated parts/hardware shall be of non-corrosive material.

~~Ensure that all signal heads meet the minimum Contract requirements for adjustable face vehicle traffic control signal heads.~~

In addition to these requirements, comply with the following:

#### **A. Optical Units**

~~Signal lamps for 8 inch lenses shall be clear, 595 rated initial lumen output, with a minimum life of 6,000 hours. Signal lamps for 12 inch lenses shall be clear, 1750 rated initial lumen output, with a minimum life of 6,000 hours.~~

Traffic signal indications shall be LED type and meet the Institute for Transportation Engineers (ITE) latest LED specifications. All LED indications shall have a five year warranty.

#### **~~A~~.B. Signal Head Mounting and Mounting Brackets**

Furnish signal heads that either have integral serrations or are equipped with positive lock rings and fittings designed to prevent heads from turning due to external forces. Lock ring and connecting fittings shall have serrated contacts. Provide signals with water-tight fittings, using neoprene washers.

Support bracket-mounted signal heads, as shown on the Plans, by mounting brackets consisting of assemblies of 1-1/2 inch standard pipe size. Ensure that all members are either plumb or level, symmetrically arranged, and securely assembled. Conceal all conductors within poles and mounting assembly. Secure each slip fitter to the pole.

#### **~~B~~.C. Directional Louvers**

Where shown on the Plans, furnish and install louvers in the hoods of the signal head sections designated.

Directional louvers shall have a snug fit in the signal hoods. Construct the outside cylinder and vanes from a non-ferrous metal or galvanized sheet steel. ~~Paint louvers with two coats of black enamel as specified in 730.24.F.~~ Louvers shall be painted with a powder coated finish.

#### **~~C~~.D. Back Plates**

Where shown on the Plans, furnish and attach back plates to the signal heads. All back plates shall be louvered and constructed of 3,003, half-hard, 0.051-inch minimum thickness aluminum sheet. Other materials such as plastic or fiberglass may be used where approved. In fabricating back plates, bend back the inside vertical edges, adjacent to the signal head, to form mounting brackets for attaching to the signal. Form back plates in two or more sections and bolt together, thus allowing for installation after signal heads are in place. Back plates shall have a dull black appearance in the front and back.

#### **~~D~~.E. Wiring**

Signal head leads shall be No. 18 AWG stranded with 221 °F thermoplastic insulation. Wire a separate white (common) lead to each socket shell; and wire a colored lead, corresponding to the color code shown on the Plans, to each socket terminal. Provide leads of sufficient length to allow connection to the terminal block

specified. Provide each complete signal head with a minimum 4-point terminal block, properly mounted in a signal section. Stud type terminal blocks shall have not less than 1/4-inch edge clearance to any portion of the stud. Exterior wiring shall have a 360-degree drip loop in advance of entering the head.

#### E.F. Pedestrian Signals

~~When shown on the Plans, provide pedestrian signals conforming to the following:~~

- ~~1. Pedestrian indications should attract the attention of and be readable to the pedestrian both day and night and at all distances from 10 feet to the full width of the area to be crossed.~~
- ~~2. All pedestrian indications shall be rectangular in shape and shall consist of the lettered messages WALK and DON'T WALK. For the purposes of these Specifications, interpret the messages WALK and DON'T WALK to be equivalent to the international symbols of a "Walking Figure" and "Upraised Hand," respectively.~~
- ~~3. When illuminated, the WALK indication shall be lunar white meeting ITE standards, with an opaque material obscuring all but the letters.~~
- ~~4. When illuminated, the DON'T WALK indication shall be Portland Orange meeting ITE standards, with an opaque material obscuring all but the letters.~~
- ~~5. When not illuminated, the WALK and DON'T WALK messages shall not be distinguishable by pedestrians at the far end of the crosswalk they control.~~
- ~~6. The letters shall be at least 3 inches high for crossing where the distance from the near curb to the pedestrian signal indication is 60 feet or less. For distances over 60 feet, the letters shall be at least 4 1/2 inches high.~~
- ~~7. Design and construct the light source so that in case of an electrical or mechanical failure of the word DON'T, the word WALK of the DON'T WALK message will also remain dark.~~

~~Provide each section with a visor encompassing the top and sides of the signal face of a size and shape adequate to shield the lens from external light sources. Provide lamps of the 69 watt traffic signal type.~~

~~Pedestrian signal heads shall meet the latest requirements published in the Equipment and Materials Standards of the Institute of Transportation Engineers (ITE) for Adjustable Face Pedestrian Signal Heads", the National Electrical Code and be compatible with NEMA standards. The arrangement of pedestrian signal heads shall be mounted as shown on the Plans or as specified by the Engineer and be in accordance with the latest versions of the MUTCD and the TDOT Traffic Design Manual. The pedestrian indications shall be LED symbols and in conformance with the Institute for Transportation Engineers (ITE) latest LED specifications. All LED indications shall have a five year warranty.~~

In addition, where pedestrian signal heads are provided, they shall:

1. include a pedestrian change interval countdown display where the calculated pedestrian change interval is more than 7 seconds;
2. include Accessible Pedestrian Signals and pedestrian pushbuttons complying with MUTCD Accessible Pedestrian Signals section;
3. incorporate a locator tone meeting the requirements of the MUTCD Accessible Pedestrian Signals;
4. include a pedestrian pushbutton with tactile vibrating arrow button and audible sound.

The pedestrian countdown display shall conform to the latest FCC regulation on Emission of Electronic Noise.

The manufacturer must supply certification, which includes a copy of the test report by an independent technical laboratory as to the compliance with ITE specifications (where it applies). The report shall also indicate that the tests were performed only after the modules received a thirty (30) minute operational warm-up period immediately preceding the tests.

The housing door, door latch, and hinges shall be of aluminum, or polycarbonate or approved equal. Hinge pins shall be stainless steel. Provide the door with a neoprene gasket capable of making a weather resistant, dust-proof seal when closed.

All pedestrian signal heads, mountings, outside of hoods, and pedestrian push button housings shall have have a powder coated finish (if aluminum) or colored resin (if polycarbonate) in accordance to MUTCD specifications, one or more coats of primer followed by two coats of high quality synthetic resin enamel of Traffic Signal Yellow, meeting or exceeding Federal Specifications TT C 595 Gloss Yellow. The interior of signal hoods shall have one or more coats of primer followed by two coats of Lusterless Black Enamel meeting or exceeding MPI Reference 94. Examine all factory enameled equipment and materials for damaged paint after installation, and repaint such damaged surfaces to the Engineer's satisfaction. Factory applied enamel finish in good condition and of appropriate color will be acceptable.

#### **F.G. Signal Head Installation**

Install signal heads and pedestrian signal heads with the faces completely covered until the entire installation is ready for operation.

### **CONTROLLERS – GENERAL**

#### **730.25 Controllers**

A controller shall consist of the complete electrical mechanism for controlling the operations of traffic control signals, including the timing mechanism and necessary auxiliary equipment, mounted in a cabinet.

#### **A. Interval Sequence**

The color sequence of signal indications shall be green, yellow, and red. Overlaps, such as green and yellow indications showing at the same time, will not be permitted. During any interval there shall be no visual flicker of signal indications. Under no conditions shall controllers allow conflicting green signal indications to be displayed.

#### **B. Flashing Operations**

Equip controllers to allow any combination of flashing red or yellow lights. However, set the flashing operation for flashing yellow lights on the main street or highway unless otherwise specified in the Special Provisions, shown on the Plans, or directed by the Engineer. The flashing mechanism shall produce between 50 and 60 flashes per minute through two 120 volt, 15 ampere circuits. One illuminated period at each flash shall not be less than 1/2 and not more than 2/3 of the total cycle.

Pedestrian signals shall be dark during flashing operations. During normal operation, pedestrian signals shall flash DON'T WALK during the pedestrian clearance interval.

Use two circuit solid state flashers unless otherwise specified.

**C. ~~Wiring Diagrams~~**

~~Submit a schematic wiring diagram of the controllers and auxiliary equipment at the time the controllers are delivered, or prior to ordering if requested by the Engineer. This diagram shall show in detail all circuits and parts. Identify such parts on the diagram by name or number and in such a manner as to be readily interpreted.~~

**D. ~~Operating Line Voltage~~**

~~Provide equipment designed to operate from a 120 volt, 60 cycle AC supply. Operation shall be satisfactory at voltages from 105 to 130. All operating voltages into and out of the controller shall be NEMA level DC voltages, except for AC power (connector A, pin p and U).~~

Controller equipment shall be permanently marked with the manufacturer’s name or trademark, part number, and serial number.

Controllers must meet the following applicable industry standards and amendments:

NEMA TS2 Controller ..... NEMA TS-2-2016

ATC Controller ..... AASHTO/ITE/NEMA ATC 5.2b

All NEMA TS2 and ATC controllers must provide functionality that meets or exceeds operational characteristics, including NTCIP support, as described in NEMA TS-2-2016.

NEMA TS2 Type 2 controllers shall be used when downward compatibility to existing TS1 cabinets is desired.

Except for replacing controllers in existing systems, all new installations must include controllers that capture high resolution event-based data elements to provide the automated traffic signal performance measures.

The manufacturer must supply certification of the conformance to the above requirements at the time of the bid.

In addition to the above requirements, the controller shall:

- 5. have all timing values entered via a front panel mounted keyboard. This keyboard shall be an integral part of the controller unit;
- 6. have an English language menu for programming or reading all controller features;
- 7. continue to operate the intersection as values are inspected or altered;
- 8. include the ability to upload and/or download the controller software operating system and user programmed database to or from external media (datakey, usb, sd card etc).
- 9. support Flashing Yellow Arrow for Permissive Left-turn Movements applications.

**Surge Protection Devices~~Lightning Protectors and Interference Suppressors~~**

The cabinet shall have Surge Protective Devices (SPDs) for the main AC power input, all signal head field wiring terminals, interconnect cable terminals and loop lead-in cable terminals which are located in the cabinet. Furnish SPDs to provide effective defense against high transient voltages caused by lightning discharges or other sources. SPDs must be unobstructed and accessible from the front side of any panel used in the cabinet. The SPD for the main AC power input of the cabinet must be connected on the load side of the cabinet circuit breaker. SPDs must meet the following minimum requirements:

1. AC power SPD:

- a. Must be UL 1449 4<sup>th</sup> Edition Listed
- b. Parallel connected device
- c. UL Nominal Surge Rating (In): 20kA
- d. UL Short Circuit Current Rating (SCCR): 150kA minimum
- e. Surge current rating: 50kA per phase minimum
- f. Visual status indication

- g. Remote signalization contacts for monitoring purposes
- h. 10 year manufacturer's warranty minimum

2. DC power SPD:

- a. Must be UL 1449 4<sup>th</sup> Edition recognized
- b. Parallel connected device
- c. UL Nominal Surge Rating (In): 10kA minimum
- d. Must provide protection between all +/-Gnd connections
- e. Surge current rating: 20kA per phase minimum
- f. Visual status indication
- g. Remote signalization contacts for monitoring purposes
- h. 10 year manufacturer's warranty minimum

3. Data and communication SPD:

- a. Must be UL 497B listed
- b. 10 year manufacturer's warranty minimum

4. Signal and interconnect cable field wiring terminal SPD:

- a. Clamp the surge voltage to a level no greater than twice the peak operating voltage of the circuit being protected
- b. Withstand a surge current of 1000A with an 8 by 20  $\mu$ s waveform six times (at 1 second intervals between surges) without damage to the suppressor
- c. 10 year manufacturer's warranty minimum

5. Loop lead-in cable field wiring terminal SPD:

- a. Protect the detector unit loop inputs against differential (between the loop lead) surges, and against common mode (between loop leads and ground) surges
- b. Clamp the surge voltage to 25 V or less when subjected to repetitive 300A surges
- c. Withstand repetitive 400A surges with an 8 by 20  $\mu$ s waveform without damage
- d. 10 year manufacturer's warranty minimum

All SPDs must be installed according to the SPD manufacturer's instructions and not affect the operation of equipment. SPD leads must be kept as short and straight as possible.



~~Furnish ample lightning protectors to provide effective defense against high transient voltages caused by lightning discharges or other sources. Furnish each controller cabinet with the following surge protection devices:~~

~~1. Provide main power suppressor, for all but flasher or remote detector cabinets, having the following characteristics:~~

- ~~a. Peak Surge Current: 20,000 amperes~~
- ~~b. Clamp Voltage: 250 volts~~
- ~~c. Response Time: Voltage NEVER exceeds 250 volts~~
- ~~d. Continuous Current: 10 amperes at 120 volts AC~~

~~2. For controller flasher, flashing beacon, and remote detector cabinets, provide a power protector having the following characteristics:~~

- ~~a. Peak Current 15,000 amperes~~
- ~~b. Power Dissipation 15 watts~~
- ~~c. Peak Voltage 212 volts~~

~~3. Provide loop detector input terminals with the following:~~

- ~~a. Peak Surge Current 400 amps Differential Mode  
1,000 amps Common Mode~~
- ~~b. Response Time 40 nanoseconds~~
- ~~c. Input Capacitance 35 picofarads typical~~
- ~~d. Clamp Voltage 30 volts max (either mode)~~

~~4. Provide auxiliary relays and fan with a resistor/capacitor circuit to suppress generated noise.~~

~~5. Provide an RF Filter in controller cabinets capable of filtering of RF noise over the range of 60 hertz through 20 Megahertz. The RF filter may be incorporated as part of the Main Power Suppressor.~~

**CABINETS – GENERAL**

**730.26 Controller Cabinets**

Cabinets must be permanently marked with a label including the manufacturer's name or trademark, model/part number, and the year and month of manufacture. The label should be placed on the inside of the main door using a water resistant method. The label must be visible after installation.

Cabinets shall be provided as a complete unit and have all terminals and facilities necessary for traffic signal control as shown on the plans and shall meet at a minimum, the following requirement:

NEMA TS2 Controller Cabinet ..... NEMA TS 2 2016

The manufacturer must supply certification of the conformance to the above requirements at the time of the bid.

Cabinets shall also be in accordance with the latest version of the TDOT Traffic Design Manual.

Two paper copies of the cabinet wiring diagram shall be provided with each cabinet. The nomenclature of signal heads, vehicular movements and pedestrian movements on the wiring diagram must be in accordance with the signal operating plan. Documentation must include a list identifying the termination points of cables used for vehicular and pedestrian signal heads, detector loop lead-ins, and pedestrian pushbutton wires. A heavy duty, resealable plastic bag must be mounted on the backside of main cabinet door for storing cabinet documentation.

House the controller in a rigid, weatherproof cabinet, constructed, finished, and equipped as follows, and as shown on the Standard Details:

- 1. **Material.** Provide weather-tight cabinets fabricated from aluminum sheet or cast aluminum alloy with a minimum 0.125-inch thickness. All welds on fabricated cabinets shall be internal and continuous: spot

[welding is not acceptable.](#) Painting of cabinets is only required if the final finish presents an unsightly appearance.

2. **Doors.** Type III, IV, and V cabinets shall have a hinged front opening door that shall include substantially the full area of the front of the cabinet. Equip the door with a positive hold fast device to secure the door in at least two open positions: one position at approximately 90 degrees and the other at 120 degrees or more. The holdfast device shall be easily secured and released without the use of tools. Equip doors for Type II, III, IV, and V cabinets with a switch compartment, and provide the manual switches, specified in [730.265.F.6.jk](#), with a hinged front opening auxiliary door. Each door shall have a gasket to provide a weatherproof seal when closed.

Provide the main door with a No. 2 pin-tumbler cylinder lock, and the auxiliary door with a standard police sub-treasury lock. Provide four keys for each lock.

[Provide a switch which is to be tied to the cabinet light so that cabinet light will be on when the door is open and off when the door is closed.](#)

3. **Cabinet Mounting.** Mount cabinets as shown on the Plans or Standard Details.
4. **Ventilation.** Unless otherwise specified, provide ventilation as follows:
- On all cabinets housing controllers, mount a screened, rain-tight vent, 1-1/2 inches in diameter or larger, on the cabinet top.
  - Provide screened or filtered inlet ventilation openings, equal to or greater in area than top vents, located in the bottom or lower back side of Type I and II cabinets or around the lower 8 inches portion of Type III cabinets.
  - Construct the vents so as to project within the cabinet no more than necessary to provide for lock nuts and gaskets to retain the vent.
  - Locate vents so as to not interfere with the mounting of controller equipment.
5. **Cabinets with Exhaust Fans.** Exhaust fans shall consist of an electric fan with ball or roller bearings and a capacity of at least 100 cubic feet per minute. Mount the fan in a rain-tight housing attached to the top of the controller cabinet.

The fan shall be controlled by a thermostat having a temperature differential between turn-on and turn-off of 15 °F (-0, +5 °F), adjustable for turn-on through a minimum calibrated range of from 100 °F to 150 °F.

Whenever a fan is to be installed, provide the air inlet filter and filter holder shown in the Standard Details, or approved equal. Internally seal other air inlets. Provide exhaust fans in all cabinets that house controllers, with the exception of flasher controllers.

6. **Auxiliary Equipment.** With the exception of cabinets used in special applications (Type I and II), provide all cabinets with the following:
- Substantial shelves or brackets to support controller and auxiliary equipment.
  - Panel for terminals arranged for adequate electrical clearance. [Panels should be located in the cabinet as described below:](#)

- Detectors	Lower left wall
- AC power	Lower right wall

- Auxiliary/police switches	Door
- Load switch bay	Back wall

c. The cabinet shall include an LED light and GFI duplex receptacle which can be used when the main circuit breaker is off.

d. Control panel assembly consisting of:

1. Power supply connections made to a 30-ampere circuit breaker mounted on the cabinet separate from the signal terminal panel. The circuit breaker shall be a magnetic trip type, having an interrupting capacity of at least 2,000 amperes at 125 volts AC. The circuit shall trip between 101% and 125% of rated load, with an inverse time delay characteristic provided. Instantaneous tripping shall occur at ten times the nominal rating. All controllers shall be internally fused.
2. Service line surge protection.
3. Electrical service termination point sized to accept No. 4 AWG copper wire.
4. Ground fault receptacle.
5. Porcelain lamp receptacle to accept a standard traffic signal lamp. If LED lenses are utilized, the shall be dimmable and switchable to reduce glare at night time. (if necessary).
6. Circuit breakers in accordance to the National Electric Code for:
  - (a) Main power input to provide all power associated with normal operation.
  - (b) Flasher power input to provide all power associated with flash operation.
  - (c) Service power to provide power for the lamp and duplex receptacle and cabinet light.
7. Copper ground bus (minimum of 12 positions).

ed. Flasher mechanism independent of controller. The cabinet shall be wired for and include a NEMA flasher mounted on the back panel. All cabinets shall have a two-circuit flasher. The flasher shall have output indicators mounted on the front of the flasher case and shall be rated at a minimum of 15 amperes.

fe. General purpose relays, where required to perform specified functions. All relays external to the controller or appurtenances shall meet NEMA standards. In addition:  
- Flash transfer relays shall be of heavy-duty type and have a minimum contact rating of 10 amperes. Contacts shall be of silver material to reduce contact pitting.  
- Unless otherwise specified, each cabinet shall include six (6) flash transfer relays.  
- Flash transfer relays shall support Flashing Yellow Arrow for Permissive Left-turn Movements applications.

fg. Type II, III, IV, and V cabinets, when specified as housing for traffic actuated controllers, with two or more insulated terminal blocks mounted within the housing, one or more for terminating each field wire.

gh. A minimum of 12 available bare ground positions tied to AC Common Return.

- hi. Earth (driven) ground tie point to terminate a single No. 4 AWG copper ground.
- ij. A tie point to tie all ground systems within the cabinet to a single reference point. All grounds (AC - return, Chassis, and Logic Ground) must be referenced to a single ground point at the electric service.
- jk. A panel (police subpanel) ~~behind the auxiliary door~~ shall contain the following ~~switches~~:
1. A main power switch, which shall be wired to remove all cabinet power when in the Off position
  2. An Automatic Flash switch, which shall be wired as follows:
    - (a) The Flash position shall cause the cabinet to provide Flash Operation. The controller shall continue to operate, and Stop Time shall be applied to the controller.
    - (b) Auto/Manual switch to activate Manual Control Enable.
    - (c) Manual control pushbutton switch with self-coiling cord. Cord shall attach to a 2 position terminal strip via fork type connector
    - ~~(bd) Upon return from Flashing to Automatic, the controller shall initialize in the Start-Up Display condition as programmed in the controller, typically major road phases. This display, unless noted otherwise, shall be Green for the Artery phase(s).~~
  3. A panel mounted inside the main door shall contain the following switches:
    - (a) A technician Stop-Time switch to apply Stop Time to each controller ring.
    - (b) An Interval Advance switch, enabled only by the Stop Time switch, to be momentary pushbutton switch to apply Interval advance to the timer.
    - (c) A Signal On-Off switch, which shall remove the AC power applied to the signal heads for normal operation while the controller continues to operate.
    - (d) Individual phase vehicle and pedestrian detector test switches to be miniature toggle of the On-Off Momentary type to place:
      - i. No Call - Call provided by detectors
      - ii. Locked detector call
      - iii. Momentary detector call

Insulate or shield switch terminals on back of main cabinet door so that no live parts are exposed.

Leads from the terminal block to the auxiliary door switches shall be no less than No. 18 AWG stranded, with TW plasticized polyvinyl chloride or nylon insulation enclosed in an insulating loom, and shall be of sufficient length to allow full opening of the main cabinet door.
- ~~kl. Wire the cabinet according to the following:~~
- ~~1. Wire four phase controllers for four vehicle phases, two pedestrian phases, and two overlaps. Include eight NEMA load switch bases per cabinet.~~
  - ~~2. Wire eight phase controllers for eight vehicle movements, four pedestrian phases, and four overlaps. Provide twelve NEMA load switch bases.~~

The cabinet shall be wired with the appropriate number of load switches to accommodate vehicular and pedestrian phasing according to plans. At a minimum cabinets shall include 16 load switch bases. The load switch wiring shall support Flashing Yellow Arrow for Permissive Left-turn Movement applications.

m. All cabinet wiring shall be neatly routed and labeled, laced and permanently secured. All cable shall be secured to the panel, where practical. There shall be no holes drilled through the cabinet walls to mount panels or secure cables.

n. All terminals in the cabinet shall be of the barrier type. The following field connector terminals shall be provided:

- Four (4) signal output positions per load switch bay (R-Y-G-FL).

- Ten (10) positions per phase for vehicle loop detector harness.

- One position per phase for pedestrian detector inputs.

o. Cabinets shall have SDLC communication between the controller, MMU, Detector Rack, Radar Detector (if applicable) and Video Detection (if applicable).

p. Cabinets should have an electrical outlet (Non GFI) that has 120 VAC from the OUTPUT side of the Main Power Surge unit.

q. Cabinets shall support Flashing Yellow Arrow for Permissive Left-turn Movements applications.

r. All cabinets shall be supplied with a Malfunction Management Unit (MMU) and shall meet at a minimum, the following requirement:

NEMA TS2 Malfunction Management Unit ..... NEMA TS 2 2016

The manufacturer must supply certification of the conformance to the above requirements at the time of the bid.

According to NEMA TS2 the MMU shall be able to detect the presence of voltage on conflicting on conflicting field connection terminals, the absence of proper voltages on all the signal field connection terminals of a channel, and shall be capable of monitoring for the presence of satisfactory operating voltages within the Controller Unit (CU) and the MMU itself. The MMU shall be able to operate as a Type 16 with sixteen channels or as a Type 12 with twelve channels (compatible with NEMA TS1 cabinets.

The MMU should have an Ethernet port.

~~1. Supply all cabinets with a Signal Conflict Monitor (SCM) that meets the NEMA standards. The SCM for all controller cabinets with three or more phases shall be the 12 channel type, and shall have the following features:~~

~~1. Liquid Crystal Display to show all data in English language format.~~

~~2. Capability to monitor all Green/Yellow/Red/Walk field display outputs.~~

~~3. Capability to monitor the Controller 24 VDC output and be user programmable to have this monitor function Latch On.~~

~~4. Capability to monitor the Controller Voltage Monitor output, and be user programmable to have this monitor function Latch On.~~

~~5. Per Channel monitoring of Phase Yellow Clearance Interval, and shall cause flash operation if Yellow Clearance is less than the SCM programmed time (2.7-9 seconds).~~

~~6. Front panel mounted over current protection (no internally mounted fuses are acceptable).~~

~~7. Front panel mounted reset switch.~~

8. ~~Fault logging features—the SCM shall log all faults as to the:~~

- ~~(a) Date of fault~~
- ~~(b) Time of fault~~
- ~~(c) Fault condition~~
- ~~(d) Power failure~~

~~and store these fault conditions in non-volatile memory for user retrieval. The monitor shall be able to store at least ten such faults. The internal time clock shall automatically adjust for Daylight Savings Time changes. There shall be a keyboard method for the user to display and clear the stored event log.~~

9. ~~There shall be an RS-232 port on the SCM to allow the user to print all data stored in the SCM. The printer shall interface with the SCM via a standard RS-232 cable. Printer to be supplied by others.~~

10. ~~The SCM shall detect the following conditions and place the cabinet in the flash mode by De-energizing the Flash Transfer Relays:~~

- ~~(a) Absence of an active AC input on a channel~~
- ~~(b) Green/Yellow both active on a channel~~
- ~~(c) Yellow/Red both active on a channel~~
- ~~(d) Green/Red both active on a channel~~
- ~~(e) Green/Green active on conflicting channels~~
- ~~(f) Green/Yellow active on conflicting channels~~
- ~~(g) Green/Walk active on conflicting channels~~
- ~~(h) Low 24 VDC sample~~
- ~~(i) Controller Voltage Monitor active~~
- ~~(j) Clearance time less than programmed~~

11. ~~On circuits where all field outputs are not used (such as left turn phases), unused circuits shall be terminated at a load resistor and the monitor plus features shall function.~~

12. ~~No functional field display shall be permitted unless monitored by the SCM.~~

13. ~~Terminate the SCM sampling inputs at the closest tie point to the field termination.~~

**Enhanced Operational Features.** ~~When shown on the Plans, or specified in the Special Provisions, supply certain enhanced operational features of controllers. When required, these inputs and outputs shall be accessed to the controller by a dedicated fourth (or “D”) Connector. Provide a connector of a type as determined by the manufacturer, and that meets the following requirements:~~

- ~~a. This connector shall not be mateable to any other connector in the cabinet.~~

- b. ~~———— All operating voltages in this connector shall be NEMA DC level voltages.~~
- e. ~~———— No special operating features shall enter or exit the controller on any NEMA pin designated as “Spare” or “Future.”~~
- d. ~~———— When the “D” connector is not connected to the controller, the cabinet facility shall operate as a standard NEMA cabinet facility with no operational loss of standard NEMA features.~~
- e. ~~———— If the “D” connector is used as the input source for Pre-Emption operation, wire the cabinet facility so that the cabinet facility will NOT perform any operation other than FLASH unless the “D” connector is terminated at the correct termination point and all cabinet features including Pre-Emption are operational.~~

### ~~TRAFFIC ACTUATED CONTROLLERS~~

#### ~~730.26 Traffic Actuated Controllers~~

~~The controller mechanism shall meet or exceed the current NEMA Traffic Signal Systems Standard. Provide Standard A, B, and C Connectors. Submit private laboratory certification that the proposed unit is in complete compliance with the NEMA standards in effect at the time of the advertisement for bids.~~

~~The controller shall have all timing values entered via a front panel mounted keyboard. This keyboard shall be an integral part of the controller unit.~~

~~Each controller shall have all operating timing parameters as specified in NEMA on a per phase basis, including all Volume/Density features. Each phase shall have a defeatable Last Car Passage feature wherein the last vehicle receiving the Phase Green shall receive at least one full Passage Time increment.~~

~~The controller shall have all of the following keyboard entered values or parameters:~~

1. ~~———— Start on condition of the controller where the user can select via the keyboard the following:~~
  - a. ~~———— Phases to start in~~
  - b. ~~———— Phase display to be on~~
  - c. ~~———— Overlap display start on condition~~
  - d. ~~———— Normal start up display shall be mainstreet green phase(s), with concurrent overlaps green~~
2. ~~———— Phase recall functions:~~
  - a. ~~———— Non lock detector~~
  - b. ~~———— Lock detector call~~
  - c. ~~———— Minimum recall~~
  - d. ~~———— Maximum recall~~
  - e. ~~———— Pedestrian recall~~
  - f. ~~———— Non-actuated phase~~
  - g. ~~———— Phase not active, phase omitted~~
  - h. ~~———— Pedestrian phase omitted~~
3. ~~———— All phase interval timing values except the Phase Yellow Clearance shall be as per NEMA. Each controller phase Yellow Clearance Interval is 3 seconds as a minimum.~~

~~The controller shall have a back lit liquid crystal display for each ring of the controller to provide an English language menu for programming with displays for programming or reading all controller features. The dynamic displays for real time operation shall be able to display the following values for each ring or phase(s) concurrently:~~

1. ~~———— Per Phase Display:~~
  - a. ~~———— Phase Vehicle Call~~

- b. ~~Phase Pedestrian Call~~
- e. ~~Phase is Next In Service~~
- d. ~~Phase is In Service~~
- e. ~~Phase Pedestrian Intervals in Service~~

- 2. ~~Per Ring Display:~~
  - a. ~~Ring Gapped Out~~
  - b. ~~Ring Maximum Green Termination~~
  - e. ~~Ring was Force Off Terminated~~
  - d. ~~Ring Maximum Green II in effect~~
  - e. ~~Ring Phase in Service Operating:~~
    - i. ~~Lock Call~~
    - ii. ~~Non Lock Call~~
    - iii. ~~Minimum Recall~~
    - iv. ~~Maximum Recall~~
    - v. ~~Pedestrian Recall~~
    - vi. ~~Non Actuated Mode~~

3. ~~Per Ring Display of Timing Values (Real Time). The following values shall be selectively displayed and shall display the current value in a real time mode.~~

- a. ~~Minimum Green Interval~~
- b. ~~Passage Timer~~
- e. ~~Pedestrian Interval Timing~~
- d. ~~Maximum Green Timer~~
- e. ~~Time Before Reduction Timer~~
- f. ~~Time to Reduce Timer~~

~~It shall be possible to inspect and alter any currently programmed value while the controller is in operation without affecting the field operation. The controller shall continue to operate the intersection as values are inspected or altered.~~

~~The controller shall store all operator entered data in EEPROM devices that require no battery to support value storage. No internal components of circuitry shall require battery support.~~

~~The timer shall have a front panel mounted RS-232 connector to allow the user to print a hard copy of all programmed data to a standard serial printer. The printer shall use a standard RS-232 connecting cable. Printer to be supplied by others.~~

### 730.27 Auxiliary Equipment for Traffic ~~Actuated-Signal~~ **Actuated-Signal** Controllers

Furnish and install the following auxiliary equipment in each cabinet for traffic actuated controllers.

#### A. Load Switches

Provide each cabinet complete, with the necessary number of NEMA load switches and Flash Transfer relays necessary to effect the specified signal sequence and phasing. Load switches shall:

1. Meet NEMA standards.
2. Have front-face mounted LED indicators to indicate the "On" condition of both the Input and Output circuits.
3. Use replaceable "cube" type circuitry or encapsulated discrete component construction. No unencapsulated discrete component construction are acceptable.



**B. Time Clock Switches**

Where shown on the Plans, provide time clock switches of solid state circuitry, continuous duty, with a 7-day cycle clock operating from the 120-volt AC service line. Provide switching for a minimum of one independent output and ensure the time of day selection is adjustable to within 1 minute of the desired time. Provide a battery backup system that can maintain time keeping and memory a minimum of 24 hours after power interruption. Furnish an omitting device as an integral part of the time switch to allow the switching operation to be skipped for any preselected day or days of the week. The time clock shall automatically compensate for daylight savings time changes. When the time clock is supplied as an internal component of the controller, supply the clock feature to provide for the selection of Maximum Green II on time of day, day of week, week of year basis. Time clocks shall meet NEMA environmental specifications.

When required in the traffic signal plans, the auxiliary equipment listed below shall meet the following requirements:

A. Uninterruptable Power Supply (UPS) – An UPS shall power the traffic signal cabinet in the event of a power failure for a minimum of 3 hours.

UPS assemblies should include off-the-shelf deepcycle AGM batteries.

Loss of utility power, transfer from utility power to battery power, and transfer back to utility power must not interfere with normal operation of connected equipment. In the event of UPS failure or battery depletion, connected equipment must be energized automatically upon restoration of utility power.

Removal and replacement of the UPS must not disrupt the operation of the equipment being protected.

All harnesses necessary to connect and operate the system must be included. All connectors must be keyed to prevent improper connection.

UPS assemblies shall be installed in accordance with the manufacturer's recommendations.

An UPS operation and maintenance manual shall be provided in the cabinet where the UPS is installed with cabinet wiring schematics, electrical interconnection drawings, parts layout and parts lists.

The UPS shall include a manufacturer's warranty covering defects for a minimum of three years (5 years for the external batteries) from the date of final equipment acceptance. The warranty must include provisions for providing a replacement UPS within 10 calendar days of notification for any UPS found to be defective during the warranty period at no cost to the maintaining agency.

B. Communications - Wireless - consist of installing a Wireless Network Communications Link with all necessary hardware in accordance with the plans and standard drawings to provide a data link between field devices (i.e. Traffic Signal Controllers).

Each link shall consist of Master ODU (Out Door Unit, Antenna) connected to a data switch within one of the signal cabinets and a Slave ODU connected to a data switch within the other signal cabinet. Each ODU is aligned to face the opposing ODU. The cable length between the ODU and its associated data switch may not exceed 300 feet.

The Wireless Network Communications Link components at each of the linked traffic signal cabinets shall include an ODU, a LPU (Lightning Protection Unit), power supply mounting hardware, and CAT 5e cabling. The ODU is pole mounted per manufacturer's specifications. The LPU and power supply are mounted within the traffic signal cabinet. CAT 5e cable is installed between the ODU and LPU.

For the applicable frequency spectrum of the radios being deployed, perform a spectrum analysis to ensure no competing equipment in the area. Ensure the radio path site survey test is performed using the supplied brand of radio equipment to be deployed. Typically, if the ODUs can be mounted with clear line of sight between them, this is sufficient to ensure proper operation. If this is not possible, it may be determined that a repeater station is necessary to complete the intended link. Provide the test results to the ENGINEER for review and approval. Submit copies of the test results and colored copies of the frequency spectrum scan along with an electronic copy of this information. The ENGINEER will approve final locations of the ODUs and any necessary repeater stations.

Install each ODU in such a manner that avoids conflicts with other utilities (separation distances in accordance with the guidelines of the NESC) and as specified in the ODU manufacturer's recommendations. Secure the ODU mounting hardware to the pole and route the CAT 5E cable such that no strain is placed on the RJ-45 connectors. Align each antenna/radio to be perpendicular to the ground (using bubble level) and to face the opposing radio.

C. Fiber optic cables - Multi-mode type fiber optic cable shall be 50  $\mu$ m core diameter, with at least 12 fibers per cable unless otherwise specified in the plans. Single-mode type cable shall be between 8-9  $\mu$ m core diameter, with at least 12 fibers per cable unless otherwise specified. A fiber optic drop cable shall be a minimum of 6 fibers (each type) and be spliced into the trunkline in a splice enclosure either aerially or in a pull box. ~~Contractor shall provide 50ft. of slack~~ shall be provided, either lashed to a span aerially, or coiled in a pull box for underground installations. Termination panels shall be provided with sufficient size to provide for a neat installation, and enough panel space to accommodate the specified number of fibers for termination. ST connectors shall be used unless otherwise specified. ~~A Contractor shall provide any necessary jumpers~~ shall be provided for installed equipment.

### MISCELLANEOUS TRAFFIC FLASHING SCHOOL SIGNALS

#### 730.28A Flashing School Signals

When shown on the Plans, provide flashing school signals that conform to the following:

1. The signal shall produce two alternate flashing lights within the marginal limits of a school speed limit sign. Details of the sign construction shall be as shown on the Plans. Sign colors shall conform to the MUTCD and be constructed of materials complying with these specifications.
2. The two LED lenses shall be yellow in color and a minimum of 8 inches in diameter. The LED lenses shall be part of a weather-proof and water-tight optical unit. The LED lenses shall meet the same requirements for vehicular signal head LED lenses. Mount the lenses in the sign using a molded endless rubber gasket with the sign being mounted to the signal case. ~~The reflector for the round lens shall be glass and firmly mounted between the lens assembly and the case so as to produce a weather proof and water tight optical unit.~~
3. Provide a two circuit type flasher unit to provide alternating equal on-off operation. The flashing mechanism shall produce between 50 and 60 flashes per minute through two 120-volt, 60-cycle AC, 15-ampere circuits. The flasher shall be of solid state construction.
4. Wire the unit for external circuits.
5. The signal shall be actuated by time switch meeting **730.27**. Locate the timing device in a remote mounted control cabinet.
6. Where an illuminated speed limit indication is shown on the Plans, the numeral message shall be illuminated in Portland Orange in a rectangular lens and illuminated only during the period when the signal produces two alternately flashing amber lights.

In addition, the Time Clock Unit/Switch used for Flashing School Signals shall be a programmable module that allows a user to define the time and day that the school speed zone flasher assembly will initiate and terminate flashing operation. The module shall be installed within the pole-mounted signal cabinet provided as part of project. The time clock shall be compatible with the cabinet's wiring relays and termination panels and the battery power supply system. The time clock switch provided shall also have the following features/capabilities outlined below:

1. Daylight Savings Time shall be a user-programmable setting, in addition to having automated compensation per TDOT specifications.
2. The unit shall provide a minimum 12-character, multi-line alpha-numeric LCD back-lit display capable of displaying all programming parameters.

3. The unit shall be capable of being programmed manually (using an integral keyboard pad) or programmed externally using an optional software program via a laptop computer and cable connection (compatible software program is a separate and distinct item from the time switch unit, and if required, will be separately specified and noted in list of estimated project quantities).
4. Unit shall provide automatic Leap Year compensation.
5. The time clock switch shall be capable of up to minimum 24-hours of capacitive back-up operation, 48 hours desirable, in the event of power interruption.
6. Unit shall be compatible with the supplied solar powered power system / battery unit
7. Time clock switch shall be capable of being programmed for one (1) Normal / Main program, and an additional minimum of 12 Exception periods /programs allowing holiday, vacation and custom skip plans. The exception programs will allow for the Normal / Main program to be skipped or allow for flasher operation on alternative schedules (i.e. early release days, summer school, etc).
8. Unit shall conform to TDOT standard specification subsection 730.27 – Auxiliary Equipment for Traffic Actuated Controller – Time Clock Switches except as superseded herein.
9. Unit shall have non-volatile program memory to allow retention during power loss.

#### 730.28B Solar Power Flashers

730.28B-Solar Power Flashers. When required, the solar power flasher equipment listed below shall meet the following requirements:

1. Solar panel and mounting equipment shall be installed on cantilever pole shaft as illustrated on layout detail sheet and as directed by manufacturer instructions.
2. Solar power unit assembly shall include all required mounting equipment, wiring/cables, battery supply, battery charging unit and other ancillary equipment necessary to operate the solar panel and properly charge the battery. The photovoltaic array shall include mounting bracket assembly to permit adjustment of the array to optimal sun exposure. The photovoltaic module shall be mounted and aligned per manufacturer recommendations to maximize solar exposure.
3. Battery unit shall meet manufacturer specifications required to operate and power L.E.D. signal displays and continuous time clock switch operation. Battery shall be compatible with cabinet equipment, including the time clock switch and the flasher signal displays. Battery unit shall meet minimum environmental and performance specifications required for system operation as recommended by solar panel and time clock switch manufacturers.
4. Solar panel and battery supply shall be of a size and power rating necessary to provide required power to time switch clock and flasher signal displays. ~~O~~The contractor shall obtain the power load requirements from the solar power equipment manufacturer and provide as required. On a typical school day, it should be expected that the flasher system will operate up to four (4) hours per day with the time clock continuously operating to maintain its clock timer. ~~P~~Contractor shall provide a solar system sizing report from the manufacturer indicating the power supply requirements of the proposed system required to meet the expected power demand.
5. The photovoltaic modules shall be warranted for a minimum of five (5) years from date of installation.

6. The battery system shall be a gelled-electrolyte type battery with capacity to provide a minimum of five (5) days continuous operation of the flasher assembly without charging. Batteries shall be field replaceable. Batteries shall have prorated warranty of a minimum of five (5) years from date of installation.

### **730.28C Portable Traffic Signals**

Portable Traffic Signals (PTS) consists of furnishing, installing and configuring a complete PTS system that may be used in construction zones or in other temporary signal locations. The work will be at various sites throughout the state of Tennessee and will consist of providing all labor, materials, equipment and incidentals necessary to make functional the PTS in accordance with these specifications.

The PTS shall be trailer or cart mounted units that provide for easy transportation and quick setup and deployment. There shall be 2 unit options and each unit shall be self-contained.

1. Type 1 units are typically used for long term projects (i.e. projects 5 days or longer in duration) and shall include 2 signal heads per trailer with an upper signal head mounted on an overhead mast arm that can be extended over the travel lane, and a lower signal head mounted on the vertical upright of the trailer.
2. Type 2 units are typically used for short term projects (i.e. projects 4 days or shorter in duration) and shall include 1 signal head that is mounted on the vertical upright of the trailer or cart. Cart-mounted units shall be successfully crash tested to NCHRP 350 TL-3, or equivalent MASH standards. If the project duration is extended beyond 4 days, then Type 1 units should be substituted in lieu of the Type 2 units for all PTS within the signal system.

The PTS shall be MUTCD Compliant and utilize standard ITE signal heads, and adhere to the ITE Specifications and Standards for Vehicle Traffic Control Signal Heads, Light Emitting Diode (LED) Circular Signal Supplement. The unit shall be solar powered and communicate via a wireless or hardwire connection. The unit shall include all the major components listed below or be able to perform the functions of these components. The major components of the unit shall include but are not limited to the trailer or cart, telescoping mast arm (on Type 1 units only), signal head(s) and back plates, traffic signal controller with operating software, solar charging system with batteries, input and output devices, flasher units, conflict monitor, relays, communications system and other equipment required for the safe operation and installation of the unit.

The PTS signal heads and all applicable components of the PTS shall meet the physical display and operational requirements of conventional traffic signals as specific in the MUTCD.

1. For Type 1 units, each unit shall contain 2 signal heads with an upper signal head mounted on an overhead mast arm that can be extended over the travel lane with a minimum clearance of 17 feet measured from the bottom of the signal head unit to the road surface. The lower signal head shall be mounted to the vertical upright of the trailer at a minimum height of 8 feet from the bottom of the signal head unit to the road surface. The signal heads shall also include black back plates that can be easily removed. The signal heads shall have the ability to be rotated 180 degrees to face in the opposite direction and shall have the ability to rotate and lock in approximately 10 degree increments to position the signal head for the optimum visibility to motorists.
2. For Type 2 units, the signal head of the unit shall be mounted to the vertical upright at a minimum height of 8 feet from the bottom of the signal head unit to the road surface. The signal head shall also include black back plate that can be easily removed. The PTS shall be easily rotated to position the signal head for optimum visibility to motorists.

The PTS shall include a solid-state controller with operating temperature range of -40°F to +180°F and compliance with NEMA TS-5 Performance Standard. The controller or programming module shall have an easy to read front panel indicator display. The display shall be backlit and have the capability to facilitate programming and display the currently operating program for each vehicular approach. The controller shall be capable of operating the PTS

system in a fixed time, traffic actuated, or manual control mode. Each PTS in a connected system shall have the capability to serve as either the master or slave signal. Each PTS shall include a Conflict Monitor Unit (CMU), or Malfunction Management System (MMS) to ensure phase conflicts do not exist during operation.

1. A minimum of 5 automatic time-of-day timing plans within a 24-hour period should be available in fixed time mode. The operating system should have the ability to control a minimum of 4 traffic phases with programmable cycle time adjustments and user adjustable red, amber, minimum green and maximum green times. The operating system shall also have the capability of facilitating standby modes of red, red flash and yellow flash.
2. The system shall also have the ability to operate in vehicle actuation mode when vehicle detection detectors are used. The operating system shall have the capability to allow the PTS to be connected to and controlled by a standard NEMA controller.
3. The system shall have the capability to be configured and controlled remotely using a handheld wireless remote control with the capability of being operated at a distance up to ¼ mile from the master.
4. The system shall have the capability of remote monitoring for reporting, at a minimum, signal location and status, battery voltage and system defaults. The remote monitoring shall have capability to alert designated individuals if a fault condition occurs.
5. The operating system shall include password protection to prevent unauthorized programming.

The PTS shall communicate with all other PTS within the signal system via license-free wireless 900 MHZ radio link communications. The radio units shall maintain communications at a minimum distance of 1 mile. The radio system shall conform to the applicable Federal Communications Commission (FCC) requirements, including FCC 90.17, and all applicable state and local requirements. The PTS shall be in direct communication at all times either by wireless or hardwire connection to provide for the required conflict monitor.

The system shall also have the ability to operate in vehicle actuation mode when vehicle detection detectors are used. For Type 1 units, the PTS detector shall be a high-definition, multi-beam, microwave radar stop bar detector for each vehicular approach. The Type 1 radar detector shall have a minimum range of 140 feet and shall be mounted at a minimum height of 17 feet measured from the top of the road surface. For Type 2 units, the PTS detector shall be a radar detector for each vehicular approach. The Type 2 radar detector shall have a minimum range of 140 feet and shall be mounted and have complete radar detection functionality at a minimum height of 8 feet measured from the top of the road surface.

The PTS shall be equipped with a solar power array, charging unit and battery system. For Type 1 units, the number and size of batteries shall be sufficient to operate the signal for a minimum of 21 days at 70 degrees without additional charging or assist from the solar array. An on-board battery charger shall be compatible with both the solar array and with a 120V AC power source. The solar panel array shall provide for a minimum of 440 watts of solar collection capability. For Type 2 units, the PTS shall have batteries sufficient to operate the signal for a minimum of 5 days at 70 degrees without additional charging or assist from a solar array. All instrumentation for the electrical system and battery compartment shall be mounted in a lockable weatherproof enclosure. Solar panels shall be secured to the mounting brackets for theft prevention. All wiring for the unit shall be protected against weather and damage.

The trailer or cart, and all mounted components, shall conform to the wind loading requirements (90 mph minimum) as described in the AASHTO Standard Specifications for Highway Signs, Luminaries and Traffic Signals. The wind load calculations shall be completed by an independent third-party contractor, and stamped by a U.S. Registered Professional Engineer. The trailer or cart shall be made of structural steel and shall include 4 leveling/stabilizer jacks capable of lifting the trailer or cart a minimum of 6 inches. The trailer or cart shall be equipped with a hydraulic or electric lift system sufficient for 1 person to be able to raise and lower the vertical upright and/or horizontal mast arm to and from the operating position. For Type 1 or 2 units, the trailer or cart shall be equipped to provide legal and safe transport on the public highway system at speeds up to 55 mph. All exterior metal surfaces,

except signal heads and back plates, shall be powder-coat painted highway safety orange.

The PTS work shall meet the following general contractor requirements:

1. Be responsible for locating the PTS in the appropriate location based on MUTCD and ITE standards for visibility to motorists and for safe operation.
2. Be responsible for providing all hardware, software, communications equipment and licenses to operate a complete PTS system.
3. Be responsible that all PTS equipment is installed according to the manufacturer's recommendations including wireless or hardwire connections.
4. Be responsible for transport, setup, configuration, operation and monitoring of the PTS throughout the entire project. The Engineer shall approve all timing and settings that are used for operation of the signal.
5. As directed by the Engineer, it may be necessary to relocate the PTS during the project. The cost of the relocation shall be included in the PTS price bid.

**DETECTORS**

**730.29 Detectors**

Provide detectors, of the type shown on the Plans, to actuate signal phases of traffic actuated controllers. Provide ample lightning protection to provide effective defense against high transient voltages caused by lightning discharges or from other sources. The lightning protection unit must withstand repeated 400-ampere surges on a 9 x 20 microsecond waveform. Also, the unit must be a two-stage device capable of clamping a minimum of one hundred 300-ampere surges to 25 volts within 40 nanoseconds for surge applied across the two detector leads.

**A. Inductive Loop Detectors System**

~~Loop amplifiers shall be of the single channel, totally self contained type, using a standard 10 pin MS connector (MS3102A-18P) and designed to operate within the NEMA environmental standards. All loop amplifiers shall be of the type to provide both "Extended" and "Delayed" outputs. Inductive loop detector units (loop amplifiers) shall meet at a minimum, the following requirement:~~

~~NEMA TS2 Inductive Loop Detector Units ..... NEMA TS 2 2016~~

~~Loop amplifiers may be single or multi-channel and shall be of the totally self-contained type.~~

~~All loop amplifiers shall be of the type to provide both "Extended" and "Delayed" outputs.~~

The loop detector amplifier shall be full automatic, requiring no adjustments to effect operational ability other than setting of the operating frequency and sensitivity. The amplifier shall:

1. Sense any legal motor vehicle traveling at speeds up to 65 miles per hour.
2. Have both a "Pulse" and "Presence" Output:
  - a. Pulse output shall generate an output of 125 ±25 millisecond output for each vehicle entry.
  - b. Presence output shall provide a continuous output for up to 60 minutes as long as a vehicle is within the detection zone.
3. Provide at least four user selectable sensitivity ranges.

4. Be supplied with at least three frequency ranges for crosstalk minimization.
5. Have a front-face mounted indicator to indicate active output of the internal relay. This indicator shall indicate the presence of:
  - a. Normal Output
  - b. Delayed Output
  - c. Extended Output
6. Have a front-panel mounted "Reset" switch that when pressed shall cause the unit to completely re-tune itself.
7. Have Delayed or Extended timing features with the following ranges:
  - a. Delayed output of 0 to 30 seconds in 1-second increments.
  - b. Extended output of 0 to 10 seconds in 1/4-second increments.
8. Have internal diagnostics to determine the operational ability of the loop. These diagnostics shall determine if a loop is opened or shorted, and shall provide a visible indication of such condition. Additionally, if such a condition occurs, the amplifier unit shall default to a "constant" output.
9. Provide output by a mechanical relay, which shall be "off" to provide an output.
10. Have all delay functions wired to the associated plan phase green to inhibit that function during controller phase green.
11. Be able to operate with loop lead-in lengths of at least 2,000 feet.

Comply with the details of the detector loop installation as shown on the Plans or Standard Drawings.

B. Video Detection System (VDS)– when specified in the plans, the equipment shall consist of all items necessary to provide a complete functional video detection system that process images and provide detection outputs to the traffic signal controller.

VDS shall be capable of NEMA TS2 operation.

VDS shall be waterproof and weather resistant.

VDS shall provide user-defined detection zone programming via a graphical user interface (GUI) and any necessary equipment for future programming. The configuration database shall have the ability to be stored on a removable data storage external to the video card.

VDS shall display programmable detection zones and detection activations overlaid on live video inputs. It shall detect vehicles in real time as they travel across each detection zone.

VDS shall have a minimum of 24 programmable detection zones per camera.

VDS shall be capable of:

1. shadow rejection without special hardware;
2. non-impaired operation under light intensity changes;
3. maintained operation during various weather conditions (e.g. rain, fog, snow)
4. anti-vibration, 5% rejection based on image change;
5. ability to select direction of flow parameters;
- 1-6.ability to properly detect directionally;
- 2-7.ability to configure presence, pulse, extend and delay outputs;
- 3-8.ability to set up a minimum of six detection zones per camera view to count the number of vehicles detected and store the information for retrieval;
- 4-9.variable focus providing a minimum of 4 to at least 40 degree horizontal field of view;
- 5-10. store detection zones in non-volatile memory;



VDS shall have no splices between the processors and the cameras.

VDS shall provide LED indicators to show active detection.

VDS camera shall have an internal heater to assure proper operation of the equipment during low temperatures.

VDS shall have surge ratings as set forth in NEMA specifications.

VDS shall have a two-year warranty and updates of all software shall be available without charge during the warranty period.

C. Radar Vehicle Detection System (RVDS) – when specified in the plans, the equipment shall consist of all items necessary to provide a complete functional ~~RVDS~~radar vehicle detection system (RVDS) that process high-definition, multi-beam radar electromagnetic waves and provide detection outputs to the traffic signal controller.

RVDS shall be capable of NEMA TS2 operation.

An ~~RVDS~~ RVSD shall consist of the following components: Radar sensor (1), detector rack interface module (1) power and surge protection panel or module (1) (cabinet interface devices that combine one or more of the above components shall be acceptable as well), and all associated equipment required to setup and operate in a field environment including software, serial and ethernet communication ports, cabling, electrical connectors and mounting hardware.

The ~~RVDS~~RVSD shall be able to operate in all types of weather conditions including: rain, snow, sleet, ice, fog and windblown dust.

Lightning and surge protection will be provided for power connections and communications links to the radar ~~RVDS~~RVSD.

The ~~RVDS~~RVSD shall provide a “fail safe” operation that triggers when communication between the radar vehicle sensor and the interface module is broken. Contact closure from the interface module will occur on all programmed detector channels associated with the affected radar sensor when the fail safe is triggered and will remain in this state until communication is re-established between the interface module and the radar vehicle sensor.

The ~~RVDS~~RVSD shall comply with all applicable Federal Communications Commission (FCC) requirements. The manufacturer will provide documentation of compliance with FCC specifications.

The ~~RVDS~~RVSD shall maintain frequency stability without the use of manual tuning elements by the user.

The RVDS as a minimum must provide a minimum of 4 separate RF channels selectable by the user to avoid interference with other devices working on the same frequency.

The communication port(s) shall support a communication speed that will not introduce excessive latency between when a vehicle is detected and the contact closure in the traffic signal cabinet.

~~RVDS~~RVSD interface modules that utilize the detector rack must operate at 12V or 24V DC. Shelf mounted interface modules must operate within a range of 89V to 135V AC, 60 Hz single phase. Power to the ~~RVDS~~RVSD radar sensor must be from the transient protected side of the AC power distribution system in the traffic control cabinet in which the ~~RVDS~~RVSD is installed.

~~RVDS~~RVSD documentation shall include a comprehensive user guide as well as quick reference guide(s).

~~RVDS~~RVSD shall have the ability to configure presence, pulse, extend and delay outputs.

D. Wireless Magnetometer Detection System (WMDS) - when specified in the plans, the equipment shall consist of all items necessary to provide a complete functional wireless magnetometer detection system that process changes to earth magnetic field and provide detection outputs to the traffic signal controller.

WMDS shall be capable of NEMA TS2 operation.

The ~~WMDS~~ WMDS shall consist of the following components: In-pavement sensors, all wireless communication equipment needed to establish communication links to the controller cabinet, interface modules compatible with NEMA TS-2 V2.06b cabinet detector rack, surge protection for the ~~WMDS~~ WMDS and system software for set-up and monitoring of the ~~WMDS~~ WMDS.

The ~~WMDS~~ WMDS must be capable of detecting a variety of vehicle types including motorcycles, automobiles and large trucks. The system must allow the user to select sensitivity levels that adjust the amount of hysteresis to the magnetic field needed to achieve contact closure to the assigned detector channel. Magnetometer sensitivity level adjustments must allow for different levels of vehicle detection.

~~WMDS~~ WMDS shall have the ability to configure presence, pulse, extend and delay outputs.



WMVDS equipment failure such as: the sensor, communications link, access point radio, repeater radio (if used) or interface module, shall result in constant vehicle call "fault state" on the affected detector channel to the traffic controller.

WMVDS detection accuracy must be comparable to properly operating inductive loops.

The WMVDS shall provide real-time vehicle detection (within 150 milliseconds (ms) of vehicle arrival). Once detection is achieved by the sensor, the traffic controller must receive contact closure to the assigned detector channel within the 150 ms time frame.

The WMVDS in-pavement sensor must operate on batteries without the need for underground power or communication cable connections to the unit.

The average operating life span of the sensor under battery power must be a minimum of 10 years.

The interface module must provide 2 or 4 detector channels. Sensors must be assignable to the available detector channels on the interface module using software provided with the WMVDS.

The front face of the module shall identify detector channel 1 and detector channel 2. Each must use an LED to indicate contact closure on the channel. When vehicle detection is achieved, the LED will be on and contact closure applied to the detector channel. During periods of no vehicle detection the LEDs will be in an off state and no contact closure will be applied to the detector channel.

The interface module will use an LED indication to indicate a "fault state" with the WMVDS. When the fault state is active contact closure will be applied to the appropriate detector channel.

### **B-E. Pedestrian Push Buttons**

Where shown on the Plans, furnish and install pedestrian push buttons of substantial tamper-proof construction. They shall consist of a direct push type button and single momentary contact switch in a cast metal housing. Operating voltage for pedestrian push buttons shall not exceed 24 volts.

Provide a weatherproof assembly, constructed to prevent electrical shocks under any weather condition.

Where a pedestrian push button is attached to a pole, the housing shall be shaped to fit the curvature of the standard or post to which it is attached to provide a rigid installation.

Unless otherwise specified, install the push button and sign on the crosswalk side of the pole.

Pedestrian push buttons shall have a transient protection that meets NEMA specifications.

### **Magnetometer Detectors**

~~Provide magnetometer detectors capable of being activated by a change in the magnetic field caused by the presence or passage of a vehicle within the lane of required detection at any speed from 0 to 80 miles per hour. The term "magnetometer detector" applies to a complete installation consisting of a sensing element or group of sensing elements installed in the roadway as shown on the Plans, lead-in cable, and a control unit with power supply installed in a traffic signal controller cabinet or special cabinet as shown on the Plans.~~

~~The sensing elements shall be no larger than 2 inches in diameter by 4 inches high and shall contain no moving parts or transistors.~~

~~The control unit shall be an electronic device capable of providing closure of an output circuit when a vehicle stands over or passes through the magnetic field of the sensing elements connected to the input circuitry of the control unit. The output shall be electrically insulated from the sensing element and the electronic circuitry.~~

~~Each detector shall operate from a 120 volt, 60 hertz, AC supply. Operation shall be satisfactory at voltages from 110 to 130. In addition, the unit shall not be affected by normal powerline transients or by powerline voltage variations of plus/minus 10%.~~

~~The control unit for the magnetometer detector shall be designed for (1) permanent presence, (2) pulse presence, (3) presence counting of vehicles, or combinations thereof.~~

~~The permanent presence control unit shall signal continually the presence of any vehicle until the vehicle leaves the area of detection, where upon the vehicle signal shall immediately drop.~~

~~The pulse presence control unit shall provide one x 30 millisecond, plus/minus 10%, pulse for every vehicle entering the area of detection.~~

~~The presence counting control unit signal shall provide separate detection of each distinct traffic lane.~~

~~Each control unit shall have solid state circuitry, except for the output relay. House each unit in a control box. Furnish each control unit with an integral power supply. Each control unit shall be designed to provide ease of maintenance. All electronic components shall be easily accessible.~~

~~Calibrate the control unit with tuning controls.~~

~~Each detector shall provide positive vehicle detection without readjustment from  $-20^{\circ}\text{F}$  to  $+160^{\circ}\text{F}$ .~~

~~Mount all controls, pilot lights, meters, fuse holders, and connectors on the front panel of the control unit or the control power source assembly. Input power shall be fused.~~

~~When control unit and power supply components are mounted on insulating boards, printed circuit wiring may be used. Provide printed circuit boards designed to facilitate identification of components; provide either part identification markings or a pictorial diagram showing the physical location and identification of each component.~~

~~Place the sensing elements in holes cut in the roadway at the locations shown on the Plans. Make each hole large enough to accept a 2 inch diameter sensing element and to be  $8 \pm 2$  inches deep. Make the holes vertical, regardless of the slope or grade of the pavement surface.~~

730.30 (Reserved)

730.31 (Reserved)

## COORDINATION

### 730.30 Coordination

~~The following are the minimum design and operating requirements for all types of local coordinating units. The general design requirements apply to master coordinating units and secondary coordinating units; as a separate unit or internal to the controller; both dial electro mechanical, and digital full solid state. Local coordinating units provided for an interconnected signal system shall be completely compatible with the master controller and all local controllers in that system.~~

~~Use the coordinating units described herein in conjunction with solid state traffic actuated signal controllers and traffic adjusted master controllers. The coordinators shall inhibit the external extension limit in the local controllers and provide external maximum control. Background cycle lengths, splits, system offsets, and other coordination functions as required shall be called in by a master controller or coordinator. These functions may also be called in by local or master override or time switches.~~

~~Furnish coordinating units capable of at least the following:~~

- ~~1. Three background time cycles.~~

2. ~~Three splits per cycle.~~
3. ~~Three offsets per cycle.~~
4. ~~Multiple and adjustable permissive periods for yielding to non-coordinated phases.~~
5. ~~Force off capability for all non-coordinated phases.~~
6. ~~Capability of generating as a minimum cycle lengths of 50, 60, 70, 80, 90, 100, and 120 seconds.~~
7. ~~Master intersection control and supervision of other coordinating units as required.~~
8. ~~Free operation when called for by the system master, time switch, or manual override.~~

~~It shall be possible to set offset splits and all synchronization functions from the front of the coordinating unit, and to make these settings in at least 1% steps to any percentage of the associated cycle length.~~

~~Absence or conflict of offset or cycle information on the interconnect shall place the coordinating unit in cycle number 1 (average offset) or a preset standby cycle.~~

### ~~730.31 Time Based Coordination Units~~

~~This Subsection covers traffic signal system time-based coordination units of solid state design. Time-based coordination units are used to control the timed relationship between intersections to maintain a system interconnect plan without the use of interconnect cable.~~

#### ~~Background Cycle~~

~~Provide time-based coordination units with at least three independently programmable background cycles. The background cycles shall be in fixed increments, not exceeding 1 second.~~

#### ~~Offsets~~

~~Provide time-based coordination units with at least three independently programmable offsets per background cycle.~~

#### ~~Splits~~

~~Each split shall have at least six independently programmable force off points, one for each non-coordinated phase. Provide two splits per background cycle.~~

#### ~~Timing Requirements~~

~~Provide color or function coded time controls for programming the background cycle, offsets, force off points, and permissive periods. Timing of all functions shall be digital, with an accuracy of  $\pm 100$  milliseconds from the programmed value.~~

~~Ensure that the minimum timing ranges and maximum increments of adjustment for the various timing functions meet Table 730.31-1.~~

**Table 730.31-1: Timing Requirements**

<b>Function</b>	<b>Minimum Timing Range</b>	<b>Maximum Increment of Adjustment</b>
Background Cycle	30 to 255 seconds	1-second
Offset	0 to 255 seconds	1-second
Force-off Points and Permissive Periods	0 to 99% of cycle	1% of cycle

The clock circuit of time-based coordination units may use either the 60 hertz AC power source or a crystal oscillator as the timing reference. If a crystal oscillator is used as the timing reference, the frequency tolerance of the clock circuit shall be  $\pm 0.005\%$ . The clock circuit of the time-based coordination unit shall allow for setting to the nearest second.

Provide the time-based coordination unit with a programmable feature that automatically changes from standard time to daylight savings time and vice versa.

#### **Battery Power**

Provide time-based coordination units with a battery to power the clock circuit and memory for a minimum of 100 hours when the 120-volt AC power source is disconnected.

#### **Manual Override**

Time-based coordination units shall be designed so that the programmed time of day function can be manually overridden to select a different function, such as cycle, offset, or splits.

#### **Indicator Requirements**

Time-based coordination units shall provide the following minimum indications:

1. Time of day (hours, minutes, and seconds)
2. Day of week or calendar date
3. Outputs controlled by day program
4. Cycle count indicates time in background cycle
5. Day program in effect
6. Week program in effect
7. Battery status

#### **Construction**

Time-based coordination units shall be a built-in component to the controller.

#### **Data Transfer**

Time-based coordination units shall provide transferring of all programmed data from unit to unit by using a data transfer cable. Supply a cable with each unit.

## **TRAFFIC SIGNAL SUPPORTS**

### **730.32 Cantilever Signal Supports**

This Subsection applies to the manufacture of steel poles and mast arms for the support of traffic signals. The height of poles, shaft dimensions and wall thickness shall meet the design requirements and mounting height of traffic signals as set forth in these Specifications and shown on the Plans. The Plans indicate bracket arm lengths.

Furnish poles consisting of a straight or uniformly tapered shaft, cylindrical or octagonal in cross-section, having a base welded to the lower end and complete with anchor bolts. All castings shall be clean and smooth with all details well defined and true to pattern. Steel castings shall conform to ASTM A27, Grade 65-35. Gray iron castings shall conform to ASTM A126, Class A.

All mast arms shall be compatible with the poles in material, strength, shape, and size.

**A. Anchor Base**

Secure an anchor base of one-piece cast steel or steel plate of adequate strength, shape, and size to the lower end of the shaft. Place the base so as to telescope the shaft, and weld at the top and bottom faces with continuous fillet welds so that the welded connection develops the full strength of the adjacent shaft section to resist bending action. Provide each base with a minimum of four holes to receive the anchor bolts. Provide cast steel bases with removable cast iron covers for anchor bolts and tapped holes for attaching covers with hex head cap screws.

Provide a welded frame handhole, 5 x 8 inches minimum and located with a clear distance above the base of no less than the pole diameter, "D". Weld a 1/2-inch 13 UNC grounding nut to the inside of the pole at a point readily accessible for wiring.

**B. Shaft**

Fabricate shafts from the best, hot-rolled basic open hearth steel. The shaft shall have only one longitudinal electrically welded joint and may have electrically welded intermediate transverse full penetration circumferential joints, at intervals of not less than 10 feet. The shaft shall be longitudinally cold-rolled to flatten the weld and increase the physical characteristics so that the metal will have a minimum yield strength of 48,000 pounds per square inch. Where transverse full penetration circumferential welds are used, the shaft fabricator shall furnish to the Engineer certification that: (1) all such welds have been radiographed and ultrasonically tested by an independent testing laboratory using a qualified Nondestructive Testing (NDT) technician and (2) the NDT equipment has been calibrated annually.

Fit the shaft with a removable pole cap, a J-hook wire support welded inside near the top, and a flange plate assembly to match that welded to the butt end of the mast arm.

**C. Mast Arms**

Provide mast arms fabricated and certified in the same manner as the upright shafts and that have the same physical characteristics.

The mast arms shall meet the design requirements necessary to support rigidly mounted traffic signals as shown on the Plans. All arms shall include a removable cap at the tip, grommeted wire outlets, and signal hanger assemblies of the type and number shown on the Plans, and a flange plate welded to the butt end to provide a rigid connection to the mast. The assembly shall be constructed so that all wiring can be concealed internally.

Connect mast arms to the upright pole at a height necessary to provide a minimum clearance of 16 feet 6 inches and a maximum clearance of 19 feet under the traffic signal heads. Install separate signal heads to provide the same clearance.

**D. Finish**

Galvanize steel poles, mast arms, and hardware in accordance with ASTM A123.

Galvanize all steel and cast iron components, hardware, and threaded fasteners, except anchor bolts, after fabrication in accordance with ASTM A123, or A153 or A385, as applicable.

**730.33 Steel Strain Poles**

Provide steel strain poles consisting of a uniformly tapered or equivalent upright shaft fitted with a removable pole top, J-hook wire support and 45-degree wire inlet near the top, a span wire clamp, a 5 x 8 inch handhole with reinforced frame and cover, bent anchor bolts, and all other accessories needed to make a complete installation. The pole and all of its component parts shall be designed to support tethered traffic signals of the type and number shown on the Plans, suspended from a span wire assembly. Fabricate and certify the poles as specified for the upright shafts in **730.32**.

Determine the shaft length required to meet field conditions and vertical clearances of signal heads over the roadway. The signal head clearance shall be a minimum of 16 feet 6 inches and a maximum of 19 feet. Fasten the span wire no closer than 1 foot 6 inches from the top of the pole.

Unless otherwise specified, provide all strain pole traffic signal supports with a one-piece anchor type base, fabricated from drop forged or cast steel of sufficient cross-section to fully develop the ultimate strength of the poles. Fasten the base to the pole with a welded connection that develops the full strength of the pole. Provide the base with a minimum of four holes of sufficient size to accommodate the proper size anchor bolts that are capable of resisting at yield strength stress, the bending moment of the shaft at its yield strength stress. Provide removable cast iron covers for the anchor bolts.

The shaft shall be fabricated from material providing a minimum yield strength of 48,000 pounds per square inch after fabrication.

Galvanize the steel poles and hardware in accordance with ASTM A123.

Galvanize all steel and cast iron components, hardware, and threaded fasteners, except anchor bolts, after fabrication in accordance with ASTM A123, or A153 or A385, as applicable.

**730.34 Pedestal Support Signal Poles**

Provide pedestal poles consisting of one upright pole with suitable base and other accessories or hardware as required to make a complete installation.

All poles shall be made of one continuous piece from top of base connection for the entire height of the pole. The cross-section shall be either cylindrical or octagonal and may or may not be uniformly tapered from butt to tip.

The cross-section at the tip shall have a 4-1/2 inch outside diameter.

**A. Type "A" Pedestal (Aluminum)**

Pedestals shall be of uniform octagonal or cylindrical cross-section of the tubular tapered type fabricated of one full length sheet.

Bases shall be octagonal or square in shape, of the ornamental type fabricated of cast material. Provide a handhole in each base.

Caps shall be of the nipple or tenon type mounting fabricated of cast material.

Furnish bases with four steel anchor bolts of sufficient size and length to securely anchor the base to the concrete footing. Weld the shaft to the cast metal base. Refer to the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals (current edition).

Type A pedestal shaft shall be fabricated from aluminum tubing 6063-T4 heat treated to T-6 temper after fabrication, and meeting ASTM B221.

Type A anchor base shall be made of sand-cast aluminum alloy 356-T6 meeting ASTM B26 - SF 70A-T5 specifications.

**B. Type "B" Pedestal (Steel)**

Pedestals shall be fabricated from a 4-1/2 inch (outside diameter) seamless steel pipe.

Bases shall be octagonal in shape of the ornamental type fabricated of cast or malleable iron and shall have minimum height of 12 inches. The top opening of the base shall be threaded to receive the shaft. Provide a handhole in each base.

Furnish bases with four steel anchor bolts of sufficient length to securely anchor the base to the concrete footing.

**730.35 Wooden Pole Signal Supports****A. General**

Provide wooden poles of the class and length shown on the Plans and that meet **917.11**. Set poles to the depth shown on the Plans, and fit them with all the necessary hardware to make the installation complete.

The signal head clearance shall be 16 feet 6 inches minimum and 19 feet maximum. Fasten the span wire at least 2 feet below the top of the pole.

**B. Guying Components**

Guy clamps shall be steel, 3-bolt type, 6 inches in length, and of the proper strand size to fit the wire used. The clamp bolts shall have upset shoulders fitting into the clamp plate. Substitution of the cable grip is subject to the Engineer's approval.

Attach guy wire to the pole with a 5/8-inch diameter x 12-inch length single strand angle-type eye bolt with 2 x 2 inch square cut washers, lock washer, and square nut.

Instead of the eye bolt specified above, an angle single strand eye of drop forged steel may be used, fastened on threaded end of span wire eye bolt.

Sidewalk guy fittings shall consist of 2-inch inside diameter standard galvanized steel pipe of required length with malleable iron pole plate and guy clamp. Fasten the pole plate to the pole with a 3/8-inch thru bolt and 1/2-inch lag screws.

All guying components and hardware shall be galvanized in accordance with ASTM A123 or A153.

Anchors for guys shall be of the pressed steel four-way expanding fluke type or of the steel or malleable iron sliding plate type. The minimum unexpanded diameter shall be 8 inches, and the minimum expanded area shall be 110 square feet. Coat anchors with a black asphaltic paint.

Guy anchor rods shall be drop-forged steel, 3/4-inch diameter and 7-foot minimum length, threaded, of the single thimble eye type, with a square anchor bolt nut.

**730.36 Pole Location**

Install all signal support poles at the locations shown on the Plans or where directed by the Engineer.

**COMPENSATION****730.37 Method of Measurement**

Measurement for traffic signals will be on a per item basis for each item to be furnished and installed, as specified herein and shown on the Plans.

With regard to items for signal head assemblies, each item to be furnished, installed, or both furnished and installed shall be distinguished with a code number as follows:

1. The first digit is the number of faces per assembly.
2. The second digit will indicate the number of 12-inch lenses per assembly (including arrow lenses).
3. The third digit is the quantity of 8-inch lenses per assembly.
4. The letter "A" indicates an arrow lens and the digit following the "A" indicates the number of 12-inch arrow lenses per assembly.
5. The letter "H" or "V" indicates the arrangement of arrow signal lenses to be horizontal or vertical with respect to solid ball indications.

**EXAMPLE:**

1 5 0 A 2 H

Digits indicate the following:

1 = one face

5 = five 12-inch lenses

0 = zero 8-inch lenses

A2 = two 12-inch arrow lenses

H = Arrow lenses placed horizontally with respect to circular indications

**A. Removal of Signal Equipment**

The Department will measure items of equipment or material designated or required for removal on a per each intersection basis. Removal and salvage of all signal heads, poles, control equipment, cabinets, span wire, cable, and similar features to be performed at an intersection shall be included as a unit cost per each intersection. This includes the cost of stockpiling salvable equipment for pick-up by the appropriate agency, as noted in the Plans.

**Signal Head Assembly (includes Pedestrian Signal Heads)**

The Department will measure signal heads of the type shown on the Plans by the individual assembly complete in place, per each. This item shall include the signal heads, terminals, lamps, attachment hardware, cable connection, and testing.

**Pull Box**

The Department will measure each pull box of the type required as one complete unit, installed, per each. This item includes the pull box, excavation, backfilling, crushed stone base, and other incidental items as called for in the Plans or Standard Drawings.

**Electrical Service Connection**

The Department will measure Electrical Service Connections on a per each signal installation basis. This item includes the electrical service supplied to the weatherhead by the local utility, all necessary materials and labor



for connection of the electrical service from the controller to the weatherhead, the wiring of the controller and detectors, and all incidentals necessary to render a complete and operable system.

**Signal Cable**

The Department will measure the length of Signal Cable of each size (number of conductors) installed in linear feet to the nearest foot from point to point along the routing for each cable.

The Department will make horizontal measurements by center to center measurement from:

1. Pole to pole
2. Pole to signal head (when terminating in a signal head)
3. Pull box to pull box
4. Pull box to pole
5. Pull box to pole-mounted or base-mounted controller

For cable inside mastarms, the Department will measure from center of vertical support to signal head where cable terminates.

The Department will make vertical measurement by one of the following:

1. For cable inside poles or conduit risers, the distance from ground level to the point of attachment of the span wire.
2. For cable inside mast arm supports, the distance from ground level to the mast arm connection.
3. For cable to pole-mounted controller,
  - a. From ground level to bottom of controller.
  - b. From bottom of controller to point of attachment of span wire.
4. For cable to pole-mounted signal head or pushbutton,
  - a. From ground level to bottom of signal head or pushbutton
  - b. From bottom of signal head or pushbutton to point of attachment of span wire.

The Department will make no additional allowance for slack length, length inside equipment or supports (except as noted), length for the required 360-degree drip loop, and similar instances requiring additional length of cable.

**Span Wire**

The Department will measure Span Wire Assembly, Tether Wire Assembly, and Messenger Cable by type in linear feet to the nearest foot. The measurement will be made from center to center of poles. These items include attachment hardware, strain insulators, and other hardware shown in the Plans as part of the assembly. The Department will make no additional allowance for slack length and other instances requiring additional length of wire.

**Steel Conduit Riser Assembly**

The Department will measure conduit riser assemblies per each for each size conduit riser installed on the outside of a pole, as shown on the Plans. This item includes conduit, weatherhead, conduit, fittings, nuts, washers, banding, clamps, grounding, and other items necessary for installation.

**Conduit**

The Department will measure conduit in linear feet to the nearest foot for each size and type of conduit installed.

The Department will measure underground conduit along the conduit by one of the following:

1. From the face of curb to the center of a pull box, pole or controller foundation,
2. From center to center of pull boxes,
3. From center to center of a pull box and a pole or controller foundation, or
4. From center to center of pole foundations or pole foundation and controller foundation.

The Department will add:

1. 1 foot to the above measurements for each entry to a pull box or pole foundation and each exit of a pull box or pole foundation.
2. 3 feet to the measurement for each capped extra entry (conduit stub) or exit to a pull box or pole foundation installed, as shown on the Plans.
3. 3 feet to the measurement for each connection between underground conduit and above ground riser.
4. 3 feet to the measurement for each entry or exit to a foundation for a base-mounted controller.

This item includes trenching, backfilling, sealing, capping, fittings, bushings, banding, grounding, and other accessories and hardware required for installation of the conduit system.

### **Vehicle Loop Detector (Amplifier)**

The Department will measure vehicle detector loop amplifier per each unit, including the cable and associated hardware necessary to electrically connect the amplifier to the controller and loop lead in.

The Department will measure two and four channel card rack type amplifiers per each unit, including the cable, card rack(s), and associated hardware necessary to electrically connect the amplifiers to the controller and loop lead-ins.

### **Shielded Detector Cable**

The Department will measure the two-conductor shielded detector cable installed between the controller cabinet and the loop detector wires in linear feet to the nearest foot.

The Department will make horizontal measurements (overhead and underground) by one of the following:

1. From center to center of pull boxes,
2. From center to center of pull box and pole,
3. From center to center of poles, or
4. From center to center of pull box or pole and controller foundation.

The Department will make vertical measurements by one of the following:

1. From ground level to the point of attachment of span wire, inside pole or conduit riser,
2. From the bottom of controller cabinet to the point of attachment of span wire, or
3. From ground level to the bottom of controller.

The Department will make no additional allowance for slack length, length inside equipment or supports (except as noted), splices, and similar instances requiring additional length of cable.

**Saw Slot**

The Department will measure the length of saw slot for installation of detection loop and lead wiring in linear feet to the nearest foot. Measurement for detection loops in the traffic lanes will be made based on the loop size shown on the Plans (the nominal length plus the nominal width) times 2. The Department will make no additional allowance for saw overruns to obtain full depth of saw slot or diagonal cuts to prevent sharp bends in the loop wire. The Department will measure saw slot for detection loop leads from the conduit entry at the face of curb or edge of pavement and along the route of the lead-in to the detection loop.

This item includes backing rods, or polyethylene foam sealant, loop sealant, and all other incidentals necessary to render a complete and operable system.

**Loop Wire**

The Department will measure the length of loop wire for installation of detection loops and lead-ins in linear feet to the nearest foot. Measurement will be made from the pull box or pole to the detection loop, around the loop the required number of turns and back to the pull box, pole, or point of splice. The Department will make no additional allowance for slack length, length inside equipment or supports, splices, and similar instances requiring additional length of wire.

This item includes electrical connections, testing, and all other incidentals necessary to render a complete and operable system.

**Controller**

The Department will measure controllers as one complete unit, installed, per each. This item includes all auxiliary equipment shown the Plans to provide signalization control as shown on the Plans, and all hardware, including the cabinet (and cabinet foundation, if base-mounted), necessary for installation.

**Wood Pole**

The Department will measure Wood Poles, of the type and size shown on the Plans, per each, installed.

**Guying Device**

The Department will measure Guying Devices, of the type shown on the Plans, per each, installed. This item includes the guy wire, anchor, clamps, and all other components shown on the Plans necessary for installation.

**Steel Strain Pole**

The Department will measure Steel Strain Poles of the type and size shown on the Plans, per each, installed. This item includes the pole, foundation, anchor bolts, grounding, and all other hardware shown on the Plans necessary for a complete installation.

**Cantilever Signal Support**

The Department will measure Cantilever Signal Supports, of the type and size shown on the Plans, per each, installed. This item includes the vertical pole shaft, mast arm, foundation, anchor bolts, grounding, and all other hardware shown on the Plans necessary for a complete installation.

**Service Cable**

The Department will measure two conductor power service cable, of the type and size shown on the Plans, in linear feet to the nearest foot, installed. Horizontal runs will be measured center to center of poles. Vertical runs will be measured from the ground to the weatherhead inside a pole or conduit riser, or from the ground to the

bottom of the controller, or from the bottom of the controller to the weatherhead. This item includes all necessary attachment hardware. The Department will make no additional allowance for slack length or other instances requiring additional length of cable.

### **Pedestrian Pushbutton with Sign**

The Department will measure Pedestrian Pushbutton with Sign as one complete unit, in place, per each. This item includes the pushbutton, sign, mounting hardware, wiring of pushbutton, testing, and all other incidentals necessary for a complete installation.

### **Pedestrian Signal Display with Pushbutton and Sign**

The Department will measure Pedestrian Signal Display with Pushbutton and Sign as one complete unit, in place, per each. This item includes the signal heads, terminals, lamps, cable connections, pushbutton, sign, all attachment hardware, testing, and other incidentals necessary for a complete installation.

### **Portable Traffic Signal**

The Department will measure Portable Traffic Signal, of the type shown on the Plans or as directed by the Engineer, per each, installed. This item includes the all of the software and hardware necessary for a complete installation.

### **730.38 Basis of Payment**

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Traffic Signal	Lump Sum
Removal of Signal Equipment	Each
Signal Head Assembly (Description)	Each
Install Pull Box (Description)	Each
Electrical Service Connection	Each
Signal Cable – (Description)	Linear Feet
Span Wire Assembly ( ___ pounds min. break strength)	Linear Feet
Tether Wire Assembly – ___" Diameter	Linear Feet
Messenger Cable – ___" Diameter	Linear Feet
Riser Assembly (Description)	Each
Conduit ___" Diameter (Type)	Linear Feet
Vehicle Detector (Description)	Each
Shielded Detector Cable	Linear Feet
Saw Slot	Linear Feet
Loop Wire	Linear Feet
Controller (Description)	Each
Wood Pole (Description)	Each
Guying Device (Description)	Each
Steel Strain Pole (Description)	Each
Cantilever Signal Support (Description)	Each
Service Cable	Linear Feet
Pedestrian Pushbutton with Sign	Each
Pedestrian Signal Display with Pushbutton and Sign	Each
<u>Portable Traffic Signal (Type)</u>	<u>Each</u>

The unit price to be paid includes the cost of furnishing and installing, complete in place, each of the various types of equipment required by the Summary of Quantities shown on the Plans. Total payment is full compensation for all materials, labor, equipment, and incidentals necessary to produce a completely operative and finished installation of a traffic signal or traffic signal system as shown on the Plans and as specified herein, including restoration of pavements, sidewalks, and appurtenances damaged or destroyed during construction and tests. All additional materials and labor not specifically shown or called for, which are necessary to complete the traffic signal installation or traffic signal system described, will be considered incidental to the system and no additional allowance will be made.

**Subsection 730.32.A.** (pg. 868), 6-27-16; revise the last paragraph of subsection 730.32 A.:

“Provide a welded frame handhole, 5 x 8 inches minimum and located with a clear distance above the base of no less than the pole diameter, “D”.”

**STATE**

(Rev. 5-18-15)  
 (Rev. 11-16-15)  
 (Rev. 6-27-16)  
 (Rev. 12-2-16)  
 (Rev. 5-15-17)  
 (Rev. 11-6-17)

**OF****TENNESSEE**

January 1, 2015

**Supplemental Specifications - Section 900****of the****Standard Specifications for Road and Bridge Construction****January 1, 2015**

**Subsection 903.01** - Table 903.01-1 (pg. 920), 5-18-15; Replace Note (1) with the following:

“(1) If the fine aggregate is manufactured from crushed stone and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 5%.

**Subsection 903.01** - Table 903.01-1, Table 903.01-2 (pg. 921), 5-15-17; replace Tables 903.01-1 and 903.01-2 with the following Tables:

**Table 903.01-1: Limits of Deleterious Substances in Fine Aggregate for Concrete**

<b>Substance</b>	<b>Maximum Permissible Limits Percent by Weight</b>
Clay Lumps	0.5
Coal and Lignite	0.5
Material Passing the No. 200 Sieve <sup>(1)(3)</sup>	3.0
Other deleterious substances (such as shale, alkali, mica, coated/grains, soft and flaky particles) <sup>(1)(2)</sup>	3.0

(1) If the fine aggregate is manufactured from crushed stone and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 10%.

(2) Determine other organic impurities according to AASHTO T 267.

(3) If the fine aggregate is manufactured from crushed gravel and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 3.5%.

**Table 903.01-2: Gradation Requirements for Fine Aggregate**

Sieve Size	Total Percent Passing by Weight
3/8 inch	100
No. 4	95-100
No. 16	50-90
No. 50	5-35
No. 100	0-20
No. 200 <sup>(1)</sup>	0-3

<sup>(1)</sup> If the fine aggregate is manufactured from crushed stone and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 10%.

**Subsection 903.03** (pg. 922) 5-15-17; Coarse Aggregate for Concrete, add the following as the 4<sup>th</sup> paragraph:

“Coarse aggregate in two-lift composite pavements shall consist of Size No. 467 in the lower lift, graded as specified in 903.22. Coarse aggregate in the upper lift shall be Size No. 57 or 67 graded as specified in 903.22 and shall meet 903.24 riding surface requirements.”

**Subsection 903.03** (pg. 922-923) 11-16-15; Coarse Aggregate for Concrete, modify the 4<sup>th</sup> and 5<sup>th</sup> paragraphs, update Table 903.03-1: Coarse Aggregate Sizes to the following:

“Coarse aggregate in Portland cement concrete bridge decks and overlays on interstates and four or more lane highways consisting of Size No. 57 shall meet 903.24.

The coarse aggregates for travel lanes and bridge decks shall be crushed and consist of stone, slag, gravel, quartzite, gneiss, or combination thereof with an absorption of plus 4 material not to exceed 5%. Do not use uncrushed gravel, pea gravel, or any other uncrushed particles. Crushed gravel, if used, shall consist of siliceous washed particles after processing, of which at least 70% by count of the material retained on the No. 4 sieve contains a minimum of two fractured faces. One face shall be fractured for the approximate average diameter or thickness of the particle.”

Table 903.03-1

Application	Coarse Aggregate Size <sup>(1)</sup>
Structural concrete	No. 57
Self-Consolidating concrete	Maximum-No.67
Prestressed concrete	No. 57 or 67
Precast concrete	Any size fraction
Concrete curbing placed by machine-extrusion methods	No. 7, 57, 67, or 78

Cement treated permeable base  
(2) No. 57

- 
- (1) Gradation shall conform to **903.22**.
  - (2) Aggregate shall meet the quality requirements specified below.
- 

**Subsection 903.03-2** (pg. 924) 5-15-17; Revise Table 903.03-2: Limits of Deleterious Substances in Coarse Aggregate for Concrete, update Material passing No. 200 Sieve and Footnote 2:

**Table 903.03-2: Limits of Deleterious Substances in Coarse Aggregate for Concrete**

Substance	Maximum Percent by Weight
Soft or non-durable fragments (fragments that are structurally weak such as shale, soft sandstone, limonite concretions, gypsum, weathered schist, or cemented gravel), and organic impurities as determined by AASHTO T 267 <sup>(1)</sup>	3
Coal and lignite <sup>(1)</sup>	1
Clay lumps <sup>(1)</sup>	0.25
Material passing the No. 200 sieve <sup>(1)(2)</sup>	1.5
Thin or elongated pieces (length greater than 5 times average thickness)	10
Other local deleterious substances <sup>(1)</sup>	1

<sup>(1)</sup> The sum of the percentages of these materials (i.e., soft or non-durable fragments, coal and lignite, clay lumps, material passing the No. 200 sieve, and other local deleterious substances) shall not exceed 5.0.

<sup>(2)</sup> For crushed aggregate, if all the material finer than the No. 200 sieve, as determined in accordance with AASHTO T 11, consists of the dust of fracture, essentially free of clay or shale, this limit may be increased to 2.0.

**Subsection 903.05 – B. Type B Aggregate** (pg. 927), 5-18-15; Replace the 1<sup>st</sup> paragraph of subsection 3. With the following:

- “3. Do not use material having clay content greater than 12%, as determined by hydrometer analysis performed in accordance with AASHTO T 88. Material may be used having a clay content exceeding 12% if a plasticity index-fines product does not exceed 3 when calculated by the following formula”

**Subsection 903.05 – Aggregate for Mineral Aggregate Base and Surface Courses** (pg. 928) 5-15-17; add section C to the bottom:

**C. Reclaimed Concrete Aggregate.** Provide material comprised of concrete reclaimed from the demolition of a concrete structure or pavement. Reclaimed Concrete Aggregate may only be used



as a mineral aggregate base course, subbase or shoulder course. The material shall be free of any materials classified as Solid or Hazardous Waste, especially asbestos, lead and mercury, with test results submitted by the contractor to the Project Supervisor. These test results shall be certified and notarized. The percentage of wear as determined in accordance with AASHTO T 96 shall not exceed 50. Deleterious substances shall be kept to a minimum, and may not be higher than the amounts listed on Table 903.05-3.

Table 903.05-3: Deleterious Materials

Material	Maximum Permissible Limits Percent by Weight
Brick	5
Bituminous Concrete Materials	5
Weathered Rock	2
Wood	0.1
Metals	0.1

The gradations of the coarse and fine fractions of aggregate shall be such that, when combined in proper proportions, the resultant mixture will fall within the grading specified in Table 903.05-4.

Table 903.05-4: RCA Grading Tolerances

Sieve Size	Total Percent Passing per Weight
1 ½ inch	100
1 inch	85-100
¾ inch	60-95
3/8 inch	50-80
No. 4	40-65
No. 16	20-40
No. 100	5-18

**Subsection 903.05** – Aggregate for Mineral Aggregate Base and Surface Courses (pg. 925) 5-15-17; add reference to subsection **903.05 C.** in the second paragraph of subsection A.:

**“903.05 Aggregate for Mineral Aggregate Base and Surface Courses**

Provide crushed stone, crushed slag, crushed or uncrushed gravel, or crushed or uncrushed chert that may be blended with crushed recycled concrete or screened reclaimed asphalt pavement (RAP), together with material such as manufactured sand or other fine materials that are either naturally contained or added as needed to conform to these Specifications.

Provide aggregate of Types A and B, as specified below.

**A. Type A Aggregate**

Provide hard, durable particles or fragments of stone, slag, gravel, or chert, and other finely divided mineral matter.

The Contractor may use recycled concrete aggregate per 903.05 C. or reclaimed asphalt pavement, at a maximum rate of 25% by weight, for Type A aggregate, provided the combined aggregate blend meets all the requirements specified below. Crush and screen the recycled concrete and asphalt to produce a uniform

stockpile before blending it with the virgin material. Keep the recycled stockpiles free of bricks, steel, wood, and all other deleterious materials. “

**Subsection 903.05** – Aggregate for Mineral Aggregate Base and Surface Courses (pg. 925-926) 5-15-17; add reference to subsection **903.05 C.** in the second paragraph of subsection B.:

“For Provide crushed or uncrushed gravel, crushed or uncrushed chert, crushed stone or crushed slag, and other finely divided particles.

The Contractor may use recycled concrete aggregate **per 903.05 C.** or reclaimed asphalt pavement, at a maximum rate of 30% by weight, for Type B aggregate, provided the combined aggregate blend meets all the requirements specified below. Crush and screen recycled concrete and asphalt to produce a uniform stockpile before blending it with the virgin material. Keep the recycled stockpiles free of bricks, steel, wood, and all other deleterious materials.”

**Subsection 903.06 - C.** Combined Aggregate Grading (pg. 930) 11-16-15; add the following sentence at the end of the first paragraph:

“For mixtures including recycled asphalt pavement, RAP, and/or recycled asphalt shingles, RAS, stockpiles will not be considered as contributing to the required minimum of three stockpile sizes.”

**Subsection 903.11 - Aggregate for Asphaltic Concrete Surface Coarses (Hot Mix)** (pg. 934) 11-16-15; add the following sentence at the end of the first paragraph:

“For mixtures including recycled asphalt pavement, RAP, and/or recycled asphalt shingles, RAS, stockpiles will not be considered as contributing to the required minimum of three stockpile sizes.”

**Subsection 903.11** (pg. 934) 11-16-15; A. Coarse Aggregate (retained on a No. 4 sieve), revise the 1<sup>st</sup> paragraph and subsection 3:

“Provide aggregate, consisting of crushed stone, crushed slag, crushed gravel, crushed granite, crushed quartzite, crushed gneiss, or natural combinations of these materials.”,

“3. Combined aggregate shall consist of siliceous particles processed from washed material, of which at least 70% by count of the material retained on the No. 4 sieve shall have a minimum of two fractured faces, one of which must be fractured for the approximate average diameter or thickness of the particle. Do not add pea gravel or uncrushed particles. The absorption of the crushed aggregate retained on the No. 4 sieve shall not exceed 5% when tested in accordance with AASHTO T 85.”

**Subsection 903.11 - A.** Coarse Aggregate (retained on a No. 4 sieve) (pg. 934), 5-18-15; revise subsection 2. as follows:

“2. Material retained on the No. 4 sieve shall contain a maximum of 10% elongated pieces (length greater than five times the average thickness)”

**Subsection 903.11 C.3.** (pg. 938), 6-27-16; revise the 1<sup>st</sup> paragraph of subsection C.3 to the following:

**“3. Grading OGFC.** A minimum of 75% of the aggregate shall meet the requirements specified in 903.24 for Surface Mixtures (Non-Skid Aggregates). The coarse aggregate shall have at least 90% crushed aggregate with two fractured faces and 100% with one fractured face as determined in accordance with ASTM D5821. The coarse aggregate shall have a LA Abrasion value of less than 40% and a maximum absorption of 3.0%.”

**Subsection 903.11** (pg. 938), 12-2-16; Add the following to C. as subsection 5.:

**“5. Grading C, CS, CW.** The mixture shall meet all requirements of **903.06**. When using Grading C, CS, or CW as a final riding surface for traffic lanes and the design ADT is greater than 1000, a minimum of 75% of the aggregate shall meet the requirements specified in **903.24** for Surface Mixtures (Polish-Resistant Aggregate) for the appropriate levels.”

**Subsection 903.12** (pg. 938) 11-16-15; A. Aggregate for Slurry Seal, revise the 1<sup>st</sup> paragraph a A. as shown; delete the 2<sup>nd</sup> paragraph:

“The aggregate shall be crushed slag, crushed granite, or crushed stone (crushed stone as specified in 903.24), meeting the requirements of ASTM D692, except the gradation shall be as specified in Table 903.12-1. The aggregate shall have a minimum sand equivalent, as determined in accordance with AASHTO T 176, of 45.

**Subsection 903.12** (pg. 939) 11-16-15; B. Aggregate for Micro-Surface: modify the first paragraph, delete the second paragraph:

“The aggregate shall be crushed slag, crushed granite, or crushed stone (crushed stone as specified in **903.24**) meeting the gradation limits specified in Table 903.12-2 and the physical properties of ASTM D692, except the percent of fractured pieces shall be 100. The aggregate shall have a minimum sand equivalent, as determined in accordance with AASHTO T 176, of 65. Polish-resistant aggregates will not be required for leveling courses, provided they will be covered with riding surface mixtures.

**Subsection 903.12** (pg. 939) 5-15-17; B. Aggregate for Micro-Surface: Add the following as the 2<sup>nd</sup> paragraph:

“If blending aggregates from more than one source, use automated proportioning and blending equipment which has individual bins for each aggregate source used to produce a stockpile meeting the job mix formula gradation. Proportion and blending equipment shall be calibrated at the beginning of production. All aggregate sources shall meet the requirements of **Table 903.24-1**. Do not blend aggregates with a front end loader. Proportion the aggregate to produce a uniform gradation meeting the requirements specified in Table 903.12-2. The contractor shall provide a Type A laboratory as defined by **106.06** capable of verifying gradation at the location where blending occurs.”

**Subsection 903.13** (pg. 940), 12-2-16; modify the last sentence of the 1<sup>st</sup> paragraph:

“Provide aggregate consisting of crushed stone, crushed slag, or crushed gravel, meeting the quality requirements of ASTM D692, except that at least 50% by count of crushed gravel aggregates shall have at least one fractured face. Crushed slag aggregate retained on the No. 4

sieve shall contain no more than 20% by weight of glassy particles. Provide aggregates meeting the requirements of **903.24** except, if ADT is less than 1000.”

**Subsection 903.15** (pg. 941), 5-15-17; revise the 3<sup>rd</sup> paragraph:

“The Contractor may use recycled concrete aggregate per 903.05 C. or reclaimed asphalt pavement (RAP), at a maximum rate of 25% by weight; provided the combined aggregate blend meets all the requirements specified above. If blending, crush and screen the recycled concrete and/or asphalt to produce a uniform stockpile before blending it with the virgin material. Keep the reclaimed asphalt pavement stockpiles free of bricks, steel, wood, and all other deleterious materials. The virgin and reclaimed pavement blend shall meet the quality requirements specified in Table **903.05-1**.”

**Subsection 903.24** (pg. 946), 5-18-15; Modify the 1<sup>st</sup> paragraph to the following:

“Provide coarse aggregate consisting of crushed gravel, crushed granite, crushed slag, crushed quartzite, crushed gneiss, or crushed sandstone. Other crushed aggregate may be used provided it has the chemical, physical, and performance characteristics specified in Table 903.24-1.”

**Subsection 904.01** (pg. 948) 11-16-15; Asphalt Cements, add the following between the 4<sup>th</sup> and 5<sup>th</sup> paragraphs:

“Polyphosphoric acid may be used as a modified not exceeding 0.5% by weight of asphalt binder and may only be used when the primary modifier is one of the styrene-based products listed above.”

**Subsection 904.01** (pg. 948) 11-6-17; Asphalt Cements, modify the fourth paragraph with the following:

“To modify the asphalt, properly blend one or more modifier(s) consisting of styrene butadiene (SB), styrene butadiene styrene (SBS), or styrene butadiene rubber (SBR), or Ground Tire Rubber (GTR) to a PG 64-22 or PG 67-22 base asphalt.

GTR used to modify asphalt shall meet the requirements of 921.17. Blending of GTR into asphalt cement shall occur only at the asphalt terminal.”

**Subsection 904.01** (pg. 948), 11-6-17; Asphalt Cements, add the following paragraph as the next to last paragraph:

“In addition to the above, asphalt cement modified with GTR shall meet the following requirement. The temperature difference determined by the Separation Test shall not exceed 15 °F. The separation test shall consist of taking the difference in softening point, as determined by the Ring and Ball Test (AASHTO T53), between the top and bottom thirds of a specimen prepared per ASTM D7173.”

Subsection 904.01 (pg. 949), 12-2-16; Modify Table 904.01-1:

“Table 904.01-1: Requirements for Asphalt Cement

Property*	PG 64-22, PG 67-22	PG 70-22	PG 76-22	PG 82-22
Non-recoverable creep compliance at 3.2kPa, Jnr(3.2), kPa <sup>-1</sup> at 64°C, Max	4.5	1.0	0.5	0.5
% Difference in Non-Recoverable Creep Compliance, Jnr(diff) at 64°C, %, Max	75	75**	n/a	n/a

\* Tested in accordance with AASHTO T350.

\*\* Shall be waived if Jnr(3.2) is equal to or less than 0.5

PG76-22 and PG82-22 grade asphalts shall meet the requirements for Indication of Elastic response as defined in Appendix X1 of AASHTO M332. PG70-22 grade asphalts shall have a minimum percent recovery at 3.2 kPa of 29%.”

Subsection 904.01 (pg. 948-950) 5-18-15; revise the 1st paragraph to add the word cement, add sentence to the end of the 2<sup>nd</sup> paragraph, add “cement high-temperature grade properties to the 4<sup>th</sup> paragraph, remove the grades of asphalts and add asphalt cements to the 5<sup>th</sup> paragraph, update Table 904-01-1 to remove “Ring and Ball” and” Elastic Recovery”, add “Non-recoverable creep compliance” requirements to Table 904-01-1, add footnote to Table, add a 6<sup>th</sup> paragraph, remove A. Test Procedures and Table 904.01-2, remove Materials Certification header, remove 8<sup>th</sup> paragraph, and revise the 9<sup>th</sup> paragraph:

“Only obtain asphalt cement for use on Department projects from Certified Asphalt Cement Suppliers that have an approved Quality Control Plan in accordance with the Department’s Standard Operating Procedures.

Asphalt cement shall conform to AASHTO M 320 and Department procedures. Direct Tension testing is not required.

Instead of PG 64-22, the Contractor may use asphalt cement graded to PG 67-22. PG 67-22 shall conform to the requirements of AASHTO M 320 when the applicable tests are conducted at 67 °C and -12 °C, and the dynamic shear of the rolling thin film, pressure aged vessel sample is tested at 26.5 °C.

To modify the asphalt cement high-temperature grade properties, properly blend styrene butadiene (SB), styrene butadiene styrene (SBS), or styrene butadiene rubber (SBR) to a PG 64-22 or PG 67-22 base asphalt.

In addition to the above requirements, asphalt cements shall meet the requirements specified in Table 904.01-1.

**Table 904.01-1: Requirements for Asphalt Cement**

<b>Property*</b>	<b>PG 64-22, PG 67-22</b>	<b>PG 70-22</b>	<b>PG 76-22</b>	<b>PG 82-22</b>
Non-recoverable creep compliance at 3.2kPa, Jnr(3.2), kPa <sup>-1</sup> at 64°C, Max	4.5	1.0	0.5	0.5
% Difference in Non-Recoverable Creep Compliance, Jnr(diff) at 64°C, %, Max	75	75	75	75

\* Tested in accordance with AASHTO T350.

All modified grades shall meet the requirements for Indication of Elastic response as defined in Appendix X1 of AASHTO M332.

Furnish a certification to the Engineer on each project stating that the asphalt cement provided meets the Department’s specification. Ensure that quality control and compliance testing are completed in accordance with the asphalt supplier’s approved quality control plan and Department procedures.

In addition, the asphalt cement supplier shall provide a temperature-viscosity curve for PG 64-22 and PG 67-22 asphalt cements with a recommended mixing temperature range. In order to develop a temperature-viscosity curve, it may be necessary to run the viscosity test at a higher temperature, based on the softening point of the modified asphalt cement.”

Subsection 904.01(pg. 949), 6-27-16; Modify Table 904.01-1:

Table 904.01-1: Requirements for Asphalt Cement

Property	PG64-22			
	PG67-22	PG70-22	PG76-22	PG82-22
Non-recoverable creep compliance at 3.2kPa, Jnr(3.2), kPa <sup>-1</sup> at 64°C, Max	4.5	1.0	0.5	0.5
% Difference in Non-Recoverable Creep Compliance, Jnr(diff) at 64°C, %, Max	75	75	75	n/a

Subsection 904.01 B. (pg. 949) 11-6-17; Asphaltic Cements, B. Materials Certification, add the following as the last sentence of the first paragraph:

“Furnish a certification to the Engineer on each project stating that the asphalt cement provided meets the Department’s specification. Ensure that quality control and compliance testing are completed in accordance with the asphalt supplier’s approved quality control plan and Department procedures. Identify on the certification, the type(s) of modifier used.”

Subsection 904.03 (pg. 951) 11-16-15; Emulsified Asphalts, Add “TTT-3” to 904.03-1 with the following requirements:

Saybolt-Furol Viscosity @ 77 °F, seconds	10-100
Particle Charge	Positive
Sieve Test, %	0.1 Max
Residue by Distillation <sup>(1)</sup>	
Residue, %	50 Min
Demulsibility, %	65 Min
Penetration	40-90

<sup>1</sup>-Distill at 350°F

Subsection 904.03 (pg. 954), 12-2-16; Revise Table 904.03-1(c) to remove TTT-1, TTT-2, and TTT-3:

Table 904.03-1(c): Test Requirements for Emulsified Asphalt

Practices	AASHTO Test Method	CRS-2P	RS-2	RS-1
Saybolt-Furol Viscosity @ 77 °F, seconds	T59	n/a	n/a	20-100
Saybolt-Furol Viscosity @ 122 °F, seconds	T59	100-400	75-400	n/a
Storage Stability Test, 24- h, %	T59	1 Max	1 Max	1 Max
5-day Settlement, %	T59	n/a	n/a	n/a
Particle Charge	T59	Positive	n/a	n/a
Sieve Test, %	T59	0.1 Max	0.1 Max	0.1 Max
Residue by	T59	<i>Evaporation</i>	Distillation	Distillation
Residue, %	T59	65 Min	63 Min	55 Min
Demulsibility, %	T59	40 Min	60 Min	60 Min
Distillate, %	T59	n/a	n/a	n/a
Oil Test, %	T59	n/a	n/a	n/a
Stone Coating	T59	n/a	n/a	n/a
Float Test, seconds	T50	n/a	n/a	n/a
Penetration	T49	75-175	100-200	100-200
Elastic Recovery, % (2)	T301	50 Min	n/a	n/a



Practices	AASHTO Test Method	CRS-2P	RS-2	RS-1
Ductility @ 77 °F, cm	T51	40 Min	40 Min	40 Min
Ductility @ 40 °F, cm	T51	n/a	n/a	n/a
R&B Softening Point, °F	T53	125 Min	n/a	n/a
Original G*/sind @ 82 °C	T315	n/a	n/a	n/a

**Subsection 904.03** (pg.954), 5-18-15; Replace with the following:

**Subsection 904.03, Table 904.03-1(c). Modify** as follows for TTT-1, TTT-2:

**Table 904.03-1(c): Test Requirements for Emulsified Asphalt**

Practices	AASHTO Test Method	CRS-2P	RS-2	RS-1	TTT-1	TTT-2
Saybolt-Furol Viscosity @ 77 °F, seconds	T59	n/a	n/a	20-100	20-100	10-100
Saybolt-Furol Viscosity @ 122 °F, seconds	T59	100-400	75-400	n/a	n/a	n/a
Storage Stability Test, 24- h, %	T59	1 Max	1 Max	1 Max	1 Max	1 Max
5-day Settlement, %	T59	n/a	n/a	n/a	n/a	n/a
Particle Charge	T59	Positive	n/a	n/a	n/a	Positive
Sieve Test, %	T59	0.1 Max	0.1 Max	0.1 Max	0.1 Max	0.1 Max
Residue by	T59	<i>Evaporation</i>	Distillation	Distillation	Distillation	Distillation (1)

Practices	AASHTO Test Method	CRS-2P	RS-2	RS-1	TTT-1	TTT-2
Residue, %	T59	65 Min	63 Min	55 Min	50 Min	50 Min
Demulsibility, %	T59	40 Min	60 Min	60 Min	n/a	n/a
Distillate, %	T59	n/a	n/a	n/a	n/a	n/a
Oil Test, %	T59	n/a	n/a	n/a	n/a	n/a
Stone Coating	T59	n/a	n/a	n/a	n/a	n/a
Float Test, seconds	T50	n/a	n/a	n/a	n/a	n/a
Penetration	T49	75-175	100-200	100-200	0-20	40-90
Elastic Recovery, % <sup>(2)</sup>	T301	50 Min	n/a	n/a	n/a	n/a
Ductility @ 77 °F, cm	T51	40 Min	40 Min	40 Min	n/a	n/a
Ductility @ 40 °F, cm	T51	n/a	n/a	n/a	n/a	n/a
R&B Softening Point, °F	T53	125 Min	n/a	n/a	60-75	n/a
Original G*/sind @ 82 °C	T315	n/a	n/a	n/a	1.0 Min	n/a

<sup>(1)</sup> Distill at 350 °F

<sup>(2)</sup> Straight-sided mold, 20-cm elongation, 5min hold, 25 °C

**Subsection 908.04** (pg. 968), 5-18-15, High Strength Bolts, A. Specifications; Add the following to the first paragraph:

“Unless otherwise shown on the Plans, mechanically galvanize all bolts, nuts and washers in accordance with ASTM B695 Class 50.”

**Subsection 908.04** (pg. 968), 12-2-16, High Strength Bolts, A. Specifications; revise the first paragraph:

“Unless otherwise shown on the Plans, all bolts, nuts and washers shall be coated with acceptable coating in accordance with ASTM F3125 for the respective grade.”

**Subsection 908.04** (pg. 968) 12-2-16; revise A. Specifications, 1.:

“A. Specifications: 1. Bolts. ASTM F3125, Grade 325 and Grade 490 - High Strength Bolts for Structural Joints”

**Subsection 908.04** (pg. 970) 12-2-16; Revise C. Testing, 3. Assemblies, subsection f., update Table 908-04-2:

C. Testing, 3. Assemblies, f. Table 908.04-2 The minimum rotation, from a snug tight condition (10% of the specified proof load), shall be as specified in Table 908.04-2.

**Table 908.04-2: Rotation from Snug Tight Condition**

<b>Bolt Length</b>	<b>Minimum Rotation from Snug</b>
Up to and including 4 diameters	240 degrees (2/3 turn)
Over 4 diameters, but not exceeding 8 diameters	360 degrees (1 turn)
Over 8 diameters	480 degrees (1-1/3 turn)

(Note: These values differ from those shown in ASTM F3125.)

**Subsection 909.02**(pg. 977), 12-2-16; Remove the 4<sup>th</sup> paragraph referencing a tolerance of 5% from B. Steel Posts and Braces.

**Subsection 909.02** (pg. 980-981), 12-2-16; Remove the word minimum from Table 909.02-1:

**Table 909.02-1: Post and Braces**

<b>Application</b>	<b>Material</b>	<b>ASTM Specification</b>	<b>Nominal Diameter (inches)</b>	<b>Outside Diameter (inches)</b>
Line Posts	Galvanized steel pipe	F1083	1.5	1.900
	Aluminum alloy standard (ANSI Schedule 40) pipe	B429, Alloy 6063, Temper T6	1.5	1.900
	Triple coated steel pipe with a	F1043, Group I-C	1.5	1.900

<b>Application</b>	<b>Material</b>	<b>ASTM Specification</b>	<b>Nominal Diameter (inches)</b>	<b>Outside Diameter (inches)</b>
	0.120-inch wall thickness			
End, Corner, and Pull Posts	Galvanized standard steel pipe	F1083	2.0	2.375
	Aluminum alloy standard (ANSI Schedule 40) pipe	B429, Alloy 6063, Temper T6	2.0	2.375
	Triple coated steel pipe with a 0.130-inch wall thickness	F1043, Group I-C	2.0	2.375
End and Corner Braces	Galvanized standard steel pipe	F1083	1.25	1.660
	Aluminum alloy standard (ANSI Schedule 40) pipe	B429, Alloy 6063, Temper T6 (for corner posts: B241)	1.25	1.660
	Triple coated steel pipe with a 0.111-inch wall thickness	F1043, Group I-C	1.25	1.660

**Subsection 909.03** (pg. 983), 12-2-16; Remove the last paragraph of the subsection.

**Subsection 912.05** (pg. 1001), 6-27-16; Add subsection 912.05 – Brick Paving Units:

**“912.05 Brick Paving Units**

Provide brick of the kind and grade specified.

**A. Masonry Brick**

- 1. Sidewalk: ASTM C902, Class SX, Type 1
- 2. Crosswalks and Roadway: ASTM C1272, Type R

**B. Concrete Brick and Truncated Dome Concrete Brick**

Provide brick conforming to ASTM C936

**C. Truncated Dome Brick**

Provide brick conforming to ASTM C902, Class SX, Type 1”

**Subsection 915.02** (pg. 1007), 6-27-16; modify the description of 915.03, remove zinc coated, iron from 915.02 A. update the first paragraph of 915.02 A., Remove subsection B. Aluminum Coated Steel Pipe, Revise C. to become B., revise D to become C, Remove 1<sup>st</sup> and 2<sup>nd</sup> paragraphs of D now C, revise E to become D, update 915.03 to match index title: :

**“SECTION 915 – METALLIC PIPE**

915.01 Ductile Iron or Cast Iron Pipe ..... 1007  
 915.02 Corrugated Metal Pipe Culverts, Pipe Arches, and Underdrains..... 1007  
 915.03 Polymer Pre-coated, Corrugated Steel Pipe, Culverts, and Underdrains.... 1008

**915.01 Ductile Iron or Cast Iron Pipe**

Provide ductile iron pipe conforming to ASTM A716 for the specified diameters and strength classes. Unless otherwise specified, either smooth, corrugated, or ribbed pipe may be furnished. For pipe diameters in excess of 48 inches, conform to ANSI Standard for Cast Iron Pit Cast Pipe, or as otherwise specified in the Contract, for the specified diameter and strength class.

Provide cast iron drain pipe conforming to ASTM A74. Unless otherwise specified, provide ductile iron pressure pipe for water lines or sewer construction conforming to the requirements of ASTM A377 for the diameters and working pressures specified.

**915.02 Corrugated Metal Pipe Culverts, Pipe Arches, and Underdrains**

**A. Corrugated Steel Pipe, Pipe Arches, and Underdrains**

Provide corrugated steel pipe, pipe arches, or underdrains, including special sections, such as elbows and flared ends, that conform to AASHTO M 36, aluminum-coated Type 2 meeting AASHTO M274. Special Sections shall be the same thickness as the pipe, arch, or underdrain to which they are joined. Furnish shop-formed elliptical pipe and shop-strutted pipe only where shown on the Plans.

**B. Corrugated Aluminum Pipe, Pipe Arches, and Underdrains**

When using corrugated aluminum pipe, pipe arches, or underdrains, conform to the applicable requirements of AASHTO M 196. Use special sections, such as elbows and flared end sections

that conform to the applicable requirements of AASHTO M 196 and that are of the same gauge as the conduit to which they are joined.

**C. Structural Plate Corrugated Steel and Aluminum Structures**

Corrugated aluminum alloy structural plate for pipe, pipe arches, and arches shall conform to the requirements of AASHTO M 219.

**D. Bituminous Coating**

When material supplied for any of the items specified above are to be bituminous-coated, ensure that the metal to be coated is free of grease, dirt, and other contaminants. Bituminous coating and paving shall conform to the requirements of AASHTO M 190. Apply the coating in accordance with the manufacturer’s recommended procedures and as directed by the Department.”

**915.03 Polymer Pre-coated, Corrugated Steel Pipe, Culverts and Underdrains**

Provide polymer pre-coated corrugated steel pipe conforming to AASHTO M 245, Grade 250/250, unless otherwise specified.”

**Subsection 916.05 E.** (pg. 1012); 12-2-16, Add sentence to first paragraph:

“Fabricators must be AISC certified as specified in **602.04 A.4.**”

**Subsection 917.02.A.6.** (pg. 1023), 6-27-16; Revise the following:

“**6. Anchor Bolts.** Use anchor rods of high strength steel meeting the requirements of ASTM F 1554, Grade to be determined by design. Fit each anchor bolt with a hex nut and lock-washer.”

**Subsection 918.04** (pg. 1036), 12-2-16; add as a 2<sup>nd</sup> paragraph:

“For small quantities less than 100 units of seeding or sod, bagged pelletized or agricultural limestone meeting the Department of Agriculture Tennessee Liming Materials Act may be utilized.”

**Subsection 921** (pg. 1049), 11-6-17, Section 921 – Miscellaneous Materials, add Ground Tire Rubber to the Index:

“921.17 Ground Tire Rubber .....1060”

**Subsection 921.01** (pg. 1049), 5-18-15, Water; Replace subsection with the following:

“For mixing concrete, use water that is reasonably clean and free of oil, salt, acid, alkali, sugar, vegetable matter, and other substances injurious to the finished product. Water provided by a municipal utility may be used without testing.

All other water shall have quality results submitted in accordance with the frequency listed in Table 921.01-01. All water quality results shall adhere to Table 921.01-2.

**Table 921.01-1 Testing Frequency for Mixing Water**

Water Source	Testing Frequency <sup>(1)</sup>
Municipal	NA
Non-Municipal	Every 3 months; tested annually after 4

	consecutive passing tests
--	---------------------------

(1) The frequency may vary at the discretion of the Department.

**Table 921.01-2 Quality Requirements for Mixing Water**

Maximum Concentration in Mixing Water	Limits	ASTM Test Method <sup>(1)</sup>
Chloride Ion Content, ppm	500	C114
Alkalies as (NaO2 + 0.658 K2O), ppm	600	C114
Sulfates as SO4, ppm	3000	C114
Total Solids by mass, ppm	50000	C1603
pH	4.5-8.5	(2)
Resistivity, Minimum, kohm-cm	0.500	D1125
Soluble Carbon Dioxide, ppm	600	D513
Calcium and Magnesium, ppm	400	D511
Iron, ppm	20	(2)
Phosphate, ppm	100	D4327

(1) Other methods (EPA or those used by water testing companies) are generally acceptable.

(2) No ASTM method available.

**Subsection 921.06** (pg.1051) 11-16-15; B. Bituminous Additives - 1. Anti-Stripping Additive, replace the ASTM C977 reference with AASHTO M 303.

“Use hydrated lime conforming to AASHTO M 303 or other heat-stable asphalt anti-stripping additive containing no ingredient harmful to the bituminous material or the workmen and that does not appreciably alter the specified characteristics of the bituminous material when added in the recommended proportions.”

**Subsection 921.06** B. Bituminous Additives (pg.1052) 10-10-16; revise the 3<sup>rd</sup> paragraph to the following:

“When using an anti-stripping additive other than hydrated lime, use a dosage rate of 0.3%, unless either gravel is used as a coarse aggregate or test results indicate moisture susceptibility, in which case mix at a dosage rate of 0.5%.

**Subsection 921.06 B. 2.** (pg. 1052) 11-6-17; B. Bituminous Additives, 2. Silicone Additives, Remove description and add the following sentence:

~~“2. Silicone Additives. Mix silicone additives at the rate of 1 pint of silicone per 4 gallons of diesel fuel. The Contractor may use a ½ pint of this mixture per 1,000 gallons of asphalt. The amount of silicone added to asphalt cement shall not exceed 2 oz. of silicone per 5500 gallons asphalt cement.”~~

**Subsection 921.17** (pg. 1060) 11-6-17; Ground Tire Rubber, add the following subsection:

**“921.17 Ground Tire Rubber**

Provide Class 30-1 Ground Tire Rubber (GTR) as defined by ASTM D5630 except for as noted in table 921.17-1. The material shall also be certified to meet the requirements of Table 921.17-01. Include certification of the GTR with the bill of lading for the modified asphalt cement.

**Table 921.17-1: Requirements for Ground Tire Rubber**

<u>Property</u>	<u>Specification</u>
<u>Specific Gravity</u>	<u>1.15 +/- 0.05</u>
<u>Moisture Content</u>	<u>0.75% Max</u>
<u>Ferrous Metal Content</u>	<u>0.01% Max</u>
<u>Fiber Content</u>	<u>0.5% Max</u>
<u>Ash (ASTM E1131)</u>	<u>10% Max</u>



**APPENDIX B**  
***SPECIAL PROVISIONS***

TITLE	SP#
EMPLOYING AND CONTRACTING WITH ILLEGAL IMMIGRANTS	102I
Specifications for Road and Bridge Construction	102 LC
SPECIAL PROVISIONS RELATIVE TO PROTECTION OF RAILROAD PROPERTY RAILROAD FLAGGING AND INSURANCE REQUIREMENTS	105 C
BUY AMERICAN REQUIREMENTS	106A
Water Quality and Storm Water Permits	107FP
PROJEET COMPLETION AND LIQUIDATED DAMAGES	108B
PAYMENT ADJUSTMENT FOR FUEL	109A
PRICE ADJUSTMENT FOR BITUMINOUS MATERIAL	109B
Section 411-Asphalt Concrete Surface (Hot Mix)	411 B
RETAINING WALLS	624
Traffic Queue Protection	712 PTQ
EQUAL EMPLOYMENT OPPORTUNITY	1230
STANDARD FEDERAL EQUAL EMPLOYMENT OPPORTUNITY CONSTRUCTION CONTRACT SPECIFICATIONS (EXECUTIVE ORDER 11246)	1231
NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)	1232
TRAINING PROGRAM REQUIREMENTS	1240
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION	1246
DBE CONTRACT GOALS	1247
REQUIRED CONTRACT PROVISIONS (FEDERAL-AID CONSTRUCTION CONTRACTS)	FHWA 1273
TENNESSEE DEPARTMENT OF TRANSPORTATION MINIMUM WAGE SCALES FOR FEDERAL-AID	1320

B

Design-Build Project

*SR 396, Saturn Parkway Extension,  
and improvement on State Route 247  
Maury County*

STATE

OF

TENNESSEE

January 1, 2015

Rev. 12-22-14

Rev. 2-13-17

Rev. 6-26-17

SPECIAL PROVISION

REGARDING

WATER QUALITY AND STORM WATER PERMITS

Scope

The conditions of this Special Provision apply to all construction on this project pursuant to the following:

1. Section 404 of the Federal Clean Water Act (33 U.S.C. §1344), and all implementing regulations, including without limitation regulations of the U.S. Army Corps of Engineers governing permits for discharges of dredged or fill material into waters of the United States in 33 CFR Part 323; and
2. The Tennessee Water Quality Control Act (T.C.A. §69-3-101, et seq.) and all implementing regulations, including without limitation the Rules of the Tennessee Department of Environment and Conservation governing NPDES permits in Chapter 1200-4-10, and Aquatic Resource Alteration permits in Chapter 1200-4-7; and
3. Section 26a of the TVA Act of 1933 as amended (49 Stat. 1079, 16 U. S. C. sec. 831y1.) and all implementing regulations, including without limitation the regulations of the Tennessee Valley Authority governing construction in the Tennessee River System in 18 C.F.R., Part 1304; and
4. The Tennessee Wildlife Resources Agency Reelfoot Lake Watershed Management permit program (T.C.A. section 70-5-1.), and all implementing regulations, including without limitation regulations authorizing any activity, practice, or project which has or is likely to have the effect of diverting surface or subsurface water from the Lake or have the effect of draining or otherwise removing water from Reelfoot Lake; and
5. Coast Guard Bridge Permit (USCG) (Section 9 of the Rivers and Harbors Appropriation Act of 1899) and all implementing regulations, including but not without limitation for projects which impact streams deemed navigable by the U.S. Coast Guard.

Responsibility

It is understood and agreed that the Contractor assumes all responsibilities of the permittee as indicated in the permit that relates to protection of the "waters of the United States" and/or "waters of the State of Tennessee."

It is also understood and agreed that the Contractor shall be responsible for obtaining any additional permits required by the Contractor's method of construction, including without

limitation haul roads, temporary channels or temporary ditches, or off-site waste and/or borrow areas.

It is also understood that the Contractor shall be responsible for implementing the provisions of the Water Quality (including, but not limited to, TDEC ARAP, USACE 404, TVA Section 26a, Coast Guard, TWRA) and Storm Water [including, but not limited to, National Pollution Discharge Elimination System (NPDES), Statewide Stormwater Management Plan (SSWMP)] Permits and requirements that pertain to construction activities.

The Contractor by signing this contract is indicating that the Contractor has reviewed a copy of the permit provisions, including NPDES Permit provisions at <http://www.tdot.state.tn.us/construction/permits/npdes.pdf>, the site specific SWPPP, the contract plans, Standard Specifications and contract Special Provisions and finds the permit requirements and erosion prevention and sediment control (EPSC) procedures to be reasonable, workable, and binding.

It is also understood that the Contractor shall not be released from the project site responsibilities under the NPDES permit provisions until the Notice of Termination (NOT) is submitted to TDEC by the TDOT Regional Construction Supervisor. The NOT is a certification that the construction project site is permanently stabilized and that all construction related discharges have ceased. This means that the use of EPSC measures to alleviate concerns of surface erosion and transport of sediment to surface water conveyances or to waters of the state is no longer necessary. Furthermore, it means that permanent controls, hard surfaces and/or vegetation, employed at the site are deemed adequate to prevent erosion and sediment transport and no other potential sources of construction-related pollution are on the project.

It is also understood that the Contractor shall not be released from any warranty provided for EPSC plantings, including sod and trees. If the entire project is complete as outlined in **Subsection 105.15** of the **Standard Specifications**, the Contractor shall be required to supply a performance bond as outlined in **Subsection 802.15** of the **Standard Specifications** to cover any warranty for EPSC plantings.

#### NPDES Permit Required Action

The Contractor (or their representative) shall accompany the EPSC inspector (TDOT personnel or TDOT hired consultant) on all EPSC inspections of the entire construction project including permitted locations and potentially impacted streams as well as attend all QA/QC Project Assessments.

EPSC Inspections shall be conducted as required in the most current TN Construction General Permit.

EPSC inspections shall be performed on the schedule established in the TN Construction General Permit until the site is permanently stabilized to determine if the permit requirements are being met. Where sites or portion(s) of construction sites have been temporarily stabilized, or runoff is unlikely due to winter conditions (e.g. site covered with snow or ice), such inspection only has to be conducted once per month until thawing or precipitation results in runoff or construction activity resumes. Written notification of the intent to change the inspection frequency and the justification for such request must be submitted to the TDOT Project Supervisor and the TDEC Central Office before proceeding.

An individual representing the Contractor, who holds a current TDEC "*Fundamentals of Erosion Prevention and Sediment Control Level I*" certification shall accompany the EPSC inspector on all required EPSC inspections. The Contractors project supervisor(s) shall also hold

a current TDEC “*Fundamentals of Erosion Prevention and Sediment Control Level I*” certification. Proof of required personnel training for the individual(s) shall be provided to the TDOT Project Supervisor prior to beginning of construction.

The TDOT EPSC inspector shall document all deficiencies on the required TDOT EPSC Inspection Report form (provided in the SWPPP). The Contractor (or their representative) shall sign the TDOT EPSC Inspection Report form and any supporting documentation indicating that he is in agreement with the report, recommendations and repair schedule as stated within the documentation.

Additionally, the Contractor shall make necessary maintenance and repairs relative to deficiencies in these permit conditions or requirements within twenty-four (24) hours after an inspection identifies the maintenance or repair need, and/or when directed to do so by the TDOT Project Supervisor, unless conditions make a particular activity impracticable. Any such conditions that make immediate repairs impracticable shall be documented and provided to the TDOT Project Supervisor, via the inspection report, and be accompanied by an expected repair schedule based on forecasted weather conditions.

The Contractor further agrees that he will execute two (2) copies of the Notice of Intent (NOI) form of the permit (provided by the Department), indicating his acceptance of the stipulations contained therein. The Contractor further agrees, that should he fail to execute said copies and return them to the TDOT Construction Division within ten (10) calendar days after submittal of the contract proposal to him, that the Department may at its discretion cancel the award with the Contractor forfeiting his bid bond.

Further, the Contractor agrees to review the site specific Stormwater Pollution Prevention Plan (SWPPP) that will be made available prior to or at the pre-construction conference, for any additional EPSC requirements. The Contractor shall sign and submit two copies of the SWPPP signature page (provided by the Department within the site specific SWPPP). The Contractor may submit for review and approval changes/revisions to the SWPPP to better prevent erosion and sediment transport at any time after contract execution. Rejection of any submittals does not relieve the contractor of any liability for appropriate Best Management Practices (BMPs).

If at any time during this contract, the requirements for the Water Quality Permits and/or the Storm Water Permits for Construction Related Activities are changed/revised/updated, the Contractor shall be notified in writing by the Department of such requirements. The Contractor shall comply with the new requirements within thirty (30) days of the Department notification.

If at any time the Contractor becomes aware that sedimentation is occurring or has occurred in streams impacted by the specified project, the Contractor shall immediately notify the TDOT Project Supervisor to evaluate the EPSC measures employed. A determination of the cause for sedimentation will be made by the Department. The Contractor shall immediately repair or replace defective EPSC measures, and install, as applicable, additional or other EPSC measures with the goal of eliminating future sedimentation. Once a remediation plan is provided by the Department, the Contractor shall, within twenty-four (24) hours after notification, begin the remediation as required. Based on the cause of sedimentation, the Department will determine if the cost of remediation will be performed at the Contractor’s expense.

**Failure to Comply**

In the event a Notice of Violation (NOV) or Order pursuant to the Tennessee Water Quality Control Act or the Federal Clean Water Act is issued on this project, any and all fines will be the

sole responsibility of the Contractor as outlined in **Subsection 107.01** of the **Standard Specifications for Road and Bridge Construction**.

Failure of the Contractor to comply with this Special Provision or take immediate corrective actions required within twenty-four (24) hours (unless documented conditions make a particular maintenance or repair activity impracticable immediately) shall be reason for the TDOT Project Supervisor to suspend all other work on the Project, except erosion prevention and sediment control (EPSC) and traffic control, applying non-refundable deductions of monies from the Contract per calendar day from monies due to the Contractor for any EPSC work on the Project. This deduction can be made for each location, as determined by the TDOT Project Supervisor, for each calendar day that the deficiency is allowed to remain and charged as item description "*Failure to Comply with Permit Deduction*". A deduction shall be made from monies due the Contractor, not as a penalty, but as liquidated damages, as indicated in **Subsection 108.09** of the **Standard Specifications for Road and Bridge Construction January 1, 2015**, as amended.

If the Contractor does not make necessary corrections/adjustments in a timely manner as required above, the Department will implement the provisions of **Subsection 209.07** and **Subsection 109.08** of the **Standard Specifications for Road and Bridge Construction** that provides for the Department making repairs and recovering the costs thereof from the Contractor.

The Department will not participate in any payment or reimbursement for fines and will not authorize time extensions due to delays in project progress for work stoppage, to remedy the violations stated within the NOV, required by the TDOT Project Supervisor as stated in **Subsection 105.01** of the **Standard Specifications for Road and Bridge Construction**.

#### **Spill Prevention, Control, and Countermeasure**

To help prevent the discharge of oil into navigable waters, the U.S. Environmental Protection Agency (EPA) developed the Spill Prevention, Control, and Countermeasure (SPCC) Program. The SPCC Program is under the authority of Section 311 (j)(1)(C) of the Federal Water Pollution Control Act (Clean Water Act) in 1974. The rule may be found at Title 40, Code of Federal Regulations (CFR), Part 112. Additional information regarding the preparation and requirements of a SPCC Plan can be found at: <http://www.epa.gov/oem/content/spcc/>.

If applicable based upon the total aggregate capacity of aboveground oil storage, the contractor shall develop a site specific SPCC Plan per EPA requirements. This plan shall be provided to the Project Supervisor as part of the required submittals during the project Pre-Construction Meeting or at which time the conditions on the project site meet the applicable criteria. The contractor shall be responsible for obtaining any other necessary local, state, and federal permits as applicable. The SPCC Plan and/or permits shall be kept on-site.

The contractor shall be responsible complying with all aspects of the site specific SPCC Plan including but not limited to: performing any required inspections as directed by the SPCC Plan as well as implementing material and spill management practices per the project's Stormwater Pollution Prevention Plan (SWPPP). In the event, where a release containing a hazardous substance in an amount equal to, or in excess of a reportable quantity established under either 40 CFR 117 or 40 CFR 302 occurs during a 24-hour period, the contractor shall immediately notify the Project Supervisor.

**DESIGN-BUILD  
RFP CONTRACT BOOK 3  
PROJECT SPECIFIC INFORMATION**

**TENNESSEE DEPARTMENT OF TRANSPORTATION**

**State Route 396, Saturn Parkway Extension,**

**Maury County- TENNESSEE**

**CONTRACT NUMBER: DB1601**



**August 31, 2017**

**Addendum#2 October 10, 2017**

**Addendum#4 October 19, 2017**

**Addendum#6 November 27, 2017**

**(Project Specific Information).** The commitment sheets and the study area is referenced in appendix C. If the Design Builder's design footprint extends beyond the study area, they will be responsible for the additional environmental technical studies and to provide plans for re-evaluation of the NEPA document. No additional time will be allotted to the project schedule for TDOT preparation of the NEPA document re-evaluation and FHWA approval.

- **Lighting:** Intersection and partial interchange lighting, in accordance with TDOT's Traffic Design Manual, is required at the GM Plant intersection and ramp is included in this project
- Project 2 (PIN 121394.00, Project Shotgun), Site 3:  
The road name is incorrectly identified as Stephen P. Hirsch Parkway. The correct name of the road is Stephen P. Yokich Parkway. Any reference to Stephen P. Hirsch Parkway shall refer to Stephen P. Yokich Parkway.

There is an existing signal pole in the northwest quadrant of the intersection of US-31 and Stephen P. Yokich Parkway. Based on the current design shown in the Right of Way plans, this signal pole will required to be relocated. The reuse of the existing signal equipment (i.e. traffic signal pole, span wire, signal heads, etc) is acceptable if the existing equipment meet the current structural and TDOT Traffic Design Manual

**For Project Nos. 1, 2, and 3:**

- The Design Builder shall ensure that minimum clearing and grubbing is performed beyond the toe of slopes, preserving as much vegetation as possible.
- The Design Builder shall identify the need for any special roadway design details (i.e. any special drainage structures, rock embankment, rock plating, special guardrail, retaining walls, concrete barrier designs, etc.) and shall provide special design drawings.
- All Design Documents and Design Reviews shall be provided by the Design Builder and performed in accordance with the Design Review schedule established in the Critical Path Method (CPM) Schedule, and in accordance with contract requirements.
- The Design Builder shall ensure that all applicable "General and Special Notes" found in Section VI of the current edition of the State of Tennessee Department of Transportation Design Division Roadway Design Guidelines are adhered to during construction.

## APPENDIX C

### *REFERENCE INFORMATION*

- [Conceptual layouts with typical](#)
- [Survey data file in Micorstation](#)
- [Existing Structure details](#)
- [Green sheets in the Environmental Document](#)
- [DB Geotechnical documents](#)
- [Environmental Boundaries](#)
- [CSX public projects manual](#)
- [Conceptual Signs recommendations](#)

<http://www.tn.gov/tdot/article/transportation-construction-division-design-build-db1601>



<b>SIGN ID</b>	<b>SIGN DESCRIPTION</b>
Sign #1	Beechcroft Road Right • Saturn Pkwy. East, I-65 & GM Visitors & Truck Entrance - Left
Sign #2	Beechcroft Road, Hwy. 31 N & Spring Hill next Left
Sign #3	Beechcroft Road, Hwy. 31 N & Spring Hill next Right
Sign #4	GM Plant Traffic, GM Visitors & Truck Entrance next Right
Sign #5	Saturn Pkwy East, I-65 & Hwy. 31 Right • Saturn Pkwy. West (Beechcroft Road) & Spring Hill Left
Sign #6	GM Plant Traffic, GM Visitors & Truck Entrance next Left
Sign #7	← GM Plant Traffic, GM Visitors & Truck Entrance →
Sign #8	GM Plant Traffic Keep Left, GM Visitors & Truck Entrance Straight
Sign #9	← Saturn Pkwy. West (Beechcroft Road) • Saturn Pkwy East, I-65 & Hwy. 31 →
Sign #10	GM Visitors Next Right • GM Truck Entrance Straight Ahead • GM Plant Traffic Next Left
Sign #11	GM Visitors Straight Ahead • Saturn Pkwy East, I-65 & Hwy. 31 Right at Intersection then keep Right • Saturn Pkwy West (Beechcroft Road) Right at Intersection then keep Left
Sign #12	GM Plant Traffic Straight Ahead • Saturn Pkwy East, I-65 & Hwy. 31 Left at Intersection then keep Right • Saturn Pkwy West (Beechcroft Road) Left at Intersection and then keep left
Sign #13	Saturn Pkwy East, I-65 & Hwy. 31 Straight at Intersection then keep Right • Saturn Pkwy West (Beechcroft Road) Straight at Intersection and then keep left
Sign #14	GM Plant Traffic Next Right • Saturn Pkwy East, I-65 & Hwy. 31 straight at Intersection
Sign #15	GM Plant Traffic Keep Left • Saturn Pkwy. West (Beechcroft Road) Straight
Sign #16	Saturn Pkwy East, I-65 & Hwy. 31 Keep Straight • Saturn Pkwy. West (Beechcroft Road) Next Left

