




REV. 4-11-14: CORRECTED CUT SECTION LABELS.
 REV. 10-10-16: UPDATED LENGTH OF TYPE 38 TERMINAL.
 REV. 06-28-19: UPDATED TO MASH GUARDRAIL ITEM NUMBERS. REDREW SHEET.




BARRIER TREATMENT DETAILS




SECTION D-D




SECTION C-C



SECTION B-B




SECTION A-A



SECTION E-E

EARTHEN BERM DIMENSIONS AND QUANTITIES			
MEDIAN WIDTH	W	ITEM NO 203-01 CY	FILL SLOPE S
36'	4	23	1.5:1
40'	8	33	1.5:1
48'	12	49	2:1
60'	24	83	2:1
64'	28	96	2:1

EARTHEN BERM DETAILS



SECTION F-F

GUARDRAIL DIMENSIONS AND QUANTITIES						
DESIGN SPEED MPH	DIMENSIONS			ESTIMATED QUANTITIES (D)		
	TAPER RATE	X	Y	705-06.25	705-06.01	705-06.20
70	15:1	200'-0"	16'-8"	EACH	225'-0"	1 EACH
60	14:1	137'-6"	13'-5"	EACH	162'-6"	1 EACH
≤55	12:1	100'-0"	12'-6"	EACH	125'-0"	1 EACH

- GENERAL NOTES**
- (A) THE CONTRACTOR IS TO ELIMINATE THE 1 FOOT FLARE SHOWN ON GUARDRAIL STANDARD DRAWINGS FOR TANGENTIAL GUARDRAIL TERMINAL ANCHORS (FLARED INSTALLATIONS ONLY).
 - (B) ONLY ONE APPROACH SHOWN; OTHER APPROACH IDENTICAL.
 - (C) THE DIMENSIONS SHOWN IN THIS TABLE ARE TO BE USED IN ALL TANGENT OR NEARLY TANGENT SITUATIONS WITH DESIGN SPEEDS 70 MPH OR BELOW. WHEN THE DESIGN SPEED EXCEEDS 70 MPH OR OTHER GEOMETRIC FEATURES SUCH AS CURVATURE, SKEWED BRIDGES, OR ADDITIONAL HAZARDS ARE PRESENT, THE DESIGNER SHALL USE STANDARD DRAWING S-PL-1.
 - (D) QUANTITIES SHOWN ARE FOR ONE APPROACH.
 - (E) BASED ON 6' SHOULDER; FOR OTHER SHOULDER WIDTHS ADJUST WIDTH OF BERM AS NECESSARY. PLACEMENT OF GUARDRAIL IS NOT AFFECTED.

MINOR REVISION -- FHWA APPROVAL NOT REQUIRED

STATE OF TENNESSEE
 STANDARD DRAWING
 DEPARTMENT OF TRANSPORTATION

SAFETY PLAN
 FOR BRIDGE
 ENDS IN MEDIANS

10/23/2019 9:58:09 AM
 C:\Users\jj00547\Desktop\ISPL5-20190628.DGN