



ADDENDUM NO. 1

PROJECT: Beech Street Resurfacing (TDOT PIN 126924.00)

ADDENDUM NO.: 1

ADDENDUM DATE: August 29, 2024

OWNER: City of LaFollette
207 South Tennessee Avenue
LaFollette, TN 37766

ENGINEER: CCI (Cannon & Cannon, Inc.)
10025 Investment Drive, Suite 120
Knoxville, TN 37932

ALL BIDS SHALL CONFORM TO THIS ADDENDUM:

This addendum forms a part of the Contract referenced above. The following items covering changes in the bidding requirements shall apply to and become a part of the requirements thereof.

Receipt of this Addendum shall be acknowledged by inserting its number and date in the space on the Bid Form. Failure to do so may result in disqualification of the Bidder.

This Addendum consists of two (2) pages and the following attachments.

- Pre-Bid Sign-in Sheet – one (1) page
- Revised Plan Sheet 2
- Revised Bid Form

ITEM NO. 1 GENERAL COMMENTS FROM PRE-BID MEETING / QUESTIONS

A Mandatory Pre-Bid Meeting was held on Tuesday, August 20, 2024, at the City of LaFollette offices. The sign in sheet from the meeting is attached. The following questions / answers and comments are a result of that meeting and subsequent question allotment period:

Q: Will water valves and associated risers be provided during construction by utility to be installed by contractor?

A: Yes



ADDENDUM NO. 1

ITEM NO. 2 ADDITIONS / ELIMINATIONS

The following items have been removed from the proposed project.

1. Plan Sheet 2 - Removal of curb ramp installation at the intersections of S. Tennessee Avenue and East Avenue. Overall quantity for Item 701-02.01 CONCRETE CURB RAMP (RETROFIT), S.F. has been reduced accordingly.

END ADDENDUM NO. 1

PIN 129624.00 - La Follette Beech St. Resurfacing

Pre-Bid Sign-In 8/20/24 @ 2pm

<u>NAME</u>	<u>COMPANY</u>	<u>PHONE</u>	<u>EMAIL</u>
1. Wesley Stokes	Cannon + Cannon, Inc	(865) 670-8555	wstokes@cci-corp.com
2. Jonah Cole	Adams Contracting	859-771-5895	Jonah@adamscontractingky.com
3. Kelly McARTT	Rogers Group	865-368-8104	Kelly.mccarthe@rogersgroupinc.com
4. Cliff Jenning		423-201-3039	Mayor
5. Johnny Byrge		423-494-9570	Rec. Director
6. Stan Foust		423-912-1934	City Administrator
7. Casey Boshears		423-437-1008	Public Works
8. Paige Conlin		865 659 0282	Paige@paigeconstruction.net
9. Wayne Kitta		865-617-4603	City Council
10. Terry Sweet		423-563-0715	tsweet@lafollette.net

FOOT NOTES	ITEM NO.	DESCRIPTION	UNIT	QTY.
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	8
(1)(9)	411-01.10	ACS MIX (PG64-22) GRADING D	TON	1941
(2)	415-01.01	COLD PLANING BITUMINOUS PAVEMENT	TON	2520
	611-01.20	ADJUSTMENT OF EXISTING MAHOLE	EACH	19
(3)	701-02.01	CONCRETE CURB RAMP (RETROFIT)	S.F.	1823
(4)	712-01	TRAFFIC CONTROL	LS	1
	712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	50
(5)	712-06	SIGNS (CONSTRUCTION)	S.F.	216
(6)(10)	716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	L.F.	30
(7)(10)	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	170
(8)	716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	3.3
	717-01	MOBILIZATION	LS	1

FOOTNOTES:

- (1) BUSINESS ENTRANCES AND PRIVATE DRIVES TO BE TIED-IN AS NEEDED OR AS DIRECTED BY CEI INSPECTOR
- (2) REMOVAL AND DISPOSAL OF ASPHALT IN EXISTING GUTTER PAN SHALL NOT BE MEASURED OR PAID SEPARATELY. COST TO BE INCLUDED IN ITEM 415-01.01, COLD PLANING BITUMINOUS PAVEMENT, TON.
- (3) ITEM QUANTITY ACCOUNTS FOR CURB RAMPS TO BE LOCATED AS DIRECTED IN PLANS SEE "CURB RAMP DETAILS". ALL DETECTABLE WARNING SURFACES INSTALLED SHALL BE FEDERAL YELLOW IN ACCORDANCE WITH TDOT STANDARDS
- (4) TRAFFIC CONTROL FOR PAVING OPERATION TO BE MOBILE BY USING FLAGGERS.
- (5) QUANTITY INCLUDES ALL TEMPORARY TRAFFIC CONTROL SIGNS
- (6) INSTALL CROSSWALK AT INTERSECTION OF BEECH AT 9TH
- (7) INSTALL NEW STOP LINES AT LOCATIONS SPECIFIED BY CEI INSPECTOR
- (8) TO BE USED ON EXISTING SURFACE AS NEEDED.
- (9) PROJECT IS TO BE SWEEPED CLEAN AFTER ALL PAVEMENT IS COMPLETE TO REMOVE "CRUMBS". COST IS TO BE INCLUDED IN OTHER ITEMS BID.
- (10) CONTRACTOR MAY ELECT TO SUBSTITUTE PREFORMED PLASTIC FOR THERMOPLASTIC. PREFORMED PLASTIC SHALL BE PAID FOR AT THE SAME UNIT PRICE AS BID FOR THERMOPLASTIC.

TRAFFIC CONTROL SIGN DETAILS				
NO.	DESCRIPTION	CODE	SIZE	QUANTITY (SF)
17	ROAD WORK	W20-1	36"X36"	153
2	ONE LANE ROAD	W20-4	36"X36"	18
2	FLAGGER	W20-7A	36"X36"	18
2	END ROAD WORK	G20-2	36"X18"	9
2	UNEVEN LANES	W8-11	36"X36"	18
TOTAL				216

CURB RAMP TABULATION

ROADWAY		LOCATION				SIGNALIZED YES / NO	STANDARD DRAWING NO.	CONC. CURB RAMP (RETROFIT) ITEM NO. 701-02.01 S.F.	REMARKS		
MAINLINE	INTERSECTING	STATION or LOG MILE (L.M.)	LEFT	MEDIAN	RIGHT					QUADRANT N. S. E. W.	
BEECH STREET	S. 17TH STREET	6+20	X			X		NO	MM-CR-5	105.0	PARALLEL CURB RAMPS FOR SINGLE CROSSING
BEECH STREET	S. 17TH STREET	6+60	X			X	X	NO	MM-CR-5	105.0	PARALLEL CURB RAMPS FOR SINGLE CROSSING
BEECH STREET	S. 13TH STREET	15+30	X			X	X	NO	MM-CR-8	70.0	DETAIL B OR D
BEECH STREET	S. 13TH STREET	15+75	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. 11TH STREET	21+00	X			X	X	NO	MM-CR-8	70.0	DETAIL B OR D
BEECH STREET	S. 11TH STREET	21+35	X			X	X	NO	MM-CR-8	70.0	DETAIL B OR D
BEECH STREET	S. 9TH STREET	24+50	X			X	X	NO	MM-CR-7	58.0	PARALLEL CURB RAMP
BEECH STREET	S. 9TH STREET	24+65	X			X	X	NO	MM-CR-7	58.0	PARALLEL CURB RAMP
BEECH STREET	S. 9TH STREET	24+80	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. 5TH STREET	35+00	X			X	X	NO	MM-CR-8	70.0	DETAIL B OR D
BEECH STREET	S. 5TH STREET	36+00	X			X	X	NO	MM-CR-5	105.0	PARALLEL CURB RAMPS FOR SINGLE CROSSING
BEECH STREET	FIRE DEPT. PARKING LOT	45+00	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	CITY ADMIN PARKING LOT	46+90	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. 4TH STREET	59+93	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. 4TH STREET	60+40	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. 6TH STREET	64+25	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. 6TH STREET	64+55	X			X	X	NO	MM-CR-8	70.0	DETAIL A OR C
BEECH STREET	S. CUMBERLAND AVENUE	73+56			X	X	X	NO	MM-CR-5	105.0	PARALLEL CURB RAMPS FOR SINGLE CROSSING
BEECH STREET	S. CUMBERLAND AVENUE	73+65	X			X	X	NO	MM-CR-7	58.0	PARALLEL CURB RAMP
BEECH STREET	S. CUMBERLAND AVENUE	74+00	X			X	X	NO	MM-CR-5	109.0	PERPENDICULAR CURB RAMPS FOR SINGLE CROSSING
BEECH STREET	S. 12TH STREET	78+22	X			X	X	NO	MM-CR-7	105.0	LOWERED CORNER CURB RAMP WITH BI-DIRECTIONAL SIDEWALK
BEECH STREET	S. 12TH STREET	78+57			X	X	X	NO	MM-CR-8	70.0	DETAIL B OR D
BEECH STREET	S. 14TH STREET	82+25			X	X	X	NO	MM-CR-7	105.0	LOWERED CORNER CURB RAMP WITH BI-DIRECTIONAL SIDEWALK
TOTAL										1823	

NOTE: CURB RAMPS AT S. TENNESSEE AVENUE & S. INDIANA AVENUE ARE NOT INCLUDED IN THIS PROJECT AND WILL BE IMPROVED AS PART OF SEPARATE PROJECTS

REVISIONS		DATE
 CANNON & CANNON INC CONSULTING ENGINEERS · FIELD SURVEYORS TEL 865.670.8555 8550 Kingston Pike WWW.CANNON-CANNON.COM Knoxville, TN 37919		
CLIENT:		
CITY OF LAFOLLETTE		
PROJECT:		
BEECH STREET RESURFACING		
ESTIMATED QUANTITIES		
CCI PROJECT NO.		01324-0005
DATE		05-03-2024
P.M.		WAS
DRAWN		WAS
C.C.		WAS
 WESLEY A. STOKES REGISTERED ENGINEER No. 21122 STATE OF TENNESSEE		05-02-2024 2

BID FORM

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL PRICE
403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	8		
411-01.10	ACS MIX (PG64-22) GRADING D	TON	1941		
415-01.01	COLD PLANING BITUMINOUS PAVEMENT	TON	2520		
611-01.20	ADJUSTMENT OF EXISTING MANHOLE	EACH	19		
701-02.01	CONCRETE CURB RAMP (RETROFIT)	S.F.	1823		
712-01	TRAFFIC CONTROL	LS	1		
712-04.01	FLEXIBLE DRUMS (CHANNELIZING)	EACH	50		
712-06	SIGNS (CONSTRUCTION)	S.F.	216		
716-02.03	PLASTIC PAVEMENT MARKING (CROSS-WALK)	L.F.	30		
716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	L.F.	170		
716-05.01	PAINTED PAVEMENT MARKING (4" LINE)	L.M.	3.3		
717-01	MOBILIZATION	LS	1		

TOTAL BID \$ _____

TOTAL BID IN WORDS _____

ADDENDUM # _____ **DATE** _____

ADDENDUM # _____ **DATE** _____

ADDENDUM # _____ **DATE** _____

ADDENDUM # _____ **DATE** _____